

BLM LIBRARY



88020308



PARAHO OIL SHALE DEMONSTRATION

COMMERCIAL
EVALUATION

FINAL REPORT
VOLUME 5-A.

#15703728

Paraho

10188020308

TP
699

P373

1976

V.5a

BLM Library
D-553A, Building 50
Denver Federal Center
P. O. Box 25047
Denver, CO 80225-0047

Under a lease approved in May, 1972, Paraho Corporation, in cooperation with the federal government, to conduct research, economic and environmental feasibility and desirability of the Paraho processes and hardware for retorting oil shale. This Final Report to participants of the Paraho Oil Shale Demonstration is a six-volume document summarizing the research and development operations, the engineering design and cost estimating, and the commercial evaluation studies carried out from late-1972 to mid-1976.

PARAHO FINAL REPORT

COMMERCIAL EVALUATION

VOLUME 5-A

THIS VOLUME 5-A IS CONSIDERED CONFIDENTIAL UNDER THE

TERMS OF THE PARTIAL COOPERATION AGREEMENTS WITH PARAHO

CORPORATION AND DEVELOPMENT ENGINEERING, INC. MORE-

OVER, BECAUSE OF THE COMMITMENT TO THE GOVERNMENT NOT TO

PUBLISH INFORMATION RELATING TO THE CONFIDENTIALITY OF THE

BY STRICTLY CONTROLLING THE DISTRIBUTION AND

AFTER THIS MATERIAL HAS BEEN REVIEWED BY THE GOVERNMENT

OR PARAHO.

PREPARED

by

THE CLEVELAND-CLIFFS IRON COMPANY
DEVELOPMENT ENGINEERING, INC.
ARTHUR G. MCKEE & COMPANY
SOHIO PETROLEUM COMPANY

The field operations were conducted at the Naval Point Oil Shale Research Facility located on the Naval Oil Shale Reserves near Rifle, Colorado. One of these leased facilities was transferred to the Bureau of Mines (BOM) to the Energy Research and Development Administration (ERDA) when the latter agency was formed in 1974.

The Paraho Oil Shale Demonstration was privately sponsored by the following seventeen participants at a total cost of \$9.4 million:

Sohio Petroleum Company
Southern California Edison Company
The Cleveland-Cliffs Iron Company
Gulf Oil Corporation

WEST COAST
FIBRE SCENT
52% COTTON FIBRE

FOREWORD

Under a lease approved by the President of the United States in May, 1972, Paraho undertook, in cooperation with the federal government, to demonstrate the engineering, economic and environmental feasibility and desirability of the Paraho processes and hardware for retorting oil shale. This Final Report to participants of the Paraho Oil Shale Demonstration is a six-volume document that describes the research and development operations, the engineering design and cost estimating, and the commercial evaluation studies carried out from late-1973 to mid-1976.

THIS VOLUME 5-A IS CONSIDERED CONFIDENTIAL UNDER THE TERMS OF THE PARTICIPANTS AGREEMENTS WITH PARAHO CORPORATION AND DEVELOPMENT ENGINEERING, INC. MORE-OVER, BECAUSE OF THE COMMITMENT TO THE GOVERNMENT NOT TO PUBLISH INFORMATION PREMATURELY, DISTRIBUTION SHOULD BE STRICTLY CONTROLLED ON A NEED-TO-KNOW BASIS UNTIL AFTER THIS MATERIAL HAS BEEN PUBLISHED BY THE GOVERNMENT OR PARAHO.

The field operations were conducted at the Anvil Points Oil Shale Research Facilities located on the Naval Oil Shale Reserves near Rifle, Colorado. Administration of these leased facilities was transferred from the Bureau of Mines (BOM) to the Energy Research and Development Administration (ERDA) when the latter agency was formed in 1974.

The Paraho Oil Shale Demonstration was privately sponsored by the following seventeen participants at a total cost of \$9.4 million:

Sohio Petroleum Company
Southern California Edison Company
The Cleveland-Cliffs Iron Company
Gulf Oil Corporation

FOREWORD


Under a lease approved by the President of the United States in May, 1975, Paraho undertook, in cooperation with the Federal government, to demonstrate the engineering, economic and environmental feasibility and desirability of the Paraho process and hardware for restoring oil shale. This final Report to participants of the Paraho Oil Shale Demonstration is a six-volume document that describes the research and development operations, the engineering design and cost estimating, and the commercial evaluation studies carried out from late-1973 to mid-1975.

THIS VOLUME 5-A IS CONSIDERED CONFIDENTIAL UNDER THE TERMS OF THE PARTICIPANTS AGREEMENTS WITH PARAHO CORPORATION AND DEVELOPMENT ENGINEERING, INC. MOREOVER, BECAUSE OF THE COMMITMENT TO THE GOVERNMENT NOT TO PUBLISH INFORMATION PREMATURELY, DISTRIBUTION SHOULD BE STRICTLY CONTROLLED ON A NEED-TO-KNOW BASIS UNTIL AFTER THIS MATERIAL HAS BEEN PUBLISHED BY THE GOVERNMENT OR PARAHO.

The field operations were conducted at the Anvil Point Oil Shale Research Facilities located on the Naval Oil Shale Reserve near Rifle, Colorado. Administration of these leased facilities was transferred from the Bureau of Mines (BOM) to the Energy Research and Development Administration (ERDA) when the latter agency was formed in 1974.

The Paraho Oil Shale Demonstration was privately sponsored by the following seventeen participants at a total cost of \$2.4 million:

Gulf Oil Corporation
The Cleveland-Clika Iron Company
Southern California Edison Company
Sohio Petroleum Company



Arthur G. McKee and Company
Kerr-McGee Corporation
Shell Development Corporation
Standard Oil Company (Indiana)
The Carter Oil Company (Exxon)
Mobil Research and Development Corporation
Webb-Gary-Chambers-McLoraine (Group)
Sun Oil Company
Texaco Inc.
Phillips Petroleum Company
Atlantic Richfield Company
Marathon Oil Company
Chevron Research Company

These participants received the right to license Paraho's oil shale technology on favorable terms for their support and cooperation which are gratefully acknowledged.

The results of Paraho's operations at Anvil Points are encouraging. They demonstrate that the process works, that the equipment is operable and durable, that thermal efficiencies and yields are high, and that the entire system developed is environmentally acceptable. The extended periods of Paraho retort operations and the results obtained demonstrate this. The evidence includes the 77-day Pilot Plant run and the 56-day Semi-Works run, both of which were terminated voluntarily.

After the 56-day retort run, 10,000 barrels of Paraho crude shale oil were shipped to the nearby Gary Western Refinery and converted into military products. This federally funded work was done for the U.S. Navy's Energy and Natural Resources Research and Development Office. That Office coordinated the refining and the nationwide, refined product testing program and publishing a report entitled:

Arthur G. McKee and Company

Kerr-McGee Corporation

Shell Development Corporation

Standard Oil Company (Indiana)

The Carter Oil Company (Exxon)

Nobil Research and Development Corporation

Webb-Gary-Chambers-Molayne (Group)

Son Oil Company

Texas Inc.

Phillips Petroleum Company

Atlantic Richfield Company

Marathon Oil Company

Chevron Research Company

These participants received the right to license Paraho's oil shale technology on favorable terms for their support and cooperation which are gratefully acknowledged.

The results of Paraho's operations at Anvil Pointe are encouraging. They demonstrate that the process works, that the equipment is operable and durable, that thermal efficiencies and yields are high, and that the entire system developed is environmentally acceptable. The extended periods of Paraho retrofit operations and the results obtained demonstrate this. The evidence includes the 75-day Pilot Plant run and the 56-day Semi-Works run, both of which were terminated voluntarily.

After the 56-day retrofit run, 10,000 barrels of Paraho crude shale oil were shipped to the nearby Gary Western Refinery and converted into military products. This federally funded work was done for the U.S. Navy's Energy and Natural Resources Research and Development Office. That Office coordinated the refining and the nationwide, refined product testing program and publishing a report entitled:



Production and Refining of 10,000 Bbl. Paraho Crude
Shale Oil Into Military Fuels, U. S. Navy Contract
#N0014-75-C-0055

VOLUME 3-A

A retorted shale management research project jointly funded by the Bureau of Mines and Paraho will be completed in late-1976 at an estimated additional cost of \$0.5 million. At that time, a report entitled, "Retorted Shale Management", will be issued as the concluding volume of this report.

2	INTRODUCTION AND OBJECTIVE	2-1
3	KEY RESULTS	3-1
	3.1 Description of Cases	3-1
	3.2 Economic Analysis	3-5
	3.3 Economic Assumptions	3-9
	3.4 Variable Studies	3-11
4	DESIGN BASIS AND PROJECT DESCRIPTION	4-1
	4.1 Site Description	4-1
	4.2 Oil Shale Mining	4-3
	4.3 Retort Feed Preparation	4-5
	4.4 Retorting	4-7
	4.5 Retorted Shale Management	4-19
	4.6 Offsite Facilities	4-21
	4.7 Upgrading	4-24
5	APPENDIX	
	Crude Assay - Direct Heated Process	
	Crude Assay - Indirect Heated Process	
	Gas Analysis - Direct Heated Process	
	Blasting and Crushing Study	

SECRET

Production and Refining of 10,000 Bbl. Paraho Crude
Shale Oil Into Military Fuels, U. S. Navy Contract
#0014-75-C-0055

A reported shale management research project jointly funded by the Bureau of Mines and Paraho will be completed in late 1976 at an estimated additional cost of \$0.2 million. At that time, a report entitled, "Reported Shale Management", will be issued as the concluding volume of this report.

CONTENTS

VOLUME 5-A

<u>Section</u>	<u>Page</u>
1 EXECUTIVE SUMMARY	1-1
2 INTRODUCTION AND OBJECTIVE	2-1
3 KEY RESULTS	3-1
3.1 Description of Cases	3-1
3.2 Economic Analysis	3-6
3.3 Economic Assumptions	3-9
3.4 Variable Studies	3-11
4 DESIGN BASIS AND PROJECT DESCRIPTION	4-1
4.1 Site Description	4-1
4.2 Oil Shale Mining	4-3
4.3 Retort Feed Preparation	4-5
4.4 Retorting	4-7
4.5 Retorted Shale Management	4-39
4.6 Offsite Facilities	4-41
4.7 Upgrading	4-44
5 APPENDIX	
Crude Assay - Direct Heated Process	
Crude Assay - Indirect Heated Process	
Gas Analysis - Direct Heated Process	
Blasting and Crushing Study	

CONTENTS

VOLUME 5-A

Section	Page
1	EXECUTIVE SUMMARY 1-1
2	INTRODUCTION AND OBJECTIVE 2-1
3	KEY RESULTS 3-1
	3.1 Description of Cases 3-1
	3.2 Economic Analysis 3-2
	3.3 Economic Assumptions 3-3
	3.4 Variable Studies 3-11
4	DESIGN BASIS AND PROJECT DESCRIPTION 4-1
	4.1 Site Description 4-1
	4.2 Oil Shale Mining 4-2
	4.3 Retort Feed Preparation 4-2
	4.4 Retorting 4-7
	4.5 Retorted Shale Management 4-39
	4.6 Offsite Facilities 4-41
	4.7 Upgrading 4-44
5	APPENDIX
	Crude Assay - Direct Heated Process
	Crude Assay - Indirect Heated Process
	Gas Analysis - Direct Heated Process
	Blasting and Crushing Study

1. EXECUTIVE SUMMARY

2. INTRODUCTION

3. KEY RESULTS

4. DESIGN BASIS

SECTION 1

EXECUTIVE SUMMARY

The objective of this report is to provide information to the management of the participating companies regarding the commercial feasibility of an oil shale venture.

Numerous alternates have been studied. All are energy self-sufficient. Two are summarized here. One produces pipelineable crude shale oil. The other upgrades the crude shale oil to a high quality syncrude. In all cases, the total oil shale retorted and the gross crude shale oil produced remain constant at 157,400 tons per stream day and 100,000 barrels per stream day, respectively. The amount of net products vary according to the methods of processing and upgrading and the internal fuel requirements. All costs necessary to provide a proper plant site, a complete mine and plant, and onsite and offsite plant facilities have been included. The results are summarized as follows:

	Crude Shale Oil Case	Syncrude Oil Case
Feed		
Oil Shale TPSD	157,400	157,400
Water - Acre ft./yr.	5,740	8,310
Net Products		
Crude Shale Oil BPSD	99,170	--
Syncrude BPSD	--	88,542
Sulfur TPSD	85	191
Ammonia TPSD	43	415
Excess Power Generated MW	53	--
Economics (1976 Dollars)		
Investment - \$ Billions	1.2	1.6
Operating Cost - \$ Millions/Yr.	150	190
Oil Price (100% Equity Basis):		
15% Return on Investment \$/Bbl.	11.50 ⁽¹⁾	17.50 ⁽¹⁾

(1) These prices should not be directly compared to crude oil prices. See Pg. 1-2.

SECTION I

EXECUTIVE SUMMARY

The objective of this report is to provide information to the management of the participating companies regarding the commercial feasibility of an oil shale venture.

Numerous alternatives have been studied. All are energy self-sufficient. Two are summarized here. One produces pipeline grade shale oil. The other upgrades the crude shale oil to a high quality synfuel. In all cases, the total oil shale recovered and the gross crude shale oil produced remain constant at 157,400 tons per stream day and 100,000 barrels per stream day, respectively. The amount of net products vary according to the methods of processing and upgrading and the internal fuel requirements. All costs necessary to provide a proper plant size, a complete mine and plant, and onsite and offsite plant facilities have been included. The results are summarized as follows:

Crude Shale Oil		Synfuel Oil	
Case		Case	
157,400	8,310	157,400	8,310
Feed		Feed	
Oil Shale TPD		Oil Shale TPD	
Water - Acft. L/Yr.		Water - Acft. L/Yr.	
Net Products		Net Products	
Crude Shale Oil BPSD		Crude Shale Oil BPSD	
Synfuel BPSD		Synfuel BPSD	
Sulfur TPD		Sulfur TPD	
Ammonia TPD		Ammonia TPD	
Excess Power Generated MW		Excess Power Generated MW	
Economics (1975 Dollars)		Economics (1975 Dollars)	
Investment - \$ Billions		Investment - \$ Billions	
Operating Cost - \$ Millions/Yr.		Operating Cost - \$ Millions/Yr.	
Oil Price (190¢ Bbl. Basis)		Oil Price (190¢ Bbl. Basis)	
15% Return on Investment \$/Bbl.		15% Return on Investment \$/Bbl.	
11.25 (1)		11.25 (1)	
1.6		1.6	
190		190	
17.50 (1)		17.50 (1)	

(1) These prices should not be directly compared to crude oil prices. See Pg. 1-2.

This preliminary Commercial Evaluation Study indicates the following:

- o A crude shale oil price of \$11.50 per barrel is needed to yield a 15% return on investment. The prices of crude shale oil and conventional crude oil cannot be properly compared without examining the possible added refinery investment and operating costs related to the processing of crude shale oil. To refine imported Saudi Light or African Sweet crudes (which in July, 1976 delivered to the U. S. Gulf Coast at \$13 to \$14 per barrel) requires lower refining investment than crude shale oil.
- o A syncrude price of \$17.50 per barrel is needed to yield a 15% return on investment. Syncrude is a high quality "bottomless" material that should carry a premium value over imported crudes. This is because of the higher proportion of high priced products available from syncrude, the additional advantage syncrude offers refiners having "bottom of the barrel" limitations, and the possibility that syncrude might be marketable directly as a wide-range distillate fuel.
- o Shale oil and imported crude oil are exempt from domestic price control. However, until a free market in domestic oil is reestablished, the true penalty and premium values of crude shale oil and syncrude will not be known. This information is essential before pioneer plant commitments can be made. A pioneer plant yield of less than 15% rate of return on investment is inadequate to justify building a commercial plant with the uncertainties described below.

This preliminary Commercial Evaluation Study indicates the following:

A crude shale oil price of \$11.50 per barrel is needed to yield a 15% return on investment. The prices of crude shale oil and conventional crude oil cannot be properly compared without examining the possible added refinery investment and operating costs related to the processing of crude shale oil. To refine imported Saudi Light or African Sweet crudes (which in July, 1976 delivered to the U. S. Gulf Coast at \$13 to \$14 per barrel) requires lower refining investment than crude shale oil.

A syncrude price of \$17.50 per barrel is needed to yield a 15% return on investment. Syncrude is a high quality "bottomless" material that should carry a premium value over imported crudes. This is because of the higher proportion of high priced products available from syncrude, the additional advantage syncrude offers refiners having "bottom of the barrel" limitations, and the possibility that syncrude might be marketable directly as a wide-range distillate fuel.

Shale oil and imported crude oil are exempt from domestic price control. However, until a free market in domestic oil is reestablished, the true penalty and premium values of crude shale oil and syncrude will not be known. This information is essential before pioneer plant commitments can be made. A pioneer plant yield of less than 15% rate of return on investment is inadequate to justify building a commercial plant with the uncertainties described below.

- o If the world price of crude oil escalates faster than the investment required to build shale plants, or if, in the best interest of the United States, our dependence on imported crude should be limited by restricting imports, crude shale oil and syncrude could command the prices required to become a viable energy supply. *this step by joint government industry cooperation is essential.*
- o A commercial oil shale installation will consist of very large and complex units of mining, retorting, and upgrading - all close coupled and interdependent. A high operational risk is involved since each operating unit must have a high "on-stream" factor to maintain the desired production levels. Failure to achieve this reliability would have a major impact on project economics. In addition, such investments are vulnerable to technological, political, commercial, and environmental risks that must be resolved. Consequently, as a first and an important step, the program that has been proposed by Paraho should be implemented to demonstrate this technology, at full-scale, in a module of the size and design anticipated for commercial plants. Such a demonstration will provide a sound basis for:
 - o Establishing reliability and "on-stream" factor.
 - o Predicting capital and operating costs for commercial units more accurately.
 - o Evaluating environmental impact, such as retorted shale disposal and ambient air quality. Since much of the undeveloped oil shale country, in its natural state, is believed to be in violation of the Clean Air Act standards, some changes in these will be needed.

STANDARD
MELON BOND

- o Determining minimum water requirements - an important aspect of oil shale development.

Such a module will represent a large research investment with no immediate return. Therefore, to maintain the momentum established by Paraho, encouragement of this step by joint government industry cooperation is essential.

SECTION 101

SECTION 101

MESLON BOND

INTRODUCTION AND OBJECTIVE

This commercial evaluation for an oil shale venture based on Paraho retorts is contained in two volumes. This volume, 5-A is a summary. Volume 5-B, which is Proprietary and Secret, contains the details.

Economic analysis of various aspects of the Paraho retorting process has been a continuing effort throughout the project. A preliminary commercial economical analysis was presented in May, 1975, in the "Prospectus for a Paraho Full-Size Module" brochure.

The objective of this report is to provide information to the participating companies regarding the commercial feasibility of an oil shale venture. The objectives, specifications, and contents of this report were developed by joint discussions between the Technical Advisory Committee of participants, The Cleveland-Cliffs Iron Company, Arthur G. McKee & Company, Sohio Petroleum Company, and Paraho.

This commercial feasibility study includes facilities for:

- o Mining, crushing, screening, materials handling, and retorted shale disposal.
- o Direct and indirect heated retorting (Combination heating is not included due to insufficient data).
- o Upgrading of shale oil to a pipelineable product.
- o Upgrading of gases to an environmentally acceptable quality.

Page 11

SECTION 2

INTRODUCTION AND OBJECTIVE

This commercial evaluation for an oil shale venture based on Paraho reports is contained in two volumes. This volume, 5-A is a summary. Volume 5-B, which is Proprietary and Secret, contains the details.

Economic analysis of various aspects of the Paraho retorting process has been a continuing effort throughout the project. A preliminary commercial economical analysis was presented in May, 1975, in the "Prospectus for a Paraho Full-Scale Module" brochure.

The objective of this report is to provide information to the participating companies regarding the commercial feasibility of an oil shale venture. The objectives, specifications, and contents of this report were developed by joint discussions between the Technical Advisory Committee of participants, The Cleveland-Cille Iron Company, Arthur G. McKee & Company, Sohio Petroleum Company, and Paraho.

This commercial feasibility study includes facilities for:

- o Mining, crushing, screening, materials handling, and retorted shale disposal.
- o Direct and indirect heated retorting (Combination Heating is not included due to insufficient data).
- o Upgrading of shale oil to a pipelineable product.
- o Upgrading of gases to an environmentally acceptable quality.

- o Utilities and offsites.
- o Waste treatment.

This report provides facilities planning and an order-of-magnitude estimate of $\pm 25\%$ accuracy. Economics are worked out using a standard discounted cash flow method on 100% equity basis.

In order to make this report more realistic and representative, it was felt necessary to select a specific site rather than a hypothetical location. The site selection on U.S. Naval Oil Shale Reserve No. 1 is considered to be typical for an oil shale venture, and oil shale for the Paraho Oil Shale Demonstration was extracted from the same area. However, this does not represent an endorsement by the Department of Navy or any other government agency.

Page 11

o Utilities and offsites.

o Waste treatment.

This report provides facilities planning and an order-of-magnitude estimate of cost accuracy. Economics are worked out using a standard discounted cash flow method on 100% equity basis.

In order to make this report more realistic and representative, it was felt necessary to select a specific site rather than a hypothetical location. The site selection on U.S. Naval Oil Shale Reserve No. 1 is considered to be typical for an oil shale venture, and oil shale for the Paraho Oil Shale Demonstration was extracted from the same area. However, this does not represent an endorsement by the Department of Navy or any other government agency.

3. KEY RESULTS

4. DESIGN BASIS

SECTION 3 KEY RESULTS

A total of five cases have been studied. In all cases the total oil shale to be retorted remains constant - 157,421 tons per stream day, as does the crude shale oil produced at the retort outlet - 100,000 barrels per stream day. The amount of products produced vary according to the processing plan used in each case. While some changes could occur in the retorted shale management area, for the purposes of this study, all cases are assumed to require the same capital and operating costs for mining, material handling, and retorted shale management. The necessary work and related costs to provide a proper site, infrastructure, and onsite and offsite facilities have been included for all cases. Both capital and operating costs have been varied as changes are made in the retorting and upgrading facilities.

3.1 DESCRIPTION OF CASES

In all cases oil shale is mined and retorted to produce a crude shale oil.

3.1.1 Base Case

Coking of crude shale oil with hydrotreating of coker liquid products is used. The major liquid product is a low nitrogen, low sulfur, low pour point syncrude.

Twelve Direct Heated and twelve Indirect Heated Paraho retorts were selected to provide an essentially balanced energy system. Hydrogenation of the individual naphtha, light gas oil and heavy gas oil liquid products produces a syncrude product. The coke produced in the refining step is burned in a power plant (built and operated by others).

SECTION 2 KEY RESULTS

A total of five cases have been studied. In all cases the total oil shale to be retorted remains constant - 157,421 tons per stream day, as does the crude shale oil produced at the retort outlet - 100,000 barrels per stream day. The amount of products produced vary according to the processing plan used in each case. While some changes could occur in the retorted shale management area, for the purposes of this study, all cases are assumed to require the same capital and operating costs for mining, material handling, and retorted shale management. The necessary work and related costs to provide a proper site, infrastructure, and onsite and offsite facilities have been included for all cases. Both capital and operating costs have been varied as changes are made in the retorting and upgrading facilities.

2.1 DESCRIPTION OF CASES

In all cases oil shale is mined and retorted to produce a crude shale oil.

2.1.1 Base Case

Coking of crude shale oil with hydrocracking of coker liquid products is used. The major liquid product is a low nitrogen, low sulfur, low pour point syn-crude.

Twelve Direct Heated and twelve Indirect Heated Furnaces re-formers were selected to provide an essentially balanced energy system. Hydrogenation of the individual naphthas, light gas oil and heavy gas oil liquid products produces a syn-crude product. The coke produced in the refining step is burned in a power plant (boiler and operated by others).

3.1.2 Alternate 1

Direct hydrogenation of crude shale oil is used. Again, the major liquid produced is a low nitrogen, low sulfur, low pour point syncrude.

This case requires 18 Direct Heated and 6 Indirect Heated Paraho retorts to balance the fuel production and requirements.

3.1.3 Alternate 2

No upgrading of crude shale oil is carried out. Three retorting schemes are considered.

2A Paraho Direct Heated retorts only

2B Paraho Indirect Heated retorts only

2C A combination of Paraho Direct Heated and Indirect Heated retorts

3.1.4 Alternate 2A

A total of 24 Direct Heated Paraho retorts are used.

Crude shale oil, with a pour point depressant is pipelined from the complex.

A large amount of low Btu gas is produced in this case. The gas is cleaned and used to generate electrical power and the excess power is exported through a high voltage power grid.

3.1.5 Alternate 2B

A total of 24 Indirect Heated Paraho retorts are used.

Crude shale oil, with a pour point depressant is pipelined from the complex.

Alternate 1

3.1.2

Direct hydrogenation of crude shale oil is used. Again, the major liquid produced is a low nitrogen, low sulfur, low pour point syn crude.

This case requires 18 Direct Heated and 6 Indirect Heated Paraho reactors to balance the fuel production and requirements.

Alternate 2

3.1.3

No upgrading of crude shale oil is carried out. Three retorting schemes are considered.

- | | |
|----|--|
| 2A | Paraho Direct Heated reactors only |
| 2B | Paraho Indirect Heated reactors only |
| 2C | A combination of Paraho Direct Heated and Indirect Heated reactors |

Alternate 2A

3.1.4

A total of 24 Direct Heated Paraho reactors are used.

Crude shale oil, with a pour point depressant is pipelined from the complex.

A large amount of low Btu gas is produced in this case. The gas is cleaned and used to generate electrical power and the excess power is exported through a high voltage power grid.

Alternate 2B

3.1.5

A total of 14 Indirect Heated Paraho reactors are used.

Crude shale oil, with a pour point depressant is pipelined from the complex.

The fuel for the IH retort heaters requires that the high Btu gas (after cleaning) from the retorts be supplemented with liquid fuel. The net liquid product output reflects this demand; a cost of producing liquid fuel that is environmentally acceptable is also included in the operating costs.

3.1.6 Alternate 2C

Retorting utilizes a combination of Paraho retorts - 18 Direct Heated and 6 Indirect Heated with a fuel pool balanced to produce no excess low Btu gas.

The major product is crude shale oil. A pour point depressant is added so that the product can be handled through conventional pipelines. A quantity of SNG is produced and exported as a pipeline gas product. The fuel balance is such that an excess of Indirect Heated retort gases are produced. A SNG plant is included in the capital and operating costs values; this plant is required to treat the Indirect Heated retort gases so that they meet existing natural gas pipeline specifications.

The full scale project facilities for each of the five case studies are described in the following Section 4 including:

- o Mining and materials handling
- o Paraho retorting
- o Retorted shale disposal
- o Upgrading of shale oil and gases
- o Offsites and support facilities

Key results of the evaluation for each of the cases are presented in Table 3-1, Feed and Product Summary, and Table 3-2, Overall Summary.

The fuel for the 18 retort heaters requires that the high Btu gas (after cleaning) from the retorts be supplemented with liquid fuel. The net liquid product output reflects this demand; a cost of producing liquid fuel that is environmentally acceptable is also included in the operating costs.

3.1.6 Alternates 2C

Retorting utilizes a combination of Paraho retorts - 18 Direct Heated and 6 Indirect Heated with a fuel pool balanced to produce no excess low Btu gas.


The major product is crude shale oil. A pour point depressant is added so that the product can be handled through conventional pipelines. A quantity of SNG is produced and exported as a pipeline gas product. The fuel balance is such that an excess of indirect heated retort gases are produced. A SNG plant is included in the capital and operating costs values; this plant is required to treat the indirect heated retort gases so that they meet existing natural gas pipeline specifications.

The full scale project facilities for each of the five cases studies are described in the following Section 4 including:

- o Mining and materials handling
- o Paraho retorting
- o Retorted shale disposal
- o Upgrading of shale oil and gases
- o Offsites and support facilities

Key results of the evaluation for each of the cases are presented in Table 3-1, Feed and Product Summary, and Table 3-2, Overall Summary.

TABLE 3-1
FEED AND PRODUCT
SUMMARY



	BASE CASE	ALTERNATE 1	ALTERNATE 2A	ALTERNATE 2B	ALTERNATE 2C
FEEDS					
SHAPE, TPSD	157,421	157,421	157,421	157,421	157,421
RAW WATER, ACRE FT./YR.	8,070	8,310	5,740	3,460	5,130
PRODUCTS					
CRUDE SHALE OIL, BPSD	--	--	99,170	83,560	94,220
HYDROTREATED OIL, BPSD	81,265	88,542	--	--	--
SNG, MMSCFD	--	--	--	--	16.4
AMMONIA, TPSD	317	415	43	23	38
SULFUR, TPSD	193	191	85	114	92
FUEL (TO POWER PLANT), BPSD, FOE	17,409	18,330	18,531	13,475	15,104
POWER (TO OIL SHALE PLANT), Kw.	343,000	344,700	277,500	269,500	279,500
POWER (TO GRID), Kw.	--	--	53,500	--	--

Table 3-2

OVERALL SUMMARY

	Base Case Coking Hydro- treating	Alternate 1 Direct Hydro- treating of Crude Shale Oil	Alternate 2A Crude Shale Oil Only Direct Heated	Alternate 2B Crude Shale Oil Only Indirect Heated	Alternate 2C Crude Shale Oil Only Direct Heated & Indirect Heated
Mining Rate TPSD	165,700	165,700	165,700	165,700	165,700
No. of Direct Heated Retorts	12	18	24	---	18
No. of Indirect Heated Retorts	12	6	---	24	6
<u>Retort Production:</u>					
Crude Shale Oil (BPSD)	100,000	100,000	100,000	100,000	100,000
Gas:* D.H. (FOE BPSD)	12,424	18,636	24,849	---	18,636
(MMSCFSD)	(482.8)	(724)	(966)	---	(724)
I.H. (FOE BPSD)	5,678	2,839	---	11,355	2,839
(MMSCFSD)	(39.0)	(19.5)	---	(78)	(19.5)
Condensate (BPSD)	400	200	---	800	200
<u>Net Production:</u>					
Synthetic Crude (BPSD)	81,265	88,542	---	---	---
Crude Shale Oil (BPSD)	---	---	99,170	83,560	94,220
SNG (MMSCFD)	---	---	---	---	16.4
Total Facilities Invest- ment \$Millions	1,619	1,578	1,166	1,285	1,216
Total Facilities Operat- ing Cost \$Millions/Year	195	191	148	179	162
Synthetic Crude Price at 15% ROI 100% Equity	19.35	17.50	11.50	15.75	12.70

* Net gas after cleaning

3.2 ECONOMIC ANALYSIS

An economic analysis was developed for a 100,000 BPSD crude shale oil complex. The capital investment and operating cost requirement were developed for a 165,700 ton per day mining operation, retorting facilities to produce 100,000 barrels per stream day of crude shale oil and upgrading facilities.

The investment and operating costs for cases studied are summarized on the following Tables 3-3, Investment Summary and 3-4, Operating Cost Summary.

	Base Case Coking Hydro- treating	Alternate 1 Direct Hydro- treating of Crude Shale Oil	Alternate 2 Crude Shale Oil Only Direct Heated
Mining	265	265	265
Materials Handling (Crushing, Screening, etc.)	147	147	147
Retorting	391	346	302
Retort Gas Cleaning & Upgrading	80	80	80
Crude Shale Oil Upgrading	278	262	---
Retorted Shale Management	53	53	53
Water Supply	18	18	18
Offsites	182	150	100
Site Prep & Roads	30	30	27
SUBTOTAL	1,376	1,351	999
OTHER COSTS:			
Reserve Acquisition	20	20	20
Owner Engrg. & Proj. Management	20	17	12
Organization Develop & Training	10	10	28
Startup & Fix-its	60	58	40
Environmental Monitoring	10	10	15
Catalysts & Chemicals	8	12	1
Royalties - Prepaid	5	4	1
Working Capital	60	60	50
Other	10	10	2
SUBTOTAL	223	227	167
TOTAL	1,613	1,578	1,166

3.2 ECONOMIC ANALYSIS

An economic analysis was developed for a 100,000 BPSD crude shale oil complex. The capital investment and operating cost requirements were developed for a 165,700 ton per day mining operation, restoring facilities to produce 100,000 barrels per stream day of crude shale oil and upgrading facilities.

The investment and operating costs for cases studied are summarized on the following Tables 3-3, Investment Summary and 3-4, Operating Cost Summary.

Table 3-3

INVESTMENT SUMMARY - \$MILLIONS

	Base Case Coking Hydro- treating	Alternate 1 Direct Hydro- treating of Crude Shale Oil	Alternate 2A Crude Shale Oil Only Direct Heated	Alternate 2B Crude Shale Oil Only Indirect Heated	Alternate 2C Crude Shale Oil Only Direct Heated & Indirect Heated
Mining	265	265	265	265	265
Materials Handling (Crushing, Screening, etc.)	147	147	147	147	147
Retorting	391	346	302	480	346
Retort Gas Cleaning & Upgrading	60	80	90	25	91
Crude Shale Oil Upgrading	270	262	---	---	---
Retorted Shale Management	53	53	53	53	53
Water Supply	18	18	15	13	14
Offsites	162	150	100	94	97
Site Prep & Roads	30	30	27	27	27
SUBTOTAL	1,396	1,351	999	1,104	1,040
OTHER COSTS:					
Reserve Acquisition	20	20	20	20	20
Owner Engrg. & Proj. Management	20	17	12	13	12
Organization Develop & Training	30	30	25	25	25
Startup & Fix-its	60	58	40	53	49
Environmental Monitoring	10	10	10	10	10
Catalysts & Chemicals	8	18	1	1	1
Royalties - Prepaid	5	4	1	1	1
Working Capital	60	60	50	50	50
Other	10	10	8	8	8
SUBTOTAL	223	227	167	181	176
TOTAL	1,619	1,578	1,166	1,285	1,216

3.3 ECONOMIC ASSUMPTIONS

Project Schedule

24 project years
5 design-construct years
21 production years

Table 3-4

Base Case & Alternates
Annual Operating Costs
(\$ Millions/Yr)

Owner's Equity

100%

Service Factor	Base Case	Alternate			
		1	2A	2B	2C
Mining, Crush, Retorted Shale	77.22	77.22	77.22	77.22	77.22
Retort, & Retort Gas	69.36	64.12	64.83	74.17	68.52
Upgrading & Offsites	38.80	41.11	6.32	6.15	6.24
Water Supply	2.15	2.19	1.70	1.37	1.66
Administration	1.78	1.77	1.17	1.17	1.21
FOE (Credit)	(21.62)	(24.57)	(23.01)	(23.37)	(19.95)
Fuel Oil (Debit)	-	-	1.11	21.60	7.60
Insurance & Tax	23.80	22.56	15.60	17.68	16.40
Corporate Overhead	4.00	4.00	3.20	3.20	3.40
TOTAL	195.49	191.40	148.14	179.20	162.30

Project Economics

Plant gas basis

By-product Values

Ammonia - \$140/ton
Sulfur - zero value
SNG - \$1.50/MM Btu

Water is available from Colorado River in required volume and at \$25 per acre-foot.

Plant effluents will meet Federal/Colorado environmental requirements.

Table 3-4
Base Case & Alternates
Annual Operating Costs
(\$ Millions/Yr)

	Base Case	I	2A	2B	2C
Mineral, Crush, Recycled Shale	77.22	77.22	77.22	77.22	77.22
Refert, & Refert Gas	69.36	64.12	64.83	74.17	68.22
Upgrading & Offsites	38.80	41.11	6.32	6.12	6.24
Water Supply	2.12	2.19	1.70	1.37	1.66
Administration	1.78	1.77	1.17	1.17	1.27
FOE (Credit)	(21.62)	(24.27)	(23.01)	(23.37)	(19.82)
Fuel Oil (Debit)	-	-	1.11	21.60	7.60
Insurance & Tax	23.80	22.26	12.60	17.68	16.40
Corporate Overhead	4.00	4.00	3.20	3.20	3.40
TOTAL	192.49	191.40	148.14	179.20	162.30

3.3 ECONOMIC ASSUMPTIONS

Project Schedule	24 project years 5 design-construct years 21 production years (1 @ 12.5%, 1 @ 56.25%, 19 @ full) See Figure 3-1
First half 1976 dollars	No change in dollar value during the project
Owner's Equity	100%
Service Factor	90%
Investors rate of return	15%
Depletion allowance on value of retorts liquid yield	15%
Depreciation	Mining 10 years Retorting & Processing 15 years Water Supply 20 years
Investment Credit	7% on initial capital
Income tax rate	51% (Federal plus State)
Severance Tax	0%
Insurance and other taxes	2% of initial capital (Site Prep. excluded)
Extraction royalty	11¢ per ton of mined shale (29 gal./ton)
Retort royalty	10¢ per bbl. crude shale oil
Process royalty	Varies - typical for process unit included
Project Economics	Plant gate basis
By-product Values	Ammonia - \$140/ton Sulfur - zero value SNG - \$1.50/MM Btu

Water is available from Colorado River in required volume and at \$25 per acre-foot.

Plant effluents will meet Federal/Colorado environmental requirements.

Figure 3-1

PROJECT SCHEDULE - BASE CASE

A permanent highway will be constructed by the state from Rio Blanco to the plant site.

Associated community development will be by others.

No extraordinary taxes or assessments are included.

Exploration and environmental studies - \$10 MM


Project abandonment costs - zero.

Salvage value at termination - zero.

Electric power - purchased at 2.2¢/KWH.

Fuel to external power plant - value equivalent to 2.2¢/KWH power.

Addition of pour point depressant in crude shale oil cases 2A, 2B, and 2C will cost 25¢/barrel. This is based on laboratory tests of commercially available pour point depressants in reducing crude shale oil pour point to 40°F.








Figure 3-1

PROJECT SCHEDULE – BASE CASE



3.4 VARIABLE STUDIES

Economic variables analyses were conducted against the Base Case only, and the results are shown in Table 3-5.

- 1. o Depletion Allowance at 0%
- 2. o Investment Credit at 0%
- 3. o 10% Fines
- 4. o Capital Investment at 110%
- 5. o All by-product values at zero
- 6. o Operating costs at 110%
- 7. o Six year design-construction period
- 8. o Retort mass rate at 110%
- 9. o Retort mass rate at 90%
- 10. o Retort liquid yield at 95% (vs. 92%)
- 11. o Retort liquid yield at 89% (vs. 92%)
- 12. o Overall service factor at 80% (vs. 90%)
- 13. o 1 Year added production
- 14. o Reserves acquisition @ 5¢/Bbl.
- 15. o Reserves acquisition @ 10¢/Bbl.

Base Case and Alternate Comparison of Product Oil Value at Different Return on Investment:

		Value of Product Oil, \$/Bbl. at Following Return on Investment	
Case	Shale Oil Product	12%	15%
Base	Refined	16.70	19.35
Alt. 1	Refined	15.15	17.50
Alt. 2A	Crude	10.10	11.50
Alt. 2B	Crude	13.85	15.75
Alt. 2C	Crude	11.15	12.70

Table 3-5

VARIATIONS TO BASE CASE

	R.O.I. @ \$18.00/Bbl. Plant Gate Oil Price, %	+ Oil Price/Bbl. From Base Case For 15% R.O.I.
1. 80% Service factor	11.0	+\$2.45
2. 0 Depletion	11.5	+ 2.15
3. + 10% Capital Cost	12.5	+ 1.15
4. 6 Yr. Construction	12.6	+ 1.15
5. + 10% Oper. Cost	12.7	+ .65
6. 0 Tax Credit	12.9	+ .65
7. 0 By-Product Values	12.9	+ .55
8. 89% Liquid Yield	13.2	+ .30
9. 10% Fines	13.2	+ .25
10. -10% Retort Mass Flow	13.4	+ .15
Base Case	13.5	19.35*
11. 1 Yr. Added Production	13.7	- .10
12. +10% Retort Mass Flow	13.7	- .15
13. 10¢/Bbl. Reserve Acquis.	13.7	- .20
14. 5¢/Bbl. Reserve Acquis.	13.7	- .25
15. 95% Liquid Yield	13.9	- .35

*Oil price for base case at 15% R.O.I.

4. DESIGN BASIS

SECTION 4

DESIGN BASIS AND PROJECT DESCRIPTION

4.1 SITE DESCRIPTION

4.1.1 General


The site assumed for this study is located within Garfield County in northwest Colorado. The plant site, including the area to be mined covers 12 square miles in the Naval Oil Shale Reserve No. 1 on the Roan Plateau. It is approximately three miles north of the site of the Paraho Oil Shale Demonstration at Anvil Points, Colorado. Figures 4-1 and 4-2 indicate the site.

The site topography and overall project layout are shown in Figure 4-3. The site is hilly containing light woods and brush with surface elevations varying from 8000 feet to 9160 feet. Drainage from the site presents no problems and eventually flows to the Colorado River. Bearing capacity of the soil is in excess of 3000 lbs. per square foot.


Access to the site is currently by unimproved dirt road from a main highway running from Rifle to Rio Blanco which, in turn, connects with other major highway arteries. The nearest railroad connection is in Rifle where provision for a siding will be made. Rail service to the site will not be provided. The nearest commercial airport is at Grand Junction.


4.1.2 Plant Layout

The mined area and layout is shown in Figure 4-3. Mine shafts are located at the centroid of the projected mining area. The mine shafts extend 1055 feet to the mine floor



<small>NOTE: This Print is the property of PARADIO and is loaned to the user. It must not be copied or reproduced in any manner without the written permission of PARADIO. It shall be used only as a means of reference to work designed or furnished by us.</small>	PARADIO COMMERCIAL EVALUATION STUDY	McKee <small>ENGINEERS AND CONSTRUCTORS CLEVELAND, OHIO</small>
	REGIONAL MAP	
	<small>SCALE 1" = 50 MILES</small>	





NOTE: This Plan is the property of PARADO OIL DEVELOPMENT CORPORATION. It may not be traced nor reproduced in any manner nor shall it be used for any other purpose than the preparation of the project. It shall be used only as a means of reference to work assigned or authorized by us.

**PARADO COMMERCIAL
EVALUATION STUDY**

FILE

AREA MAP

SCALE

1" = 1 MI.


McKEE
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO


FIG. 4-2


SECTION



1. Name of the project 2. Date of the survey 3. Name of the surveyor 4. Name of the company 5. Name of the client	SHEET 1064	FIG. 4-5
	EASTING 21704 NORTHING 10640	



 ELEVATION STUDY PARAHIO COMMERCIAL	NOTE: This study is the property of PARAHIO WILL BE RETURNED TO THE COMPANY AND NOT BE REPRODUCED OR COPIED WITHOUT THE WRITTEN PERMISSION OF THE COMPANY.
	OVERALL PROJECT LAYOUT
FIG. 4-3	FROM ANVIL POINTS QUADRANGLE MAP R. 94 W. 13 S.



— N

SCALE 1:1000

0 1000 2000

FROM ANVIL POINTS QUADRANGLE MAP
R. 94 W. 13 S.

The processing area is situated such that the mine shafts are in close proximity, but dust intake from the processing area is minimal. The processing area plan, which includes the crushers, screening, retort batteries, and associated materials handling is shown in Figure 4-4. The retorted shale disposal area outlined in Figure 4-3 represents a 20 year disposal pile. Runoff retention dams will be built at the base on each disposal area to collect normal runoff and leach waters.

4.1.3 Site Resources

Assayed samples from two core hole drillings done by the Bureau of Mines indicate the existence of mineable oil shale 76 feet thick averaging 29 gallons per ton. Oil shale averaging 29 gallons per ton contains approximately 2040 barrels per acrefoot mined, and the overall extraction by the room-and-pillar mining technique chosen is 62%. Thus the mineable oil shale reserves within the entire 7680 acres are 738 million barrels. At the production rate anticipated, this represents a 19.7 year mine life.

4.1.4 Construction Considerations

Skilled and unskilled construction labor is assumed to be short supply in the area. Labor training and incentive programs will be provided to meet the construction schedule. It is also assumed that sufficient living accommodations will not be available in the limited populated surrounding areas, therefore, a construction labor camp is required.

Being a grass-roots plant, all temporary construction facilities such as office, storage, and service building, as well as utilities, will be provided. Temporary shelters and enclosures will be included to allow construction during adverse weather conditions. Site preparation will require extensive cutting and filling to develop a clear and graded plant site.

The processing area is situated such that the mine shafts are in close proximity, but dust intake from the processing area is minimal. The processing area plan, which includes the crushers, screening, rector batteries, and associated materials handling is shown in Figure 4-4. The rector shale disposal area outlined in Figure 4-3 represents a 10 year disposal pile. Runoff retention dams will be built at the base of each disposal area to collect normal runoff and leach water.


4.1.3 Site Resources

Assayed samples from two core hole drillings done by the Bureau of Mines indicate the existence of minable oil shale 75 feet thick averaging 15 gallons per ton. Oil shale averaged 25 gallons per ton contains approximately 1040 barrels per acre-foot mined, and the overall extraction by the room-and-pillar mining technique chosen is 63%. Thus the minable oil shale reserves within the entire 1680 acres are 718 million barrels. At the production rate anticipated, this represents a 13.7 year mine life.


4.1.4 Construction Considerations



Skilled and unskilled construction labor is assumed to be short supply in the area. Labor training and incentive programs will be provided to meet the construction schedule. It is also assumed that sufficient living accommodations will not be available in the limited populated surrounding areas, therefore, a construction labor camp is required.

Being a grass-roots plant, all temporary construction facilities such as office, storage, and service building, as well as utilities, will be provided. Temporary shelters and enclosures will be included to allow construction during adverse weather conditions. Site preparation will require extensive cutting and filling to develop a clear and graded plant site.



<p>NOTES: This Plan is the property of PARADO and shall not be loaned nor reproduced in any manner nor shall it be submitted for public review for construction without our consent. It shall be used only as a basis of reference for work designed or directed by us.</p>	<p>PARADO COMMERCIAL EVALUATION STUDY</p> <p>PROCESSING AREA PLAN</p>	<p>McKee ENGINEERS AND CONSTRUCTORS CLEVELAND, OHIO</p> <p>FIG. 4-4</p>
---	--	---

	FIG. 4-4	SECTION VIEW 4-4
	SECTION 4-4 EASTERN 21/24 WESTERN 21/24	



It is assumed that upgrading the existing dirt roads to the site will be done by the state. Large sized equipment will be field erected.

4.2 OIL SHALE MINING

4.2.1 General

The proposed mining method is a modified room-and-pillar system. The upper 40 feet of the oil shale horizon will utilize a conventional room-and-pillar system, whereas the lower 36 feet will be mined by a benching system. Face and bench mining are to be performed simultaneously.

A preproduction period of three-and-one-half years has been allowed. During this period, a production shaft, man and materials shaft and three ventilation shafts will be sunk to the mining zone. The primary crushing stations, underground shops and other needed facilities will also be completed in the period. About 8.3 million tons of development ore and panel preparation ore will be excavated and stockpiled on surface prior to plant startup.

4.2.2 Mine Design and Parameters

Scheduled work year	355 Days
Scheduled work week	20 shifts
Panel extraction	68%
Overall extraction	62%
Development entries	50 feet wide by 40 feet high
Development pillars	70 feet wide
Panel rooms (upper level)	55 feet wide by 40 feet high
Lower level bench	55 feet wide by 36 feet high (average)
Panel pillars	60 feet by 88 feet
Panel barrier pillars	70 feet wide
Average mineable horizon	76 feet
Average shale grade	29 gallons per ton

It is assumed that upgrading the existing dirt roads to the site will be done by the state. Large sized equipment will be field erected.

4.2 OIL SHALE MINING

4.2.1 General

The proposed mining method is a modified room-and-pillar system. The upper 40 feet of the oil shale horizon will utilize a conventional room-and-pillar system, whereas the lower 10 feet will be mined by a benching system. Face and bench mining are to be performed simultaneously.

A production period of three-and-one-half years has been allowed. During this period, a production shaft, man and material shaft and three ventilation shafts will be sunk to the mining zone. The primary crushing stations, underground shops and other needed facilities will also be completed in the period. About 5.5 million tons of development ore and panel preparation ore will be excavated and stockpiled on surface prior to plant startup.

4.2.2 Mine Design and Parameters

Scheduled work year	355 Days
Scheduled work week	30 shifts
Panel extraction	684
Overall extraction	632
Development entries	50 feet wide by 40 feet high
Development pillars	70 feet wide
Panel rooms (upper level)	55 feet wide by 40 feet high
Lower level rooms	55 feet wide by 35 feet high (average)
Panel pillars	60 feet by 88 feet
Panel barrier pillars	70 feet wide
Average mineable horizon	76 feet
Average stria grade	25 gallons per ton

4.2.3 Mining Layout

The mine plan consists of a series of mining panels that are eight rooms wide and 16 crosscuts deep. The rooms and crosscuts are 55 feet wide. Pillars within the panels are 60 feet by 88 feet. Panels will be separated by 70 foot barrier pillars. Each panel will have two ramps for access to the lower level.

4.2.4 Mining Function Description

Drilling. The upper level drilling will be done by specialized drill jumbos, each mounting two rotary drills capable of drilling 4-1/4 inch diameter holes 27 feet deep. The units are to be self-contained with an air compressor and drill water tank. Lower level drilling will be done with vertical rotary drills which are also self-contained.

Charging and Blasting. Ammonium nitrate mixed with fuel oil will be the primary blasting agent. The AN/FO will be placed in blastholes pneumatically. Each hole will be primed with a high strength primer that contains a cap and delay element. The overall powder factor will be 0.51 pounds of explosive for each ton of shale produced.

Loading and Hauling. Large front-end loaders will load the blasted ore into 75 ton haulage trucks. Haulageways will be assigned for one way travel, thereby minimizing interference and delays. Loader requirements will be constant once full production is attained. Truck requirements will increase as haul distances increase.

Scaling and Roof Bolting. Rib and face scaling will be accomplished with mechanical scalers. Roof bolts will be systematically installed in all exposed back by a roof bolting machine.

Primary Crushing and Hoisting. Toothed single roll crushers, 48 inch by 72 inch, will be used to crush shale to minus 12 inch prior to hoisting. Total mine production will be hoisted from a single 38 foot diameter shaft with four 100 ton skips. Primary crushers will be located underground.

4.3 RETORT FEED PREPARATION


The raw shale crushing and screening facilities will be designed to produce a retort feed consist (nominal 3/8 inch x 3 inch) as shown in Figure 4-5.

4.3.1 Raw Shale Stockpiles

Retort feed preparation will begin with hoisting the -12 inch primary crusher product from the mine to the surface for diversion to either the plant surge pile or to a 625,000 ton stockpile. The stockpile will serve as storage for excess mine production to be used during non-productive periods of the mine and as surge capacity when a retort or retort battery is down for scheduled maintenance. The plant surge pile has a capacity of 7000 tons and prevents loss of feed to the secondary crushers.

4.3.2 Secondary Crushers

Primary crushed material (-12 inch) passes over a vibrating grizzly screen with 6" openings. The +6 inch oversize reports to a double roll secondary crusher to be crushed to -6 inch. Secondary crushing is divided into 3 circuits (2 operating, 1 stand-by). The 6 inch undersize from the grizzly screen is combined with the secondary crusher product and conveyed to surge bins.



Retort Feed & Three Stage Crushing Particle Distribution

Three Stage Crushing _____

Retort Feed - - - - -

Figure 4-5

4.3.3 Tertiary Crushers and Screens

The -6 inch material from secondary crushing is discharged from the surge bins across the top deck of a triple deck vibrating screen comprised of 16 parallel circuits. The top deck has 3 inch openings; the second deck has 1 -1/2 inch openings, and the bottom deck 3/8 inch openings. Thus, three separations are produced: +3 inch oversize, -3 inch to +3/8 inch product for retorting, -3/8 inch material unsuitable for retorting.

The +3 inch oversize off the top deck is routed through eight double roll tertiary crushers. Product from the tertiary crushers is recirculated back over the top deck of the triple deck screen. Retort feed is collected from that material passing through the 3 inch top deck screen but withheld by the 3/8 inch lower deck screen. The intermediate 1 -1/2 inch second deck screen serves to improve screen efficiency and reduce loading on the 3/8 inch lower deck screen. Material passing through the 3/8 inch lower deck represents fines and is routed to the retorted shale disposal area as top cover.

4.3.4 Fines Production (see appendix)

The particle size distribution obtained from the three stage crushing scheme described above is shown in Figure 4-5. Fines production (minus 1/2 inch material) amounts to 8.8% of the total mined shale. This is a result of a detailed blasting and crushing study performed by Cleveland-Cliffs Iron Company. The particle size distribution (nominal 3/8 inch x 3 inch) required for retort feed is also shown in Figure 4-5. Thus, out of the 8.8% minus 1/2 inch material, 3.8% of the larger consist may be fed to the retorts. This leaves 5.0% of the total mine production not suitable for retort feed. This is utilized as top cover with retorted shale disposal.

The -5 inch material from secondary crushing is discharged from the surge bins across the top deck of a triple deck vibrating screen comprised of 16 parallel circuits. The top deck has 3 inch openings; the second deck has 1-1/2 inch openings, and the bottom deck 3/8 inch openings. Thus, three separations are produced: +3 inch oversize, -3 inch to +3/8 inch product for reorting, -3/8 inch material unsuitable for reorting.

The +3 inch oversize off the top deck is routed through eight double roll tertiary crushers. Product from the tertiary crushers is recirculated back over the top deck of the triple deck screen. Retort feed is collected from that material passing through the 3 inch top deck screen but withheld by the 3/8 inch lower deck screen. The intermediate 1-1/2 inch second deck screen serves to improve screen efficiency and reduce loading on the 3/8 inch lower deck screen. Material passing through the 3/8 inch lower deck represents fines and is routed to the retorted shale disposal area as top cover.

4.3.4 Fines Production (see appendix)

The particle size distribution obtained from the three stage crushing scheme described above is shown in Figure 4-5. Fines production (minus 1/2 inch material) amounts to 8.8% of the total mined shale. This is a result of a detailed blasting and crushing study performed by Cleveland-Cliffs Iron Company. The particle size distribution (nominal 3/8 inch x 3 inch) required for retort feed is also shown in Figure 4-5. Thus, out of the 8.8% minus 1/2 inch material, 1.8% of the larger consist may be fed to the retorts. This leaves 5.0% of the total mine production not suitable for retort feed. This is utilized as top cover with retorted shale disposal.

4.4 RETORTING

4.4.1 Process Description

The Paraho retort is a refractory lined, cylindrical vertical shaft vessel for processing lump size (nominal 3/8" x 3") shale. Figure 4-6 exhibits the construction to be described herein. The raw shale is fed in the top from a feed hopper and rotating distributor which distributes the lumps evenly across the bed. The shale lumps move downward as a packed bed by gravity with the movement being controlled by the unique grate in the bottom of the retort. In moving downward, the shale first passes the off-gas collector zone, then through a retorting zone (thermal decomposition of kerogen to oil vapor), over the gas distributors and through a cooling zone to the grate. The grate is operated hydraulically and its speed is controlled to give the desired flow of the shale through the retort. The grate causes the column of material to descend uniformly over the cross-section of the retort. The retorted shale is discharged through a pressure seal at the bottom of the retort.

Cool recycle gas enters the bottom of the retort through gas distributors built in the grate. The gas as it ascends through the shale bed is heated by descending retorted shale, which in turn is cooled. Additional heat enters through two levels of gas distributors.

Two levels of heat distribution are used to completely distribute heat uniformly over the cross-section and prevent cold gas channeling. The hot gases ascending above the distributors preheat and retort the shale. The ascending gases and shale oil vapors from retorting are cooled by incoming raw shale; oil is condensed in the form of a stable mist and carried with the gases out of the retort through off-gas collection devices to oil/gas separators for recovery of the oil and recycle of the gases.

4.4 RETORTING

4.4.1 Process Description

The Retort is a refractory lined, cylindrical vertical shaft vessel for processing lump size (nominal 3/8" x 3") shale. Figure 4-5 exhibits the construction to be described herein. The raw shale is fed in the top from a feed hopper and rotating distributor which distributes the lumps evenly across the bed. The shale lumps move downward as a packed bed by gravity with the movement being controlled by the unique grate in the bottom of the retort. In moving downward, the shale first passes the off-gas collector zone, then through a retorting zone (thermal decomposition of kerogen to oil vapor), over the gas distributors and through a cooling zone to the grate. The grate is operated hydraulically and its speed is controlled to give the desired flow of shale through the retort. The grate causes the column of material to descend uniformly over the cross-section of the retort. The retorted shale is discharged through a pressure seal at the bottom of the retort.

Cool recycle gas enters the bottom of the retort through gas distributors built in the grate. The gas as it ascends through the shale bed is heated by descending retorted shale, which in turn is cooled. Additional heat enters through two levels of gas distributors. Two levels of heat distribution are used to completely distribute heat uniformly over the cross-section and prevent cold gas channeling. The hot gases ascending above the distributors preheat and retort the shale. The ascending gases and shale oil vapors from retorting are cooled by incoming raw shale; oil is condensed in the form of a stable mist and carried with the gases out of the retort through off-gas collection devices to oil/gas separators for recovery of the oil and recycle of the gases.


Paraho


The Paraho retort is based on the counter-current, gas-to-shale heat exchanger effect. Three processes have been developed using the above principles.

The Direct Heated Process. In the direct heated process, shale is heated by a gas-to-shale heat exchanger. The shale is then retorted in the retort. The retort is a vertical cylinder with a rotating solids distributor at the top. The distributor is a rotating drum with slots that allow the shale to fall into the retort. The retort is lined with refractory. The retort is heated by a gas-to-shale heat exchanger. The gas enters the retort at the bottom and flows upward. The shale enters the retort at the top and flows downward. The gas and shale are in contact for a long time, allowing the shale to be heated and retorted. The gas exits the retort at the top and flows into off-gas collectors. The shale exits the retort at the bottom and flows into a discharge chute.

The Indirect Heated Process. In the indirect heated process, the shale is heated by a gas-to-shale heat exchanger. The shale is then retorted in the retort. The retort is a vertical cylinder with a rotating solids distributor at the top. The distributor is a rotating drum with slots that allow the shale to fall into the retort. The retort is lined with refractory. The retort is heated by a gas-to-shale heat exchanger. The gas enters the retort at the bottom and flows upward. The shale enters the retort at the top and flows downward. The gas and shale are in contact for a long time, allowing the shale to be heated and retorted. The gas exits the retort at the top and flows into off-gas collectors. The shale exits the retort at the bottom and flows into a discharge chute.

The Combination Process. In the combination process, the shale is heated by a gas-to-shale heat exchanger. The shale is then retorted in the retort. The retort is a vertical cylinder with a rotating solids distributor at the top. The distributor is a rotating drum with slots that allow the shale to fall into the retort. The retort is lined with refractory. The retort is heated by a gas-to-shale heat exchanger. The gas enters the retort at the bottom and flows upward. The shale enters the retort at the top and flows downward. The gas and shale are in contact for a long time, allowing the shale to be heated and retorted. The gas exits the retort at the top and flows into off-gas collectors. The shale exits the retort at the bottom and flows into a discharge chute.





McKibb
 ENGINEERING CORPORATION
 10000 WILSON AVENUE
 BOSTON, MASS. 02116

BRAND COMMERCIAL
 EVALUATION STUDY

FIG-6

PARADO RETORT

The Paraho retort is basically a counter-current gas-to-shale heat exchanger effecting thermal efficiency. Three processes have been developed utilizing the above principles.

The Direct Heated Process. Products of retorting are gas, oil, and residual coke on the retorted shale. In the direct heated process shown in Figure 4-7, residual coke and gas are burned in the retort by the addition of air at the distributors to heat the process. Recycle gas flows and air injection are controlled to provide enough hot gases to retort the shale in the zone above the top distributor. Air addition at the distributors is diluted by recycle gas to moderate extreme localized temperatures at the point of combustion. The net gas produced in the direct heated process has a lower heating value (118 Btu/SCF) due to the retort gases being diluted by products of combustion and nitrogen.

The Indirect Heated Process. The Indirect Heated process is presented in Figure 4-8. This method eliminates combustion within the retort and, therefore, produces product gas of higher value (808 Btu/SCF). The residual coke produced in retorting remains on the retorted shale. The process heat is supplied by recycling gas through heaters, and the hot gas is then injected into the retort at the two distributor levels. The temperature and quantity of the entering hot gases are controlled to provide sufficient heat to retort the shale above the top distributor when combined with the ascending preheated gases added at the grate.


The Combination Process. The combination process uses both hot gas addition at the top distributor and air injection at the mid distributor (refer to Figure 4-9). Air injection at the mid distributor allows utilization of the residual carbon by combustion to assist the top gas heaters in fueling the

The retort is basically a counter-current gas-to-shale heat exchanger effecting thermal efficiency. Three processes have been developed utilizing the above principles.

The Direct Heated Process. Products of retorting are gas, oil, and residual coke on the retorted shale. In the direct heated process shown in Figure 4-7, residual coke and gas are burned in the retort by the addition of air at the distributor to heat the process. Retort gas flows and air injection are controlled to provide enough hot gases to retort the shale in the zone above the top distributor. Air addition at the distributor is diluted by retort gas to moderate extreme localized temperatures at the point of combustion. The hot gas produced in the direct heated process has a lower heating value (115 Btu/SCF) due to the retort gases being diluted by products of combustion and nitrogen.

The Indirect Heated Process. The Indirect Heated process is presented in Figure 4-8. This method eliminates combustion within the retort and, therefore, produces product gas of higher value (160 Btu/SCF). The residual coke produced in retorting remains on the retorted shale. The process heat is supplied by retorting gas through heaters, and the hot gas is then injected into the retort at the two distributor levels. The temperature and quantity of the entering hot gases are controlled to provide sufficient heat to retort the shale above the top distributor when combined with the ascending preheated gases added at the grate.

The Combination Process. The combination process uses both hot gas addition at the top distributor and air injection at the mid distributor (refer to Figure 4-9). Air injection at the mid distributor allows utilization of the residual carbon by combustion to assist the top gas heaters in fueling the




NOTE: This Print is the property of
PARAHO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
furnished by us.


**PARAHO COMMERCIAL
EVALUATION STUDY**

**PARAHO DIRECT
HEATED PROCESS**

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG. 4-7





NOTE: This Print is the property of PARAHO DEVELOPMENT CORPORATION. It must not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.


PARAHO COMMERCIAL
EVALUATION STUDY


PARAHO INDIRECT
HEATED PROCESS

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG. 4-8








NOTE: This Report is the property of PARAH0 DEVELOPMENT CORPORATION. It must not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.

PARAH0 COMMERCIAL
EVALUATION STUDY

PARAH0 COMBINATION
HEATED PROCESS

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG. 4-9



BARANO COMMERCIAL
EVALUATION STUDY

BARANO COMMERCIAL
HEATED PROCESS

FIG. 4-9

McKAY
TECHNICAL CONSULTING
DESIGNER

process. A net product gas of intermediate heating value (300 Btu/SCF) is produced.

Consideration of the combination process will not be included in the Commercial Evaluation Study due to the lack of definitive data and an extended demonstration run.

4.4.2 The Paraho Oil Shale Demonstration

Two Paraho retorts were erected at Anvil Points. The Pilot Plant retort was a nominal 2-1/2 feet in internal diameter and served the primary purpose of testing operating conditions applicable to later trial in the larger 8-1/2 foot nominal diameter Semi-Works retort.

Retort operations for the Paraho Oil Shale Demonstration began with cold flow rock tests in the Pilot Plant on April 9, 1974 and the Semi-Works on August 23, 1974. A total of 19 runs with the Pilot Plant and 31 runs with the Semi-Works were completed through April 12, 1976. Runs in both retorts were established on the basis of key objectives. Continual progress was made throughout the demonstration project in establishing startup procedures, operating conditions, mechanical design, efficient operation, and extended operability. Runs given in the following Table 4-1 are particularly noteworthy since extended operability with high on-stream time was demonstrated.

process. A net product gas of intermediate heating value (300 Btu/SCF) is produced.

Consideration of the combination process will not be included in the Commercial Evaluation Study due to the lack of definitive data and an extended demonstration run.

4.4.2 The Paraho Oil Shale Demonstration

Two Paraho reactors were erected at Anvil Point. The Pilot Plant reactor was a nominal 2-1/2 feet in internal diameter and served the primary purpose of testing operating conditions applicable to later trial in the larger 8-1/2 foot nominal diameter Semi-Works reactor.

Reactor operations for the Paraho Oil Shale Demonstration began with cold flow rock tests in the Pilot Plant on April 9, 1974 and the Semi-Works on August 23, 1974. A total of 19 runs with the Pilot Plant and 31 runs with the Semi-Works were completed through April 12, 1976. Runs in both reactors were established on the basis of key objectives. Continuous progress was made throughout the demonstration project in establishing startup procedures, operating conditions, mechanical design, efficient operation, and extended operability. Runs given in the following Table 4-1 are particularly noteworthy since extended operability with high on-stream time was demonstrated.

4.1.1 Criteria for Design Basis Selection

Selection of a commercial design basis for Direct Heated and Indirect Heated retorting on analysis of the Semi-Works and Pilot Plant runs and periods within the runs. Key criteria used in the selection of a run or test period applicable to the demonstrated operability design basis were as follows:

TABLE 4-1

PARAHO RETORTS

DEMONSTRATED OPERABILITY

<u>Retort</u>	<u>Run No.</u>	<u>Process</u>	<u>Run Length (Days)</u>	<u>% On-Stream Time</u>
Pilot Plant	16	Direct Heated	77.0	99.1
Pilot Plant	18	Direct Heated	27.3	94.6
Pilot Plant	19	Direct Heated	12.1	99.8
Semi-Works	7	Direct Heated	56.0	88.4
Semi-Works	20	Direct Heated	25.6	99.7
Semi-Works	23	Indirect Heated	31.2	99.6
Semi-Works	28	Indirect Heated	10.6	100.0

TABLE 4-1
PARANO REPORTS
DEMONSTRATED OPERABILITY

Report	Run No.	Process	Run Length (Days)	# On-Stream Time
Pilot Plant	16	Direct Heated	77.0	99.1
Pilot Plant	18	Direct Heated	27.3	94.8
Pilot Plant	19	Direct Heated	12.1	99.8
Semi-Works	7	Direct Heated	26.0	88.4
Semi-Works	20	Direct Heated	25.6	99.7
Semi-Works	23	Indirect Heated	31.2	99.6
Semi-Works	28	Indirect Heated	10.6	100.0

4.4.3 Criteria for Design Basis Selection

Selection of a commercial design basis for Direct Heated and Indirect Heated retorting was based on analysis of the Semi-Works and Pilot Plant runs and test periods within the runs. Key criteria used in the selection of a run or test period applicable to the selection of a commercial design basis were as follows:

- 1) Run length or test period duration should be of extended length. On-stream time during the run should be high.
- 2) Test periods should preferably be consecutive and under closely similar operating conditions. A retest of operating conditions is desirable to verify data reproducibility.
- 3) Operation should have minimal upsets particularly those process related.
- 4) Post-run inspection of the retort and auxiliary equipment should be satisfactory. The retort should be free of agglomerations; air/gas distributor holes should be open; off-gas piping and oil recovery equipment should be free of sludge.
- 5) Oil yield should be high.
- 6) Mass rates should be reasonably high.
- 7) Operation should be thermally efficient.
- 8) Data and sample collection should be reliable and laboratory analysis sound.

Criteria for Design Basis Selection

4.4.1

Selection of a commercial design basis for Direct Heated and Indirect Heated retorting was based on analysis of the Semi-Works and Pilot Plant runs and test periods within the runs. Key criteria used in the selection of a run or test period applicable to the selection of a commercial design basis were as follows:

- 1) Run length or test period duration should be of extended length. On-stream time during the run should be high.
- 2) Test periods should preferably be consecutive and under closely similar operating conditions. A repeat of operating conditions is desirable to verify data reproducibility.
- 3) Operation should have minimal upsets particularly those process related.
- 4) Post-run inspection of the retort and auxiliary equipment should be satisfactory. The retort should be free of agglomerations; air/gas distributor holes should be open; off-gas piping and oil recovery equipment should be free of sludge.
- 5) Oil yield should be high.
- 6) Mass rates should be reasonably high.
- 7) Operation should be thermally efficient.
- 8) Data and sample collection should be reliable and laboratory analysis sound.

- 9) Operating conditions should be as economically viable as possible.
- 10) A design basis derived from the Semi-Works retort would be preferable since the scale-up factor to a commercial retort is less than with the Pilot Plant.

4.4.4 Design Basis - Direct Heated Process

Semi-Works Run No. 20 (SW-20) best satisfies the criteria listed previously. Run length and interruptions to operating time are given in Table 4-2, Summary of Operating Time. Test period conditions during the run were designed to explore various air ratios to the top and middle air/gas distributors. Five consecutive 24 hour test periods designated as Test A conditions using 82% of total air to the top air/gas distributor and 18% in the middle air/gas distributor were obtained. Operation during the five days was stable with the exception of two brief power failures, the effects of which were negligible. Toward the end of Run No. 20, a retest of Test A conditions was made for five consecutive 24 hour test periods to verify data reproducibility.

The post-run inspection was satisfactory. The retort internals showed no evidence of agglomerated material in the retort or indicated from markings on the refractory walls. The refractory walls were clean and polished from shale movement but without evidence of coke or shale adhering to the walls or eroding the refractory. The outside surface of the air/gas distributors were clean and orifice holes were open and clear of coke or buildup from the run. The off-gas collectors and external piping manifold were clean and free of sludge buildup.

The reliability of data taken during Semi-Works Run No. 20 is considered as excellent. The number of laboratory samples taken both routine and special were extensive. The results

Operating conditions should be as economically viable as possible.

10) A design basis derived from the Semi-works report would be preferable since the scale-up factor to a commercial reactor is less than with the Pilot Plant.

4.4.4 Design Basis - Direct Heated Process

Semi-works Run No. 20 (SW-20) best satisfies the criteria listed previously. Run length and interruptions to operating time are given in Table 4-2, Summary of Operating Time. Test period conditions during the run were designed to explore various air ratios to the top and middle air/gas distributors. Five consecutive 24 hour test periods designated as Test A conditions using 85% of total air to the top air/gas distributor and 15% in the middle air/gas distributor were obtained. Operation during the five days was stable with the exception of two brief power failures, the effects of which were negligible. Toward the end of Run No. 20, a recent of Test A conditions was made for five consecutive 24 hour test periods to verify data reproducibility.

The post-run inspection was satisfactory. The reactor internals showed no evidence of agglomerated material in the reactor or indicated from markings on the refractory walls. The refractory walls were clean and polished from shale movement but without evidence of coke or shale adhering to the walls or eroding the refractory. The outside surface of the air/gas distributors were clean and orifice holes were open and clear of coke or buildup from the run. The oil-gas collectors and external piping manifold were clean and free of residue buildup.

The reliability of data taken during Semi-works Run No. 20 is considered as excellent. The number of laboratory samples taken both routine and special were extensive. The results

TABLE NO. 4-2
SEMI-WORKS RUN NO. SW-20

SUMMARY OF OPERATING TIME

DATE	OPERATING TIME HOURS	TIME ON-STREAM		TIME LOST		REMARKS OR REASON FOR OUTAGE
		DAYS	HOURS	DAYS	HOURS	
11-04-75	2143					Fire Off
11-07-75	1145	2	14.02		0.13	Power Failure
11-09-75	0405	1	16.20		0.07	Power Failure
11-14-75	1100	5	6.85		0.33	Power Failure
11-17-75	1558	3	4.63		0.82	Standby to repair splice on ret. shale conveyor.
11-18-75	1127		18.67		0.22	Power Failure
11-28-75	1055	9	23.25		0.02	Power Failure
11-30-75	1140	2	0.73		--	Shutdown
TOTAL		25	12.36		1.59	99.74% operating time

Shale Grade. A shale grade of 29 gallons per ton was dictated for the Commercial Evaluation Study because it is a physical feature of the site selection. During Semi-Works Run No. 20, 32 out of 139 eight hour periods (23%) operated with greater than 29 gallon per ton shale feed; similarly, 28 out of 128 (22%) in Pilot Plant Run No. 16, 10 out of 24 (42%) in Pilot Plant Run No. 18. Both retorts also had excursions in shale grade of greater than 30 gpt for several eight hour periods. Based on the above, sustained operation with 29 gpt shale is feasible.

TABLE NO. 4-2

SEMI-WORKS RUN NO. SW-20

SUMMARY OF OPERATING TIME

DATE	OPERATING TIME HOURS	ON-STREAM TIME DAYS	ON-STREAM TIME HOURS	LOST TIME DAYS	LOST TIME HOURS	REMARKS OR REASON FOR OUTAGE
11-04-75	2143					Fire Off
11-07-75	1145	2	18.02		0.13	Power Failure
11-09-75	0402	1	16.30		0.07	Power Failure
11-14-75	1108	8	8.82		0.33	Power Failure
11-17-75	1228	3	4.83		0.82	Standby to repair splice on ret. shaft conveyor.
11-18-75	1127		18.47		0.32	Power Failure
11-28-75	1022	9	23.22		0.02	Power Failure
11-30-75	1140	2	0.73		--	Shutdown
TOTAL		22	12.36		1.29	99.74% operating time

of oil rundown tank calibrations, raw shale and retorted shale weigh belt checks, and gas losses through the rotary discharge seals were all incorporated into the data. Product gas samples were taken and analyzed by Atlantic Richfield Company. Oil samples were sent to Sohio Petroleum Company for crude assay. (For details see Appendix.)

The core of the commercial design basis for Direct Heated retorting was formulated by combination of the test periods run under Test A conditions. A review of all data from Test A conditions is summarized in Table 4-3. Test period A-6 and A-7 were excluded since the operating conditions deviate from the other Test A periods to a greater degree. The repeatability of the data and degree of control are indicated by the standard deviations. This combination of test periods represents 303 stable operating hours. A data summary calculated by weight averaging the individual test period data on the basis of test period length is given in Table 4-4.

Design parameters for the commercial retort were basically extracted from the data summary Table 4-4. Various figures were rounded off. The following design parameters differ from those in Table 4-4, and justification and reason for such deviations are described.

Shale Grade. A shale grade of 29 gallons per ton was dictated for the Commercial Evaluation Study because it is a physical feature of the site selection. During Semi-Works Run No. 20, 32 out of 139 eight hour periods (23%) operated with greater than 29 gallon per ton shale feed; similarly, 29 out of 128 (23%) in Pilot Plant Run No. 16, 10 out of 24 (42%) in Pilot Plant Run No. 19. Both retorts also had excursions in shale grade of greater than 30 gpt for several eight hour periods. Based on the above, sustained operation with 29 gpt shale is feasible.

of all run-down tank calibrations, raw shale and retested shale weigh belt checks, and gas losses through the rotary discharge seals were all incorporated into the data. Production gas samples were taken and analyzed by Atlantic Richfield Company. Oil samples were sent to Sohio Petroleum Company for crude assay. (For details see Appendix.)

The core of the commercial design basis for Direct Heated retorting was formulated by combination of the test periods run under Test A conditions. A review of all data from Test A conditions is summarized in Table 4-3. Test period A-6 and A-7 were excluded since the operating conditions deviate from the other Test A periods to a greater degree. The repeatability of the data and degree of control are indicated by the standard deviations. This combination of test periods represents 303 stable operating hours. A data summary calculated by weight averaging the individual test period data on the basis of test period length is given in Table 4-4.

Design parameters for the commercial retort were basically extracted from the data summary Table 4-4. Various figures were rounded off. The following design parameters differ from those in Table 4-4, and justification and reason for such deviations are described.

Shale Grade. A shale grade of 25 gallons per ton was dictated for the Commercial Evaluation Study because it is a physical feature of the site selection. During Semi-Works Run No. 20, 32 out of 139 eight hour periods (23%) operated with greater than 25 gallon per ton shale feed; similarly, 29 out of 138 (21%) in Pilot Plant Run No. 16, 10 out of 24 (42%) in Pilot Plant Run No. 19. Both retorts also had excursions in shale grade of greater than 30 gpt for several eight hour periods. Based on the above, sustained operation with 25 gpt shale is feasible.

TABLE NO. 4-3

DEVIATION OF OPERATING VARIABLES AND YIELDS
SEMI-WORKS RUN NO. SW-20 TEST A CONDITIONS
TESTS NOS. A-1, 2, 3, 4, 5, 9, 10, 11, 12
13, 14, 15 AND 16

ITEM	MEAN	STANDARD DEVIATION
Raw Shale Rate, TPH	11.17	0.27
Raw Shale F.A., GPT	27.21	0.52
Oil Yield (DRY), GPH	277.40	9.67
Oil Water Content, WT%	4.84	2.58
Oil Yield, Vol% F.A.	91.27	4.48
Oil Yield, Wt% F.A.	91.56	4.53
Air to Top Dist., SCFM	709.29	7.95
Air to Mid Dist., SCFM	158.24	1.96
Gas to Top Dist., SCFM	253.19	3.09
Gas to Mid Dist., SCFM	245.74	3.72
Gas to Bottom Dist., SCFM	2254.48	23.37
Gas to Product, SCFM	1340.40	27.54

6-1-15

TABLE NO. 4-1

DEVIATION OF OPERATING VARIABLES AND YIELDS
SEMI-WORKS RUN NO. SW-20 TEST A CONDITIONS
TESTS NOS. A-1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12
13, 14, 15 AND 16

ITEM	MEAN	STANDARD DEVIATION
Raw Shale Rate, TPN	11.17	0.27
Raw Shale F.A., GPT	27.21	0.22
Oil Yield (DRT), GPH	277.40	2.67
Oil Water Content, WTS	4.84	2.28
Oil Yield, Vol% F.A.	91.27	4.48
Oil Yield, Wts F.A.	91.26	4.23
Air to Top Dist., SCFM	709.29	7.92
Air to Mid Dist., SCFM	158.24	1.96
Gas to Top Dist., SCFM	253.19	3.09
Gas to Mid Dist., SCFM	245.74	3.72
Gas to Bottom Dist., SCFM	2254.48	23.37
Gas to Product, SCFM	1340.40	27.24

TABLE NO. 4-4

DATA SUMMARY

Sheet 1 of 2

Run No. SW-20
 Test No. Combined A-1,2,3,4
 5,9,10,11,
 12,13,14,15
 & 16
 Length, Hours 303

TEMPERATURES
 Product Oil Out^{OF} 139
 Retorted Shale Out^{OF} 384
 Raw Shale In ^{OF} 36
 Air ^{OF} 184
 Product & Recycle Gas ^{OF} 241
 Offgas Temperature ^{OF} 145
 Dist. Cooling H₂O In, ^{OF} 116
 Dist. Cooling H₂O Out, ^{OF} 134

RATES AND QUANTITIES

Air
 Top SCF/Ton 3810
 Mid SCF/Ton 850
 Bottom SCF/Ton 0
 Total SCF/Ton 4660

YIELDS
 Oil Collected Gal/Ton 24.82
 Oil Collected Vol% F.A. 91.27
 Product Gas SCF/Ton 7200
 Retorted Shale Wt% R.S. 81.0
 Retorted Shale Tph 9.05
 Liquid Water lbs/Ton 9.67
 Material Recovery Wt% 99

Recycle
 Top SCF/Ton 1360
 Mid SCF/Ton 1320
 Bottom SCF/Ton 12110
 Total SCF/Ton 14790

Raw Shale Tph 11.17

MISCELLANEOUS
 Retort dp in H₂O/ft bed 1.00
 Carbonate Decomp. Wt% 27
 Retort Bed Height, Ft.In. 25'-6"
 Throughput, lbs/hr/ft² 454
 Barometric Press. In Hg. 23.94
 Relative Humidity % (Air) 61
 Ambient Air ^{OF} 36

RETORTED SHALE PROPERTIES

Fischer Assay Gal/Ton 0.28
 Mineral CO₂ Wt% 15.86
 Organic Carbon Wt% 1.37
 F.A. Wet Oil 6.18
 F.A. Wet Water 0.16
 F.A. Wet Gas + Loss 0.29
 Ignition Loss Wt% 17.72
 Carbon Wt% 6.26
 Hydrogen Wt% 0.17
 Nitrogen Wt% 0.21

CO₂ 0.87
 C₂H₄ 0.52
 C₂H₆ 0.71
 C₃'s 0.38
 C₄'s 0.41
 C₅'s 0.23
 H₂ 0.21
 NH₃ 0.21

VOL% MOISTURE 17.33

DATA SUMMARY

Sheet 1 of 2

TEMPERATURES		SW-20		Run No.	
Product Oil Out	139	A-1, 2, 3, 4	5.9, 10, 11	Test No. Combined	
Retorted Shale Out	384	12, 13, 14, 15	4.16	Length, Hours	
Raw Shale In	36			RATES AND QUANTITIES	
Air	184			Air	
Product & Recycle Gas	241			Top SCF/Ton	3810
Offgas Temperature	145			Mid SCF/Ton	850
Dist. Cooling H ₂ O In	116			Bottom SCF/Ton	0
Dist. Cooling H ₂ O Out	134			Total SCF/Ton	4660
YIELDS				Recycle	
Oil Collected Gal/Ton	24.82			Top SCF/Ton	1380
Oil Collected Vol% W.A.	91.27			Mid SCF/Ton	1320
Product Gas SCF/Ton	7500			Bottom SCF/Ton	1310
Retorted Shale Wt R.S.	81.0			Total SCF/Ton	14790
Retorted Shale Tph	9.05			Raw Shale Tph	11.17
Liquid Water lbs/Ton	9.67				
Material Recovery Wt%	99				
MISCELLANEOUS					
Retort hp in H ₂ O/t bed	1.00				
Carbonates Decomp. Wt%	27				
Retort Bed Height, Ft. In.	25'-6"				
Throughput, lbs/hr/ft ²	454				
Barometric Press. in Hg.	23.94				
Relative Humidity % (Air)	61				
Ambient Air	36				

TABLE 4-4 - Cont.

DATA SUMMARY

Sheet 2 of 2

Run No. SW-20
Test No. Comb. Test A's

RAW SHALE PROPERTIES

Moisture Content Wt%	0.96
Fischer Assay Gal/Ton	27.2
F.A. Wt% Oil	10.39
F.A. Wt% Water	1.66
F.A. Wt% Gas + Loss	2.29
Mineral CO ₂ Wt%	17.71
Ignition Loss Wt%	33.07
Carbon Wt%	17.05
Hydrogen Wt%	1.84
Nitrogen Wt%	0.51

PRODUCT OIL PROPERTIES

Gravity, Deg. API	21.4
Viscosity SUS @ 130°	89.9
Viscosity SUS @ 210°	46.5
Ramsbottom Carbon Wt%	1.73
Water Content Vol%	4.46
Solids, BS, Wt%	0.47
Carbon Wt%	84.62
Hydrogen Wt%	11.50
Nitrogen Wt%	2.00

PRODUCT GAS PROPERTIES (Dry)

Gross Heat. Value	118
Btu/scf	
Specific Gravity	1.1

RETORTED SHALE PROPERTIES

Fischer Assay Gal/Ton	0.28
Mineral CO ₂ Wt%	15.86
Organic Carbon Wt%	1.97
F.A. Wt% Oil	0.10
F.A. Wt% Water	0.16
F.A. Wt% Gas + Loss	0.29
Ignition Loss Wt%	17.72
Carbon Wt%	6.30
Hydrogen Wt%	0.17
Nitrogen Wt%	0.21

SCREEN ANALYSIS

Size - Inches	Amount - Wt%
3.00	0
2.50	2.1
2.00	13.1
1.50	32.8
1.05	21.7
0.742	15.3
0.525	9.9
0.371	1.4
0.263	1.3
0.185	0.5
0.093	0.7

Pan	1.2
Loss	0

GAS ANALYSIS, VOL% (Dry)

H ₂	2.50
N ₂	65.45
O ₂	0.01
CO	2.51
CH ₄	2.19
CO ₂	24.14
C ₂ H ₄	0.67
C ₂ H ₆	0.62
C ₃ 's	0.71
C ₄ 's	0.36
C ₅ +s	0.41
H ₂ S	0.22
NH ₃	0.21

VOL% Moisture	17.55
---------------	-------

TABLE 4-4 - Cont.

DATA SUMMARY

Sheet 3 of 3

Run No. SW-20
Test No. Comp. Test A's

ROCK ANALYSIS

Amount - Wt%	Size - Inches
0	3.00
2.1	2.50
17.1	2.00
32.8	1.50
21.7	1.00
12.3	0.75
8.9	0.50
1.4	0.375
1.3	0.25
0.2	0.1875
0.7	0.09375
1.3	pan
0	loss

GAS ANALYSIS, VOL% (dry)

17.22	Moisture
0.21	NH ₃
0.22	H ₂
0.41	C ₂ H ₆
0.38	C ₃ H ₈
0.71	C ₄ H ₁₀
0.62	C ₅ H ₁₂
0.87	C ₆ H ₁₄
24.14	CO ₂
2.19	CH ₄
2.21	CO
0.01	O ₂
62.42	N ₂
1.20	Ar

RAW SHALE PROPERTIES

0.21	Nitrogen Wt%
0.27	Hydrogen Wt%
1.84	Carbon Wt%
17.02	Ignition loss Wt%
17.71	Mineral CO ₂ Wt%
2.23	P.A. Wt% Gas + Loss
1.66	P.A. Wt% Water
10.39	P.A. Wt% Oil
27.2	Fischer Assay Gal/Ton
0.95	Moisture Content Wt%

PRODUCT OIL PROPERTIES

3.00	Nitrogen Wt%
11.50	Hydrogen Wt%
84.62	Carbon Wt%
0.47	Solids, 85, Wt%
4.46	Water Content Vol%
1.73	Residual Carbon Wt%
46.2	Viscosity SUS @ 100°
89.9	Viscosity SUS @ 150°
21.4	Gravity, Deg. API

PRODUCT GAS PROPERTIES (dry)

1.1	Specific Gravity
118	Gross Heat Value Btu/scf

RETORTED SHALE PROPERTIES

0.21	Nitrogen Wt%
0.17	Hydrogen Wt%
0.30	Carbon Wt%
17.72	Ignition loss Wt%
0.23	P.A. Wt% Gas + Loss
0.16	P.A. Wt% Water
0.10	P.A. Wt% Oil
1.97	Organic Carbon Wt%
15.88	Mineral CO ₂ Wt%
0.28	Fischer Assay Gal/Ton

Shale Mass Rate. Raw shale throughput for the combined Test A periods of Semi-Works Run No. 20 averaged 11.17 tons per hour (dry) or 453.6 lb/hr/ft². Shale mass rate for the Commercial Evaluation Study has been adjusted to 455.5 lbs/hr/ft² for the purpose of having a discrete number of retorts (24) and 100,000 BPSD crude shale oil production. Four batteries of six retorts will be used.

Product Gas Quality. Product gas quality (dry, H₂S, NH₃ Free) is based on Atlantic Richfield Company's sampling and analysis of the product gas during Semi-Works Run No. 20. ARCO's gas samples were taken on 11/25/75 during test period A-13. (See Appendix for details.) Concentration of hydrogen sulfide, ammonia, and water were included from the average values measured by the Paraho laboratory.

Product Oil Properties. Oil samples were taken during Semi-Works Run No. 20. Sohio Petroleum Company performed a final limited assay of this crude shale oil and have supplied the results for the purposes of the Commercial Evaluation Study. (See Appendix for details.)

Raw Shale Feed Screen Analysis. Tylab screen analysis for raw shale feed during the combined Test A periods of Semi-Works Run 20 averaged as given in Table 4-4. As the basis for the blasting and crushing study performed by Cleveland-Cliffs Iron Company to determine fines production, (the results of which were described in Section 4.3), a two-day (11/10/75 - 11/12/75) average screen analysis was taken during Semi-Works Run No. 20. This screen analysis is nearly equivalent, particularly in the percentage of fines, to the combined Test A average. Thus, to prevent discrepancy with the blasting and crushing study, the two-day screen analysis will be used for commercial retort feed.

WESTON BOND

25 KODAK BOND

In Table 4-5, the commercial design basis for the Paraho Direct Heated process is summarized utilizing the information from Table 4-4 with the modifications described above.

4.4.5 Design Basis - Indirect Heated Process

The following discussion will cite two Semi-Works runs which were significant in formulating a commercial retort design basis for indirect heated retorting.

Semi-Works Run Number 23. Semi-Works Run No. 23 (SW-23) demonstrated extended operability. A variable study to improve thermal efficiency was made as the run progressed. The run length and interruptions to operating time are given in Table 4-6. As mentioned above, the test periods were designed to progressively improve thermal efficiency as shown in Table 4-7. Thermal efficiency was basically accomplished by shifting total recycle gas input from the top distributor to the bottom distributor with corresponding increase in the top gas temperature. Thus, the recovery of heat in the retorted shale was greater. A measure of thermal efficiency is the enthalpy of the top distributor gas, since this represents energy the external recycle gas heaters must supply.

Semi-Works Run Number 28. Semi-Works Run No. 28 (SW-28) concentrated on retesting and further improving the thermal efficiencies of the later test periods of Semi-Works Run No. 23. The percentage on-stream time was 100% for the 10.6 day period. Three momentary (less than 5 minutes) heater outages did occur, but their effect is considered negligible. Test periods were designed in an effort to determine the operating conditions that minimize carbonate decomposition yet exhibit complete retorting resulting in maximum thermal efficiency. Table 4-8 shows the results of those test

In Table 4-5, the commercial design basis for the Paraho Direct Heated process is summarized utilizing the information from Table 4-4 with the modifications described above.

4.4.5 Design Basis - Indirect Heated Process

The following discussion will cite two Semi-Works runs which were significant in formulating a commercial retort design basis for indirect heated retorting.

Semi-Works Run Number 23, Semi-Works Run No. 23 (SW-23) demonstrated extended operability. A variable study to improve thermal efficiency was made as the run progressed. The run length and interruptions to operating time are given in Table 4-6. As mentioned above, the test periods were designed to progressively improve thermal efficiency as shown in Table 4-7. Thermal efficiency was basically accomplished by shifting total recycle gas input from the top distributor to the bottom distributor with corresponding increase in the top gas temperature. Thus, the recovery of heat in the retorted shale was greater. A measure of thermal efficiency is the enthalpy of the top distributor gas, since this represents energy the external recycle gas heaters must supply.

Semi-Works Run Number 28, Semi-Works Run No. 28 (SW-28) concentrated on retesting and further improving the thermal efficiencies of the later test periods of Semi-Works Run No. 23. The percentage on-stream time was 100% for the 10.6 day period. Three moments (less than 5 minutes) heater outages did occur, but their effect is considered negligible. Test periods were designed in an effort to determine the operating conditions that minimize carbonate decomposition yet exhibit complete retorting resulting in maximum thermal efficiency. Table 4-8 shows the results of these test

TABLE NO. 4-5

PARAHO DIRECT HEATED RETORT

COMMERCIAL DESIGN BASIS

Rates and Quantities

Shale Mass Rate, lbs/hr/ft ²	455.5
Air to Top Distributor, SCF/Ton	3810
Air to Middle Distributor, SCF/Ton	850
Total Air, SCF/Ton	4660
Recycle to Top Distributor, SCF/Ton	1360
Recycle to Middle Distributor, SCF/Ton	1320
Recycle to Bottom Distributor, SCF/Ton	12110
Total Recycle, SCF/Ton	14790
Distributor Cooling Water, gal/ton	430

Yields

Raw Shale Grade, gpt	29
Oil Collected, Vol.% Fischer Assay	92
Product Gas, SCF/Ton	7200
Retorted Shale, wt.% Raw Shale	81

Temperatures

Offgas, °F	150
Retorted Shale, °F	380
Distributor Cooling Water Rise, °F	18
SUS @ 500°F	Too Heavy
SUS @ 1000°F	162.9
SUS @ 1400°F	71.0
SUS @ 2100°F	41.1
Total Sulfur, Wt%	0.63
Total Nitrogen, Wt%	1.90
Bottoms Carbon, Wt%	1.59
H ₂ & N ₂ , Vol%	0.14
Carbon, Wt%	84.20
Hydrogen, Wt%	11.69
Oxygen, Wt%	1.24

TABLE NO. 4-2
PARANO DIRECT HEATED RETORT
COMMERCIAL DESIGN BASIS

Rates and Quantities

452.2	Shale Mass Rate, lbs/hr/ft ²
3810	Air to Top Distributor, SCF/Ton
820	Air to Middle Distributor, SCF/Ton
4660	Total Air, SCF/Ton
1360	Recycle to Top Distributor, SCF/Ton
1320	Recycle to Middle Distributor, SCF/Ton
1210	Recycle to Bottom Distributor, SCF/Ton
14790	Total Recycle, SCF/Ton
430	Distributor Cooling Water, gal/ton

Yields

29	Raw Shale Grade, ppt
92	Oil Collected, Vol. % Fischer Assay
7200	Product Gas, SCF/Ton
81	Retorted Shale, wt. % Raw Shale

Temperatures

150	Offgas, °F
380	Retorted Shale, °F
18	Distributor Cooling Water Rise, °F

PRODUCT GAS:

	Wet Vol%	Dry Vol%
H ₂	3.59	4.36
O ₂ + Ar	0.76	0.92
N ₂	52.89	64.15
Cl	1.90	2.30
CO	1.63	1.98
CO ₂	17.93	21.75
C ₂ (E)	0.76	0.92
C ₂	0.78	0.94
C ₃ (E)	0.37	0.45
C ₃	0.39	0.47
C ₄ s (MW=57.0)	0.33	0.40
C ₅ s (MW=71.5)	0.13	0.16
C ₆ + (MW=96.2)	0.63	0.77
H ₂ S	0.18	0.22
NH ₃	0.17	0.21
H ₂ O	17.56	--
	100.00	100.00

PRODUCT OIL:

Gravity, °API	21.2
Specific Gravity @ 60°F	0.9267
Pourpoint, °F	80
Viscosity	
SUS @ 60°F	Too Heavy
SUS @ 100°F	162.9
SUS @ 140°F	71.0
SUS @ 210°F	41.3
Total Sulfur, Wt%	0.63
Total Nitrogen, Wt%	1.90
Ramsbottom Carbon, Wt%	1.59
BS & W, Vol%	0.14
Carbon, Wt%	84.20
Hydrogen, Wt%	11.69
Oxygen, Wt%	1.24

PRODUCT GAS:

Wet Vol%	Dry Vol%
17.56	100.00
0.17	0.21
0.18	0.22
0.63	0.77
0.13	0.16
0.33	0.40
0.39	0.47
0.37	0.45
0.78	0.94
0.76	0.92
17.93	21.72
1.63	1.98
1.90	2.30
22.89	64.12
0.76	0.92
3.29	4.36

PRODUCT OIL:

Gravity, °API	21.2
Specific Gravity @ 60°F	0.9267
Pourpoint, °F	80
Viscosity	
SUS @ 60°F	
SUS @ 100°F	
SUS @ 140°F	
SUS @ 210°F	
Total Sulfur, Wt%	0.63
Total Nitrogen, Wt%	1.90
Ramabottom Carbon, Wt%	1.29
BS & W, Vol%	0.14
Carbon, Wt%	84.20
Hydrogen, Wt%	11.69
Oxygen, Wt%	1.24
Tot Heavy	162.9

MISCELLANEOUS

Retort Pressure Drop, Inches H₂O/foot bed 1.0

Retort Bed Height, feet-inches 25-6

Raw Shale Feed Screen Analysis Figure 4-5

DATE	HOURS	DAYS	HOURS	TIME LOST-TIME DAYS HOURS	REMARKS OR REASON OUTAGE*
1-18-76	0830				Startup
1-19-76	1918	5	2.30	0.37	Heater off 3 times
1-19-76	0730	3	21.17	0.07	Heater off
1-24-76	2040	5	12.77	1.17	Heater off 7 times
1-25-76	0145		3.92	7.23	Heater off - standby
1-26-76	1100	1	2.00	3.78	Standby to in- stall gas cooler
1-26-76	1347		3.03	0.23	Heater off
1-27-76	2030	1	2.50	2.50	Heater off
1-29-76	0920	1	10.33	0.33	Heater off
1-30-76	0100		15.33	0.08	Heater off
1-30-76	0410		3.08	0.08	Heater off
1-30-76	0430		0.25	0.08	Heater off
1-30-76	0530		0.92	0.08	Heater off
1-30-76	0610		0.58	0.08	Heater off
1-30-76	1800		11.75	1.33	Heater off
1-31-76	0320		5.00	0.30	Heater off 3 times
1-31-76	0655		1.28	4.23	Heater off
2-5-76	1400	5	4.23	0.17	Heater off
2-6-76	1607	1	1.88	1.06	Standby to check weigh belt
2-9-76	2130	1	4.22	1.03	Heater off
2-10-76	1921		14.19		Shutdown
	TOTAL	30	3.76	1	1.32
					96.6% Operating Time

*Includes heater outage of 3 minutes or more.

MISCELLANEOUS

Retort Pressure Drop, Inches H₂O/foot bed
Retort Bed Height, Feet-inches
Raw Shale Feed Screen Analysis

1.0

25-6

Figure 4-2

TABLE NO. 4-6
SEMI-WORKS RUN NO. SW-23
SUMMARY OF OPERATING TIME

DATE	OPERATING TIME HOURS	TIME ON-STREAM		TIME LOST-TIME		REMARKS OR REASON FOR OUTAGE*
		DAYS	HOURS	DAYS	HOURS	
1-10-76	0800					Startup
1-15-76	1018	5	2.30		0.37	Heater off 5 times
1-19-76	0750	3	21.17		0.07	Heater off
1-24-76	2040	5	12.77		1.17	Heater off 7 times
1-25-76	0145		3.92		7.25	Heater off - standby
1-26-76	1100	1	2.00		3.76	Standby to in- install gas cooler
1-26-76	1747		3.03		0.22	Heater off
1-27-76	2030	1	2.50		2.50	Heater off
1-29-76	0920	1	10.33		0.33	Heater off
1-30-76	0100		15.33		0.08	Heater off
1-30-76	0410		3.08		0.08	Heater off
1-30-76	0430		0.25		0.08	Heater off
1-30-76	0530		0.92		0.08	Heater off
1-30-76	0610		0.58		0.08	Heater off
1-30-76	1800		11.76		1.33	Heater off
1-31-76	0320		8.00		0.30	Heater off 3 times
1-31-76	0455		1.28		4.83	Heater off
2-5-76	1400	5	4.25		0.17	Heater off
2-6-76	1607	1	1.88		1.00	Standby to check weigh belt
2-9-76	2120	3	4.22		1.83	Heater off
2-10-76	1321		14.18			Shutdown
	TOTAL	30	3.76	1	1.52	96.6% Operating Time

*Includes heater outage of 5 minutes or more.

SEMI-WORKS RUN NO. SW-23
SUMMARY OF OPERATING TIME

DATE	OPERATING TIME HOURS	ON-STREAM DAYS HOURS	LOST-TIME DAYS HOURS	REMARKS OR REASON FOR OUTAGE*
1-10-76	0800			Startup
1-12-76	1018	2.30	0.37	Heater off 2 times
1-19-76	0750	21.17	0.07	Heater off
1-24-76	2040	12.77	1.17	Heater off 7 times
1-25-76	0145	3.52	7.25	Heater off - standby
1-26-76	1100	2.00	3.76	Standby to in- stall gas cooler
1-26-76	1747	3.03	0.22	Heater off
1-27-76	2030	2.20	2.50	Heater off
1-29-76	0920	10.33	0.33	Heater off
1-30-76	0100	12.33	0.08	Heater off
1-30-76	0410	3.08	0.08	Heater off
1-30-76	0430	0.22	0.08	Heater off
1-30-76	0530	0.22	0.08	Heater off
1-30-76	0610	0.28	0.08	Heater off
1-30-76	1800	11.76	1.33	Heater off
1-31-76	0320	8.00	0.30	Heater off 3 times
1-31-76	0452	1.28	4.83	Heater off
2-2-76	1400	4.25	0.17	Heater off
2-6-76	1607	1.88	1.00	Standby to check weigh belt
2-9-76	2120	4.22	1.83	Heater off
2-10-76	1321	14.18		Shutdown
TOTAL	30	3.76	1.52	96.68 Operating Time

*Includes heater outage of 2 minutes or more.

TABLE NO. 4-7
SEMI-WORKS RUN SW-23
THERMAL EFFICIENCY PROGRESSION

<u>Test Period</u>	<u>Heat Input*</u> MBTU/Ton	<u>Recycle Gas**</u> Ratio	<u>Top Gas</u> Temp., °F
A-1	610	3.68	1142
A-2	609	3.79	1148
A-3	641	3.72	1148
A-4	628	3.72	1151
A-5	617	3.77	1143
A-6	592	3.79	1148
A-7	578	2.00	1136
B-1	617	2.57	1146
B-2	603	2.59	1141
A-8	661	3.73	1133
B-5	532	1.94	1151
C-1	516	1.79	1183
C-2.1	485	1.47	1206
C-2.2	444	1.45	1153
C-2.3	487	1.46	1198
C-5	461	1.39	1206

*Heat input defined as top gas enthalpy at the distributor inlet temperature above a 770°F datum.

**Recycle gas ratio defined as ratio of top gas rate (SCF/ton) to bottom gas rate (SCF/ton).

TABLE NO. 4-7
SEMI-WORKS RUN SW-23
THERMAL EFFICIENCY PROGRESSION

Test Period	Heat Input* MBTU/Ton	Recycle Gas** Ratio	Top Gas Temp., °F
A-1	610	3.68	1142
A-2	609	3.79	1148
A-3	641	3.72	1148
A-4	628	3.72	1151
A-5	617	3.77	1143
A-6	592	3.79	1148
A-7	578	2.00	1136
B-1	617	2.57	1146
B-2	603	2.59	1141
A-8	661	3.73	1133
B-3	532	1.94	1151
C-1	516	1.79	1183
C-2.1	485	1.47	1206
C-2.2	444	1.45	1153
C-2.3	487	1.46	1198
C-2	461	1.39	1206

*Heat input defined as top gas enthalpy at the distributor inlet temperature above a 77°F datum.

**Recycle gas ratio defined as ratio of top gas rate (SCF/ton) to bottom gas rate (SCF/ton).

TABLE NO. 4-8

SEMI-WORKS RUN NO. SW-28

THERMAL EFFICIENCY STUDY

Test Period	Heat Input* MBTU/Ton	C ₅ + Yield Wt% Fischer Assay	Organic Carbon in Retorted Shale, Wt%
C-1	478	91.3	3.30
C-2	451	88.4	3.79
Step 3	348	60.4	5.52
A-3	341	60.1	5.93
A-4	392	85.4	4.16
A-4.1	440	94.9	3.10
A-4.2	424	94.0	3.04
A-4.3	397	79.7	3.74
A-4.4	386	69.5	5.51

*Heat input defined as top gas enthalpy at the distributor inlet temperature above a 77°F datum.

TABLE VI. 4-2

HEAT-LOSS DATA FOR 19-19

THERMAL EFFICIENCY STUDY

Time Period	Heat Input Btu/hr	C ₂ + Yield Wt % Flasher Heavy	Organic Carbon in Resorbed Solids, Wt %
0-1	108	85.1	2.10
0-2	102	88.4	2.78
0-3	108	88.4	2.21
0-4	102	80.1	2.91
0-5	102	85.4	4.18
0-6	102	84.9	3.18
0-7	102	84.8	3.04
0-8	107	78.7	3.74
0-9	104	69.2	2.21

*Heat input defined as top gas enthalpy at the distributor in-
let temperature above a 75°F datum.

periods where heat input was purposely insufficient as evident from low Fischer Assay yields and high organic carbon content remaining in the retorted shale. Organic carbon contents in the vicinity of 2.5 weight% represent complete retorting.

The reliability of the data during Semi-Works Runs No. 23 and 28 is considered to be excellent with respect to the frequency and accuracy of readings taken and laboratory samples analyzed. The results of oil rundown tank calibrations and rotary seal losses obtained during Semi-Works Run No. 20 were incorporated into these data. Raw shale weigh belt checks were made when necessary. Retorted shale weights were determined by ash balance. Oil samples were taken during Semi-Works Run No. 23 and sent to Sohio Petroleum for crude assay. It should be noted that operation with simultaneous hot gas injection to both top and mid gas distributors was not possible during these runs due to limitations in the recycle gas heaters.

Analysis of the test period data from Semi-Works Runs No. 23 and 28, with the criteria given in Section 4.4.3, resulted in selection of the consecutive test periods A-4.1 and A-4.2 of Semi-Works Run No. 28 as the core of the commercial design basis for the Indirect Heated process. Combination of these two test periods represents 36 stable operating hours of high yield and thermal efficiency. A data summary calculated by weight averaging the two test periods data on the basis of test period length is given in Table 4-9.

Design parameters for the commercial retort were basically extracted from the Data Summary Table 4-9. Various figures were rounded off. The following design parameters differ from those in Table 4-9 and justification and reason for the such deviations are described.

periods where heat input was purposely insufficient as evident from low Fischer Assay yields and high organic carbon content remaining in the retorted shale. Organic carbon contents in the vicinity of 2.5 weights represent complete retorting.

The reliability of the data during Semi-Works Run No. 23 and 28 is considered to be excellent with respect to the frequency and accuracy of readings taken and laboratory samples analyzed. The results of oil rundown tank calibrations and rotary seal losses obtained during Semi-Works Run No. 20 were incorporated into these data. Raw shale weight belt checks were made when necessary. Retorted shale weights were determined by ash balance. Oil samples were taken during Semi-Works Run No. 23 and sent to Sohio Petroleum for crude assay. It should be noted that operation with simultaneous hot gas injection to both top and mid gas distributors was not possible during these runs due to limitations in the recycle gas heaters.

Analysis of the test period data from Semi-Works Run No. 23 and 28, with the criteria given in Section 4.4.3, resulted in selection of the consecutive test periods A-4.1 and A-4.2 of Semi-Works Run No. 28 as the core of the commercial design basis for the indirect heated process. Combination of these two test periods represents 36 stable operating hours of high yield and thermal efficiency. A data summary calculated by weight averaging the two test periods data on the basis of test period length is given in Table 4-9.

Design parameters for the commercial reactor were basically extracted from the data Summary Table 4-9. Various figures were rounded off. The following design parameters differ from those in Table 4-9 and justification and reason for such deviations are described.

Shale Grade. As stated previously, a shale grade of 29 gpt was a physical feature of the site selection made for the Commercial Evaluation Study. During Semi-Works Run No. 23, 16 out of 71 eight hour periods (23%) operated with greater than 29 gpt shale feed; similarly, 2 out of 22 (9%) in Semi-Works Run No. 28. Excursions of greater than 30 gpt shale feed were experienced during Semi-Works Run No. 23. Based on the above, sustained operation with 29 gpt shale is feasible.

Shale Mass Rate. Raw shale throughput for the combined test periods A-4.1 and A-4.2 of Semi-Works Run No. 28 averaged 414 lbs/hr/ft². For the purpose of the Commercial Evaluation Study, shale mass rate for the Indirect Heated process will be the same as that for the Direct Heated process, 455.5 lbs/hr/ft². Explanation of the basis for 455.5 lbs/hr/ft² was given previously for the Direct Heated process. Indirect Heated operation at 455.5 lbs/hr/ft² was demonstrated during Semi-Works Runs No. 23 and 28.

Product Gas Quality. Atlantic Richfield Company obtained and analyzed samples of the product gas during Semi-Works Run No. 28, however, the results were not available when work on the Commercial Evaluation Study was initiated. The gas analysis used in commercial evaluation study, for the Indirect Heated process will be as sampled and analyzed by the Paraho laboratory during the A-4.1 and A-4.2 test periods of Semi-Works Run No. 28. The data summary of test periods A-4.1 and A-4.2 shown in Table 4-9 present the gas analysis on a C₄- basis. The corresponding oil yield is reported as C₅+ wt% of Fischer Assay. For the Commercial Evaluation Study, oil yield will be as collected and gas quality will be as produced. Thus, the gas analysis for the Commercial Evaluation Study will be as given in Table 4-9 with the C₅+ fraction as sampled and analyzed by the Paraho Laboratory included.

... he stated previously... a shale grade of 19 gpt
was a physical feature of the area selected... for the
Commercial Evaluation Study. During Semi-Work No. 11,
in one of 12 steps from periods 1-4-1 and 1-4-2, the shale
was 19 gpt shale (oil) and 12 gpt (oil) in Semi-
Work No. 12. Evaluation of greater than 19 gpt shale
had been expected during Semi-Work No. 11. Based
on the above, estimated operations with 19 gpt shale is
feasible.

... The shale throughout for the combined test
periods 1-4-1 and 1-4-2 of Semi-Work No. 11 averaged
19 gpt. For the purpose of the Commercial Evaluation
Study, shale was run for the direct heated process with
the same as that for the direct heated process, 455.2
lb/hr. The evaluation of the shale for 455.2 lb/hr.
was given previously for the direct heated process. Indi-
rect heated operation at 455.2 lb/hr. was demonstrated
during Semi-Work No. 11 and 12.

Product Gas Quality. Analysis of product gas during Semi-Work
and analyzed samples of the product gas during Semi-Work
No. 11. However, the analysis was not available when
was the Commercial Evaluation Study was initiated.
The gas analysis used in commercial evaluation study, for
the indirect heated process will be as sampled and analyzed
by the Paraho Laboratory during the 1-4-1 and 1-4-2 test
periods of Semi-Work No. 12. The data summary of test
periods 1-4-1 and 1-4-2 shown in Table 4-2 present the gas
analysis on a C₂-basis. The corresponding oil yield is
reported as C₂-oil of direct assay. For the Commercial
Evaluation Study, oil yield will be as collected and gas
quality will be as reported. Thus, the gas analysis for the
Commercial Evaluation Study will be as given in Table 4-2
with the C₂-fraction as sampled and analyzed by the Paraho
Laboratory included.

TABLE NO. 4-9

DATA SUMMARY

Sheet 1 of 2

RAW SHALE PROPERTIES

Run No.	SW-28
Test No.	A-4.1,A-4.2
Start, Date & Time	3/19/76 2000
End, Date & Time	3/21/76 0800
Length, Hours	36

TEMPERATURES

Product Oil Out °F	147
Retorted Shale Out °F	336
Raw Shale in °F	40
OffGas Temperature °F	326
Top Heater °F	1379
Top Dist. Inlet °F	1299
Bottom Dist. Inlet °F	150

RATES AND QUANTITIES

Recycle Gas	
Top SCF/Ton	10530
Mid SCF/Ton	0
Bottom SCF/Ton	11950
Total SCF/Ton	22480
Raw Shale Tph	10.2

YIELDS

Oil Collected Gal/Ton	24.24
Oil Collected Vol% F.A.	92.2
Total Oil Yield	
C ₅ + Wt% F.A.	95
Product Gas SCF/Ton (wet)	535
Retorted Shale Tph	9.1
Retorted Shale Wt% R.S.	89.2
Liquid Water Lbs/Ton	29.9
Material Recovery Wt%	100.3

MISCELLANEOUS

Retort dp in H ₂ O/ft bed	1.4
Carbonate Decomp. Wt%	2.5
Retort Bed Height, Ft.In.	24'-6"
Throughput, Lbs/Hr/Ft ²	414

RETORTED SHALE PROPERTIES

Fischer Assay Gal/Ton	0.5
Mineral CO ₂ Wt%	19.47
Organic Carbon Wt%	1.06
F.A. Wt% Oil	0.19
F.A. Wt% Water	0.74
F.A. Wt% Gas + Loss	0.62
Ignition Loss Wt%	23.32
Carbon Wt%	8.37
Hydrogen Wt%	0.13
Nitrogen Wt%	0.34
Sulphur Wt%	0.74

C ₂ H ₆	4.52
C ₃ 's	2.78
C ₄ 's	2.61
H ₂ S	1.82
NH ₃	1.23
Vol.% Moisture	25.82

TABLE NO. 4-2

DATA SUMMARY

Sheet 1 of 2

Run No.	Test No.	Start, Date & Time	End, Date & Time	Length, Hours
EW-28	A-4.1, A-4.2	3/12/76 2000	3/21/76 0800	36
TEMPERATURES				
	Product Oil Out °F			147
	Reformed Shale Out °F			336
	Raw Shale in °F			40
	Oil Gas Temperature °F			326
	Top Heater °F			1379
	Top Dist. Inlet °F			1339
	Bottom Dist. Inlet °F			150

RATES AND QUANTITIES		YIELDS	
Recycle Gas		Oil Collected Gal/Ton	24.24
Top SCF/Ton	10530	Oil Collected Vol. F.A.	92.2
Mid SCF/Ton	0	Total Oil Yield	92
Bottom SCF/Ton	11920	Cg + Wt F.A.	92
Total SCF/Ton	22450	Product Gas SCF/Ton (wet)	232
Raw Shale Tph	10.2	Reformed Shale Tph	9.1
		Reformed Shale Wt R.S.	89.2
		Liquid Water lbs/Ton	29.9
		Material Recovery Wt%	100.3

MISCELLANEOUS	
Reform dp in H ₂ O/ft bed	1.4
Carbonate Decom. Wt%	2.2
Reform Bed Height, Ft. In. 24'-6"	24'-6"
Throughput, lbs/hr/ft ²	418

TABLE NO. 4-9 CONT.

DATA SUMMARY

Sheet 2 of 2

Run No. SW-28
Test No. A-4.1, A-4.2

RAW SHALE PROPERTIES

Moisture Content Wt %	1.23
Fischer Assay Gal/Ton	26.3
F.A. Wt% Oil	10.02
F.A. Wt% Water	1.68
F.A. Wt% Gas + Loss	2.03
Mineral CO ₂ Wt%	17.70
Ignition Loss Wt%	32.02
Carbon Wt%	16.16
Hydrogen Wt%	1.70
Nitrogen Wt%	0.45
Sulphur Wt%	0.79

PRODUCT OIL PROPERTIES

Gravity, Deg. API	20.2
Viscosity SUS @ 130°	85.0
Viscosity SUS @ 210°	45.7
Ramsbottom Carbon Wt%	1.93
Water Content Vol%	1.07
Solids, BS, Wt%	1.56
Carbon Wt%	84.89
Hydrogen Wt%	11.44
Nitrogen Wt%	2.03
Sulphur Wt%	0.62

PRODUCT GAS PROPERTIES (Dry) C₄-

Gross Heat. Value	
Btu/SCF	808
Specific Gravity	0.721

RETORTED SHALE PROPERTIES

Fischer Assay Gal/Ton	0.5
Mineral CO ₂ Wt%	19.47
Organic Carbon Wt%	3.06
F.A. Wt% Oil	0.19
F.A. Wt% Water	0.74
F.A. Wt% Gas + Loss	0.62
Ignition Loss Wt%	23.32
Carbon Wt%	8.37
Hydrogen Wt%	0.33
Nitrogen Wt%	0.34
Sulphur Wt%	0.74

SCREEN ANALYSIS

Size - Inches	Amount - Wt%
3.00	0.0
2.50	0.0
2.00	0.0
1.50	26.2
1.05	31.8
0.742	23.2
0.525	13.6
0.371	1.5
0.263	1.4
0.185	0.8
0.093	0.5

GAS ANALYSIS, VOL% (Dry) C₄-

H ₂	25.12
N ₂	0.56
O ₂	0.0
CO	2.73
CH ₄	32.15
CO ₂	15.24
C ₂ H ₄	12.74
C ₂ H ₆	4.52
C ₃ 's	2.28
C ₄ 's	0.61
H ₂ S	2.82
NH ₃	1.23

Vol.% Moisture 28.82

TABLE NO. 4-2 CONT.
DATA SUMMARY
Sheet 2 of 2

Run No. 2W-28
Test No. A-4.1, A-4.2

SCREEN ANALYSIS

Size - Inches Amount - Wt%

3.00	0.0
2.50	0.0
2.00	0.0
1.50	26.2
1.05	31.8
0.742	23.2
0.525	13.6
0.371	1.2
0.253	1.4
0.182	0.8
0.093	0.2
Pan	0.2
Loss	0.1

GAS ANALYSIS, VOL% (Dry) C₄-

H ₂	28.12
N ₂	0.26
O ₂	0.0
CO	2.73
CH ₄	32.12
CO ₂	12.24
C ₂ H ₆	12.74
C ₃ H ₈	4.22
C ₃ H ₄	2.38
C ₄ H ₁₀	0.61
H ₂ S	2.82
NH ₃	1.23

Vol.% Moisture 28.82

RAW SHALE PROPERTIES

Moisture Content Wt %	1.23
Fischer Assay Gal/Ton	26.2
F.A. Wet Oil	10.02
F.A. Wet Water	1.68
F.A. Wet Gas + Loss	2.03
Mineral CO ₂ Wt%	17.70
Ignition Loss Wt%	32.02
Carbon Wt%	16.16
Hydrogen Wt%	1.70
Nitrogen Wt%	0.42
Sulphur Wt%	0.72

PRODUCT OIL PROPERTIES

Gravity, Deg. API	20.2
Viscosity SUS @ 130°	82.0
Viscosity SUS @ 210°	42.7
Rambottom Carbon Wt%	1.93
Water Content Vol%	1.07
Solids, SS, Wt%	1.26
Carbon Wt%	84.89
Hydrogen Wt%	11.44
Nitrogen Wt%	2.03
Sulphur Wt%	0.62

PRODUCT GAS PROPERTIES (Dry) C₄-

Gross Heat Value	808
Btu/scf	0.721
Specific Gravity	

RETORTED SHALE PROPERTIES

Fischer Assay Gal/Ton	0.2
Mineral CO ₂ Wt%	19.47
Organic Carbon Wt%	3.08
F.A. Wet Oil	0.19
F.A. Wet Water	0.74
F.A. Wet Gas + Loss	0.62
Ignition Loss Wt%	23.32
Carbon Wt%	8.37
Hydrogen Wt%	0.33
Nitrogen Wt%	0.34
Sulphur Wt%	0.74

Product Oil Properties. Oil samples were taken during Semi-Works Run No. 23. The Sohio Petroleum Company performed a final limited crude assay of this crude shale oil and have supplied the results for the purposes of the Commercial Evaluation Study. (For details see Appendix.)

Time did not allow a complete crude assay to be run on oil produced from test periods A-4.1 and A-4.2 of Semi-Works Run No. 28. Since a complete crude assay is necessary for process calculations in crude shale oil upgrading, the assay from Semi-Works Run No. 23 will be utilized here. It is interesting to note that oils produced during Semi-Works Runs No. 28 and 31 and test periods of higher thermal efficiency in Semi-Works Run No. 23 exhibited lower viscosities as shown in Table 4-10.

Raw Shale Feed Screen Analysis. The Tylab screen analysis for raw shale feed during the combined test periods A-4.1 and A-4.2 of Semi-Works Run No. 28 averaged as given in Table 4-9. In order to utilize the blasting and crushing study performed by Cleveland-Cliffs Iron Company, the two day screen analysis of 11/10/75 to 11/12/75 as described previously in Section 4.4.4 will be assumed as the feed consist for commercial indirect heated operation. Screen analysis for retort feed is shown in Figure 4-5.

Product Gas Production. Product gas production for the combined test periods A-4.1 and A-4.2 of Semi-Works Run No. 28 averaged 535 SCF/Ton wet basis. The quantity includes predicted losses from the top and bottom rotary seals. During the above test periods, leakage of recycle gas in the external heaters was known to exist, but quantitative information on the degree of leakage is not available. Thus, taking into account heater leakages, the gas production for commercial design was conservatively assumed to be 700 SCF/Ton.

Product Oil Properties. Oil samples were taken during Semi-Works Run No. 23. The Sohio Petroleum Company performed a final limited crude assay of this crude shale oil and have supplied the results for the purposes of the Commercial Evaluation Study. (For details see Appendix.)

Time did not allow a complete crude assay to be run on oil produced from test periods A-4.1 and A-4.2 of Semi-Works Run No. 28. Since a complete crude assay is necessary for process calculations in crude shale oil upgrading, the assay from Semi-Works Run No. 23 will be utilized here. It is interesting to note that oils produced during Semi-Works Runs No. 28 and 31 and test periods of higher thermal efficiency in Semi-Works Run No. 23 exhibited lower viscosities as shown in Table 4-10.

Raw Shale Feed Screen Analysis. The typical screen analysis for raw shale feed during the combined test periods A-4.1 and A-4.2 of Semi-Works Run No. 28 averaged as given in Table 4-9. In order to utilize the blasting and crushing study performed by Cleveland-Cliffs Iron Company, the two day screen analysis of 11/10/75 to 11/12/75 as described previously in Section 4.4.4 will be assumed as the feed consist for commercial indirect heated operation. Screen analysis for retrofit feed is shown in Figure 4-5.

Product Gas Production. Product gas production for the combined test periods A-4.1 and A-4.2 of Semi-Works Run No. 28 averaged 535 SCF/Ton wet basis. The quantity includes predicted losses from the top and bottom rotary seals. During the above test periods, leakage of recycle gas in the external heaters was known to exist, but quantitative information on the degree of leakage is not available. Thus, taking into account heater leakages, the gas production for commercial design was conservatively assumed to be 700 SCF/Ton.

TABLE NO. 4-10

SEMI-WORKS RUN NO. SW-23, SW-28, SW-31
Crude Shale Oil Viscosities

Run Number	Test Period	Viscosity @ 130°F, SUS	Viscosity @ 210°F, SUS
SW-23	A-1	105.9	50.4
	A-2	106.0	52.1
	A-3	112.8	53.0
	A-4	94.9	49.1
	A-5	111.9	53.1
	A-6	112.4	53.0
	A-7	112.9	53.4
	B-1	106.6	51.7
	B-2	115.4	56.5
	A-8	102.4	50.5
	B-5	111.0	53.9
	C-1	117.4	53.1
	C-2.1	105.0	58.0
	C-2.2	88.5	51.4
	C-2.3	85.4	49.1
	C-5	89.5	48.9
SW-28	C-1	68.4	42.2
	C-2	66.8	41.6
	Step 3	63.4	41.4
	A-3	63.5	42.5
	A-4	64.6	41.8
	A-4.1	82.9	45.0
	A-4.2	86.1	46.1
	A-4.3	72.2	44.1
	A-4.4	71.5	44.7
SW-31	B	67.0	41.9
	D	68.2	42.1

TABLE NO. 4-10

SEMI-WORKS RUN NO. SW-23, SW-28, SW-31
Crude Shale Oil Viscosities

Run Number	Test Period	Viscosity @ 130°F, SUS	Viscosity @ 210°F, SUS
SW-23	A-1	105.9	50.4
	A-2	106.0	52.1
	A-3	112.8	53.0
	A-4	94.9	49.1
	A-5	111.9	53.1
	A-6	112.4	53.0
	A-7	112.9	53.4
	B-1	106.8	51.7
	B-2	115.4	56.5
	A-8	102.4	50.5
	B-5	111.0	53.9
	C-1	117.4	53.1
	C-2.1	105.0	58.0
	C-2.2	88.5	51.4
	C-2.3	85.4	49.1
	C-5	89.5	48.9
SW-28	C-1	68.4	42.5
	C-2	66.8	41.8
	Step 3	63.4	41.4
	A-3	63.5	42.5
	A-4	64.6	41.8
	A-4.1	82.9	45.0
	A-4.2	86.1	46.1
	A-4.3	72.2	44.1
	A-4.4	71.5	44.7
	B	67.0	41.9
	D	68.5	42.1
SW-31	B	67.0	41.9
	D	68.5	42.1

Shale Bed Pressure Drop. The bed pressure drop for test periods A-4.1 and A-4.2 for Semi-Works Run No. 28 was unusually high compared with similar operating test periods. The higher pressure drop during the combined A-4.1 and A-4.2 test periods indicates the possibility of internal restriction to gas flow within the retort. A shale bed pressure drop of 1.0 inch of water per foot of bed is considered more typical of Indirect Heated operation and will be used for commercial retort design.

In Table 4-11, the commercial design basis for the Paraho Indirect Heated process is summarized utilizing the information from Table 4-9 with the modifications described above.

4.4.6 Commercial Retorts

Process Flow Diagrams. Process flow diagrams for the Direct and Indirect Heated commercial retorts are shown in Figures 4-11 and 4-12, respectively. The process flow and material balances were derived from the retort design basis given in Sections 4.4.4 and 4.4.5 and standard engineering practice. Preliminary sizes are given for major equipment and lines for the purpose of cost estimating.

Offgas, °F	300
Cooled offgas, °F	150
Retorted Shale, °F	310
Bottom Cooling Gas, °F	150
Heating Gas, °F	1300

Shale Bed Pressure Drop. The bed pressure drop for test periods A-4.1 and A-4.2 for Semi-Works Run No. 28 was unusually high compared with similar operating test periods. The higher pressure drop during the combined A-4.1 and A-4.2 test periods indicates the possibility of lateral restriction to gas flow within the retort. A shale bed pressure drop of 1.0 inch of water per foot of bed is considered more typical of indirect heated operation and will be used for commercial retort design.

In Table 4-11, the commercial design basis for the Paraho Indirect Heated process is summarized utilizing the information from Table 4-9 with the modifications described above.

4.4.6 Commercial Retorts

Process Flow Diagrams. Process flow diagrams for the Direct and Indirect Heated commercial retorts are shown in Figures 4-11 and 4-12, respectively. The process flow and material balances were derived from the retort design basis given in Sections 4.4.4 and 4.4.5 and standard engineering practice. Preliminary sizes are given for major equipment and lines for the purpose of cost estimating.

TABLE NO. 4-11

PARAHO INDIRECT HEATED RETORT
COMMERCIAL DESIGN BASIS

Rates and Quantities:

Shale Mass Rate, lbs/hr/ft ²	455.5
Recycle to Top Distributor, SCF/Ton	10500
Recycle to Bottom Distributor, SCF/Ton	12000
Total Recycle, SCF/Ton	22500
Top Gas Heat Input, Btu/Ton	429000
Raw Shale Grade, gpt	29
Oil Collected, Vol.% Fischer Assay	92
Product Gas, SCF/Ton	700
Retorted Shale, Wt.% Raw Shale	86.5

Temperatures:

Offgas, °F	300
Cooled Offgas, °F	150
Retorted Shale, °F	310
Bottom Cooling Gas, °F	150
Heating Gas, °F	1300
Total Sulfur, Wt%	0.62
Total Nitrogen, Wt%	2.05
Rawbottom Carbon, Wt%	1.14
AS & W, Vol%	0.05
Carbon, Wt%	84.88
Hydrogen, Wt%	11.57
Oxygen, Wt%	1.28

TABLE NO. 4-11

PARANO INDIRECT HEATED RETORT
COMMERCIAL DESIGN BASIS

Rates and Quantities:

432.5	Shale Mass Rate, lbs/hr/ft ²
10500	Recycle to Top Distributor, SCF/Ton
13000	Recycle to Bottom Distributor, SCF/Ton
23500	Total Recycle, SCF/Ton
432000	Top Gas Heat Input, Btu/Ton

Yields:

29	Raw Shale Grade, gpt
92	Oil Collected, Vol. % Fischer Assay
700	Product Gas, SCF/Ton
86.5	Retorted Shale, Wt. % Raw Shale

Temperatures:

300	Offgas, °F
150	Cooled Offgas, °F
110	Retorted Shale, °F
150	Bottom Cooling Gas, °F
1300	Heating Gas, °F

PRODUCT GAS:

	Wet Vol%	Dry Vol%
H ₂	17.40	24.20
N ₂ + Ar + O ₂	0.36	0.50
C ₁	22.53	31.34
CO	1.91	2.66
CO ₂	10.57	14.70
C ₂ E	8.79	12.23
C ₂	3.16	4.39
C ₃ E	1.62	2.25
C ₃	Incl. in C ₃ (E)	Incl. in C ₃ (E)
C ₄ S (mol wt. = 57.0)	0.47	0.65
C ₅ + Light Naphtha (MW=100)	1.15	1.60
C ₆ + Heavy Naphtha (MW=144)	0.57	0.79
H ₂ S	2.45	3.41
NH ₃	0.92	1.28
H ₂ O	28.10	--
	100.00	100.00

PRODUCT OIL:


Gravity, °API	19.1
Specific Gravity @ 60°F	0.9396
Pourpoint, °F	85
Viscosity	
SUS @ 60°F	Too Heavy
SUS @ 100°F	241
SUS @ 140°F	88.0
SUS @ 210°F	45.0
Total Sulfur, Wt%	0.62
Total Nitrogen, Wt%	2.05
Ramsbottom Carbon, Wt%	1.14
BS & W, Vol%	0.05
Carbon, Wt%	84.88
Hydrogen, Wt%	11.57
Oxygen, Wt%	1.28

PRODUCT GAS:

	Wet Vol%	Dry Vol%
H ₂	17.40	24.20
N ₂ + Ar + O ₂	0.36	0.50
CO	22.53	31.34
CO ₂	1.91	2.66
CO ₂	10.57	14.70
C ₂ H ₆	8.79	12.23
C ₃ H ₈	3.16	4.39
C ₄ H ₁₀	1.52	2.25
C ₅ H ₁₂	0.47	0.62
C ₆ H ₁₄	1.15	1.60
C ₇ H ₁₆	0.57	0.79
C ₈ H ₁₈	2.45	3.41
NH ₃	0.92	1.28
H ₂ O	28.10	--
	100.00	100.00

PRODUCT OIL:

Gravity, °API	19.1
Specific Gravity @ 60°F	0.9386
Pourpoint, °F	82
Viscosity	
SUS @ 60°F	241
SUS @ 100°F	88.0
SUS @ 140°F	45.0
SUS @ 210°F	0.62
Total Sulfur, Wt%	2.02
Total Nitrogen, Wt%	1.14
Rammbottom Carbon, Wt%	0.02
BS & W, Vol%	84.88
Carbon, Wt%	11.57
Hydrogen, Wt%	1.28
Oxygen, Wt%	



MISCELLANEOUS:

Retort Pressure Drop, Inches H_2O /foot bed


1.0

Retort Bed Height, feet-inches

24-6

Raw Shale Feed Screen Analysis

Figure 4-5



STREAM NO. STREAM NAME	1 RAW SHALE FEED	2 SPENT SHALES	3 PROCESS AIR	4 RECYCLE GAS	5 PRECIPITATOR PRODUCT GAS	6 PRODUCT OIL	7 PRODUCT GAS
TEMPERATURE, °F	50	380	175	225	150	120	225
PRESSURE, PSIA	10.4	10.4	15.0	15.0	10.0	60	12.5
SOLIDS							
LBS/HR.	546600	437975					
TONS/DAY	6559	5256					
GASES							
COMPOSITION MOL/HR.							
N ₂			2625	5687.1	8472.6		2785.5
O ₂			699				
H ₂				380.6	567.0		186.4
CO				172.7	257.3		84.6
CO ₂				1800.8	2831.8		931.0
CH ₄				201.3	299.9		98.6
C ₂ H ₆				80.6	120.1		39.5
C ₃ H ₈				82.7	123.2		40.5
C ₄ H ₁₀				39.2	58.4		19.2
C ₅ H ₁₂				41.2	61.4		20.2
C ₆ H ₁₄ (MW=98.2)				34.9	52.0		17.1
C ₇ H ₁₆ (MW=100.2)				13.7	20.4		6.7
C ₈ H ₁₈ (MW=114.2)				66.8	99.5		32.7
H ₂ O			33	1861.4	2773.1		911.7
H ₂ S				19.0	28.3		9.3
NH ₃				18.0	26.8		8.8
TOTAL MOL/HR.			3357	10600.0	15791.8		5191.8
LBS/HR.			96510	303925	452786		148861
M SCFH			1.272	4.018	5.986		1.968
MW			28.75	28.67	28.67		28.67
LIQUIDS							
BPSD						4167	
LBS/HR.						56274	
API						21.2	
CS @ 100°F						35.0	
CS @ 210°F						4.6	
CS @ COND.						20.0	
WT % S						0.63	
WT % N						1.90	
POUR PT. °F						80	

NOTES: 1) DESIGN BASIS

RETORT THROUGH PUT	456 LB/HR/FT ²
ACTIVE AREA	1200 FT ²
FISHER ASSAY	29 GAL/TON
OIL YIELD	92 % F.A.
GAS YIELD	7200 SCF/TON
RECYCLE GAS	14700 SCF/TON
AIR RATE	4660 SCF/TON
RETORT ΔP	1.0" H ₂ O/FT

2) DESIGN BASIS FROM PARARO AND DEI.
3) ALL RATES ARE FOR ONE RETORT.


NOTE: This print is the property of
PARARO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a basis of reference to work designed or
furnished by us.

PARARO COMMERCIAL
EVALUATION STUDY

PARARO DIRECT HEATED RETORT
PROCESS FLOW DIAGRAM

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG/ 4-11



管脚号	管脚名称	管脚符号	管脚单位	管脚数值	管脚备注	管脚说明	管脚备注
1	屏极	1	V	250	屏极电压	250V	屏极电压
2	控制极	2	V	0	控制极电压	0V	控制极电压
3	帘栅极	3	V	250	帘栅极电压	250V	帘栅极电压
4	加速极	4	V	250	加速极电压	250V	加速极电压
5	阳极	5	V	250	阳极电压	250V	阳极电压
6	阴极	6	V	0	阴极电压	0V	阴极电压
7	第一阳极	7	V	250	第一阳极电压	250V	第一阳极电压
8	第二阳极	8	V	250	第二阳极电压	250V	第二阳极电压
9	第三阳极	9	V	250	第三阳极电压	250V	第三阳极电压
10	第四阳极	10	V	250	第四阳极电压	250V	第四阳极电压
11	第五阳极	11	V	250	第五阳极电压	250V	第五阳极电压
12	第六阳极	12	V	250	第六阳极电压	250V	第六阳极电压
13	第七阳极	13	V	250	第七阳极电压	250V	第七阳极电压
14	第八阳极	14	V	250	第八阳极电压	250V	第八阳极电压
15	第九阳极	15	V	250	第九阳极电压	250V	第九阳极电压
16	第十阳极	16	V	250	第十阳极电压	250V	第十阳极电压
17	第十一阳极	17	V	250	第十一阳极电压	250V	第十一阳极电压
18	第十二阳极	18	V	250	第十二阳极电压	250V	第十二阳极电压
19	第十三阳极	19	V	250	第十三阳极电压	250V	第十三阳极电压
20	第十四阳极	20	V	250	第十四阳极电压	250V	第十四阳极电压
21	第十五阳极	21	V	250	第十五阳极电压	250V	第十五阳极电压
22	第十六阳极	22	V	250	第十六阳极电压	250V	第十六阳极电压
23	第十七阳极	23	V	250	第十七阳极电压	250V	第十七阳极电压
24	第十八阳极	24	V	250	第十八阳极电压	250V	第十八阳极电压
25	第十九阳极	25	V	250	第十九阳极电压	250V	第十九阳极电压
26	第二十阳极	26	V	250	第二十阳极电压	250V	第二十阳极电压
27	第二十一阳极	27	V	250	第二十一阳极电压	250V	第二十一阳极电压
28	第二十二阳极	28	V	250	第二十二阳极电压	250V	第二十二阳极电压
29	第二十三阳极	29	V	250	第二十三阳极电压	250V	第二十三阳极电压
30	第二十四阳极	30	V	250	第二十四阳极电压	250V	第二十四阳极电压
31	第二十五阳极	31	V	250	第二十五阳极电压	250V	第二十五阳极电压
32	第二十六阳极	32	V	250	第二十六阳极电压	250V	第二十六阳极电压
33	第二十七阳极	33	V	250	第二十七阳极电压	250V	第二十七阳极电压
34	第二十八阳极	34	V	250	第二十八阳极电压	250V	第二十八阳极电压
35	第二十九阳极	35	V	250	第二十九阳极电压	250V	第二十九阳极电压
36	第三十阳极	36	V	250	第三十阳极电压	250V	第三十阳极电压
37	第三十一阳极	37	V	250	第三十一阳极电压	250V	第三十一阳极电压
38	第三十二阳极	38	V	250	第三十二阳极电压	250V	第三十二阳极电压
39	第三十三阳极	39	V	250	第三十三阳极电压	250V	第三十三阳极电压
40	第三十四阳极	40	V	250	第三十四阳极电压	250V	第三十四阳极电压
41	第三十五阳极	41	V	250	第三十五阳极电压	250V	第三十五阳极电压
42	第三十六阳极	42	V	250	第三十六阳极电压	250V	第三十六阳极电压
43	第三十七阳极	43	V	250	第三十七阳极电压	250V	第三十七阳极电压
44	第三十八阳极	44	V	250	第三十八阳极电压	250V	第三十八阳极电压
45	第三十九阳极	45	V	250	第三十九阳极电压	250V	第三十九阳极电压
46	第四十阳极	46	V	250	第四十阳极电压	250V	第四十阳极电压
47	第四十一阳极	47	V	250	第四十一阳极电压	250V	第四十一阳极电压
48	第四十二阳极	48	V	250	第四十二阳极电压	250V	第四十二阳极电压
49	第四十三阳极	49	V	250	第四十三阳极电压	250V	第四十三阳极电压
50	第四十四阳极	50	V	250	第四十四阳极电压	250V	第四十四阳极电压
51	第四十五阳极	51	V	250	第四十五阳极电压	250V	第四十五阳极电压
52	第四十六阳极	52	V	250	第四十六阳极电压	250V	第四十六阳极电压
53	第四十七阳极	53	V	250	第四十七阳极电压	250V	第四十七阳极电压
54	第四十八阳极	54	V	250	第四十八阳极电压	250V	第四十八阳极电压
55	第四十九阳极	55	V	250	第四十九阳极电压	250V	第四十九阳极电压
56	第五十阳极	56	V	250	第五十阳极电压	250V	第五十阳极电压
57	第五十一阳极	57	V	250	第五十一阳极电压	250V	第五十一阳极电压
58	第五十二阳极	58	V	250	第五十二阳极电压	250V	第五十二阳极电压
59	第五十三阳极	59	V	250	第五十三阳极电压	250V	第五十三阳极电压
60	第五十四阳极	60	V	250	第五十四阳极电压	250V	第五十四阳极电压
61	第五十五阳极	61	V	250	第五十五阳极电压	250V	第五十五阳极电压
62	第五十六阳极	62	V	250	第五十六阳极电压	250V	第五十六阳极电压
63	第五十七阳极	63	V	250	第五十七阳极电压	250V	第五十七阳极电压
64	第五十八阳极	64	V	250	第五十八阳极电压	250V	第五十八阳极电压
65	第五十九阳极	65	V	250	第五十九阳极电压	250V	第五十九阳极电压
66	第六十阳极	66	V	250	第六十阳极电压	250V	第六十阳极电压
67	第六十一阳极	67	V	250	第六十一阳极电压	250V	第六十一阳极电压
68	第六十二阳极	68	V	250	第六十二阳极电压	250V	第六十二阳极电压
69	第六十三阳极	69	V	250	第六十三阳极电压	250V	第六十三阳极电压
70	第六十四阳极	70	V	250	第六十四阳极电压	250V	第六十四阳极电压
71	第六十五阳极	71	V	250	第六十五阳极电压	250V	第六十五阳极电压
72	第六十六阳极	72	V	250	第六十六阳极电压	250V	第六十六阳极电压
73	第六十七阳极	73	V	250	第六十七阳极电压	250V	第六十七阳极电压
74	第六十八阳极	74	V	250	第六十八阳极电压	250V	第六十八阳极电压
75	第六十九阳极	75	V	250	第六十九阳极电压	250V	第六十九阳极电压
76	第七十阳极	76	V	250	第七十阳极电压	250V	第七十阳极电压
77	第七十一阳极	77	V	250	第七十一阳极电压	250V	第七十一阳极电压
78	第七十二阳极	78	V	250	第七十二阳极电压	250V	第七十二阳极电压
79	第七十三阳极	79	V	250	第七十三阳极电压	250V	第七十三阳极电压
80	第七十四阳极	80	V	250	第七十四阳极电压	250V	第七十四阳极电压
81	第七十五阳极	81	V	250	第七十五阳极电压	250V	第七十五阳极电压
82	第七十六阳极	82	V	250	第七十六阳极电压	250V	第七十六阳极电压
83	第七十七阳极	83	V	250	第七十七阳极电压	250V	第七十七阳极电压
84	第七十八阳极	84	V	250	第七十八阳极电压	250V	第七十八阳极电压
85	第七十九阳极	85	V	250	第七十九阳极电压	250V	第七十九阳极电压
86	第八十阳极	86	V	250	第八十阳极电压	250V	第八十阳极电压
87	第八十一阳极	87	V	250	第八十一阳极电压	250V	第八十一阳极电压
88	第八十二阳极	88	V	250	第八十二阳极电压	250V	第八十二阳极电压
89	第八十三阳极	89	V	250	第八十三阳极电压	250V	第八十三阳极电压
90	第八十四阳极	90	V	250	第八十四阳极电压	250V	第八十四阳极电压
91	第八十五阳极	91	V	250	第八十五阳极电压	250V	第八十五阳极电压
92	第八十六阳极	92	V	250	第八十六阳极电压	250V	第八十六阳极电压
93	第八十七阳极	93	V	250	第八十七阳极电压	250V	第八十七阳极电压
94	第八十八阳极	94	V	250	第八十八阳极电压	250V	第八十八阳极电压
95	第八十九阳极	95	V	250	第八十九阳极电压	250V	第八十九阳极电压
96	第九十阳极	96	V	250	第九十阳极电压	250V	第九十阳极电压
97	第九十一阳极	97	V	250	第九十一阳极电压	250V	第九十一阳极电压
98	第九十二阳极	98	V	250	第九十二阳极电压	250V	第九十二阳极电压
99	第九十三阳极	99	V	250	第九十三阳极电压	250V	第九十三阳极电压
100	第九十四阳极	100	V	250	第九十四阳极电压	250V	第九十四阳极电压
101	第九十五阳极	101	V	250	第九十五阳极电压	250V	第九十五阳极电压
102	第九十六阳极	102	V	250	第九十六阳极电压	250V	第九十六阳极电压
103	第九十七阳极	103	V	250	第九十七阳极电压	250V	第九十七阳极电压
104	第九十八阳极	104	V	250	第九十八阳极电压	250V	第九十八阳极电压
105	第九十九阳极	105	V	250	第九十九阳极电压	250V	第九十九阳极电压
106	第一百阳极	106	V	250	第一百阳极电压	250V	第一百阳极电压
107	第一百零一阳极	107	V	250	第一百零一阳极电压	250V	第一百零一阳极电压
108	第一百零二阳极	108	V	250	第一百零二阳极电压	250V	第一百零二阳极电压
109	第一百零三阳极	109	V	250	第一百零三阳极电压	250V	第一百零三阳极电压
110	第一百零四阳极	110	V	250	第一百零四阳极电压	250V	第一百零四阳极电压
111	第一百零五阳极	111	V	250	第一百零五阳极电压	250V	第一百零五阳极电压
112	第一百零六阳极	112	V	250	第一百零六阳极电压	250V	第一百零六阳极电压
113	第一百零七阳极	113	V	250	第一百零七阳极电压	250V	第一百零七阳极电压
114	第一百零八阳极	114	V	250	第一百零八阳极电压	250V	第一百零八阳极电压
115	第一百零九阳极	115	V	250	第一百零九阳极电压	250V	第一百零九阳极电压
116	第一百一十阳极	116	V	250	第一百一十阳极电压	250V	第一百一十阳极电压
117	第一百一十一阳极	117	V	250	第一百一十一阳极电压	250V	第一百一十一阳极电压
118	第一百一十二阳极	118	V	250	第一百一十二阳极电压	250V	第一百一十二阳极电压
119	第一百一十三阳极	119	V	250	第一百一十三阳极电压	250V	第一百一十三阳极电压
120	第一百一十四阳极	120	V	250	第一百一十四阳极电压	250V	第一百一十四阳极电压
121	第一百一十五阳极	121	V	250	第一百一十五阳极电压	250V	第一百一十五阳极电压
122	第一百一十六阳极	122	V	250	第一百一十六阳极电压	250V	第一百一十六阳极电压
123	第一百一十七阳极	123	V	250	第一百一十七阳极电压	250V	第一百一十七阳极电压
124	第一百一十八阳极	124	V	250	第一百一十八阳极电压	250V	第一百一十八阳极电压
125	第一百一十九阳极	125	V	250	第一百一十九阳极电压	250V	第一百一十九阳极电压
126	第一百二十阳极	126	V	250	第一百二十阳极电压	250V	第一百二十阳极电压
127	第一百二十一阳极	127	V	250	第一百二十一阳极电压	250V	第一百二十一阳极电压
128	第一百二十二阳极	128	V	250	第一百二十二阳极电压	250V	第一百二十二阳极电压
129	第一百二十三阳极	129	V	250	第一百二十三阳极电压	250V	第一百二十三阳极电压
130	第一百二十四阳极	130	V	250	第一百二十四阳极电压	250V	第一百二十四阳极电压
131	第一百二十五阳极	131	V	250	第一百二十五阳极电压	250V	第一百二十五阳极电压
132	第一百二十六阳极	132	V	250	第一百二十六阳极电压	250V	第一百二十六阳极电压
133	第一百二十七阳极	133	V	250	第一百二十七阳极电压	250V	第一百二十七阳极电压
134	第一百二十八阳极	134	V	250	第一百二十八阳极电压	250V	第一百二十八阳极电压
135	第一百二十九阳极	135	V	250	第一百二十九阳极电压	250V	第一百二十九阳极电压
136	第一百三十阳极	136	V	250	第一百三十阳极电压	250V	第一百三十阳极电压
137	第一百三十一阳极	137	V	250	第一百三十一阳极电压	250V	第一百三十一阳极电压
138	第一百三十二阳极	138	V	250	第一百三十二阳极电压	250V	第一百三十二阳极电压
139	第一百三十三阳极	139	V	250	第一百三十三阳极电压	250V	第一百三十三阳极电压
140	第一百三十四阳极	140	V	250	第一百三十四阳极电压	250V	第一百三十四阳极电压
141	第一百三十五阳极	141	V	250	第一百三十五阳极电压	250V	第一百三十五阳极电压
142	第一百三十六阳极	142	V	250	第一百三十六阳极电压	250V	第一百三十六阳极电压
143	第一百三十七阳极	143	V	250	第一百三十七阳极电压	250V	第一百三十七阳极电压
144	第一百三十八阳极	144	V	250	第一百三十八阳极电压	250V	第一百三十八阳极电压
145	第一百三十九阳极	145	V	250	第一百三十九阳极电压	250V	第一百三十九阳极电压
146	第一百四十阳极	146	V	250	第一百四十阳极电压	250V	第一百四十阳极电压
147	第一百四十一阳极	147	V	250	第一百四十一阳极电压	250V	第一百四十一阳极电压
148	第一百四十二阳极	148	V	250	第一百四十二阳极电压	250V	第一百四十二阳极电压
149	第一百四十三阳极	149	V	250	第一百四十三阳极电压	250V	第一百四十三阳极电压
150	第一百四十四阳极	150	V	250	第一百四十四阳极电压	250V	第一百四十四阳极电压
151	第一百四十五阳极	151	V	250	第一百四十五阳极电压	250V	第一百四十五阳极电压
152	第一百四十六阳极	152	V	250	第一百四十六阳极电压	250V	第一百四十六阳极电压
153	第一百四十七阳极	153	V	250	第一百四十七阳极电压	250V	第一百四十七阳极电压
154	第一百四十八阳极	154	V	250	第一百四十八阳极电压	250V	第一百四十八阳极电压
155	第一百四十九阳极	155	V	250	第一百四十九阳极电压	250V	第一百四十九阳极电压
156	第一百五十阳极	156	V	250	第一百五十阳极电压	250V	第一百五十阳极电压
157	第一百五十一阳极	157	V	250	第一百五十一阳极电压	250V	第一百五十一阳极电压
158	第一百五十二阳极	158	V	250	第一百五十二阳极电压	250V	第一百五十二阳极电压
159	第一百五十三阳极	159	V	250	第一百五十三阳极电压	250V	第一百五十三阳极电压
160	第一百五十四阳极	160	V	250	第一百五十四阳极电压	250V	第一百五十四阳极电压
161	第一百五十五阳极	161	V	250	第一百五十五阳极电压	250V	第一百五十五阳极电压
162	第一百五十六阳极	162	V	250	第一百五十六阳极电压	250V	第一百五十六阳极电压
163	第一百五十七阳极	163	V	250	第一百五十七阳极电压	250V	第一百五十七阳极电压
164	第一百五十八阳极	164	V	250	第一百五十八阳极电压	250V	第一百五十八阳极电压
165	第一百五十九阳极	165	V	250	第一百五十九阳极电压	250V	第一百五十九阳极电压
166	第一百六十阳极	166	V	250	第一百六十阳极电压	250V	第一百六十阳极电压
167	第一百六十一阳极	167	V	250	第一百六十一阳极电压	250V	第一百六十一阳极电压
168	第一百六十二阳极	168	V	250	第一百六十二阳极电压	250V	第一百六十二阳极电压
169	第一百六十三阳极	169	V	250	第一百六十三阳极电压	250V	第一百六十三阳极电压
170	第一百六十四阳极	170	V	250	第一百六十四阳极电压	250V	第一百六十四阳极电压
171	第一百六十五阳极	171	V	250	第一百六十五阳极电压	250V	第一百六十五阳极电压
172	第一百六十六阳极	172	V	250	第一百六十六阳极电压	250V	第一百六十六阳极电压
173	第一百六十七阳极	173	V	250	第一百六十七阳极电压	250V	第一百六十七阳极电压
174	第一百六十八阳极	174	V	250	第一百六十八阳极电压	250V	第一百六十八阳极电压
175	第一百六十九阳极	175	V	250	第一百六十九阳极电压	250V	第一百六十九阳极电压
176	第一百七十阳极	176	V	250	第一百七十阳极电压	250V	第一百七十阳极电压
177	第一百七十一阳极						

RECEIVED

1900

MESON BOND

I hereby certify that the within and foregoing is a true and correct copy of the original as the same appears in the files of the Department of the Interior, Bureau of Land Management, at Washington, D.C.

Witness my hand and the seal of the Department of the Interior, at Washington, D.C., this 1st day of January, 1900.

Very truly yours,
[Signature]

Special Agent in Charge

Department of the Interior

Bureau of Land Management

Washington, D.C.



The module, or plant, would be considered successful if at the end of the first year:

The projected service factor is 90 percent or greater.

The throughput is greater than 90 percent of design.

The thermal efficiency, as measured by heat input, is no more than 10 percent greater than design.

The quality specifications are no more than 10 percent less than design.

The maximum diameter of the module was set at forty feet, because in McKee's opinion, this is the largest vessel that could be built using commercially available mill shapes and beams.

The scale up factor for both the 32 and 40 foot diameter retorts, 16 and 24, are well within those normally experienced by McKee in the development of ferrous and nonferrous pyro processes.

A forty foot diameter selection was justified on the overall development schedule as one which is subject to risks which are reasonable for a development project and the path which minimizes the overall project cost and time.

The model, or plant, would be considered successful if at the end of the first year;

The projected service factor is 90 percent or greater.

The throughput is greater than 90 percent of design.

The thermal efficiency, as measured by heat input, is no more than 10 percent greater than design.

The quality specifications are no more than 10 percent less than design.

The maximum diameter of the model was set at forty feet, because in McKee's opinion, this is the largest vessel that could be built using commercially available mill shapes and beams.

The scale up factor for both the 32 and 48 foot diameter reactors, 16 and 24, are well within those normally expected by McKee in the development of towers and heat exchangers.

A forty foot diameter selection was justified on the overall development schedule as one which is subject to risks which are reasonable for a development project and the path which minimizes the overall project cost and time.

TABLE NO. 4-12

DIRECT HEATED PROCESS
RETORT HEAT AND MASS BALANCE

<u>IN:</u>	<u>Lbs/hr</u>	<u>MMBtu/hr</u>
Raw Shale (50°F)	546,600	-3.06
Recycle Gas (225°F)	303,780	12.94
Air (175°F)	95,880	2.24
Combustion	---	128.7
	946,260	140.82
<u>OUT:</u>	<u>Lbs/hr</u>	<u>MMBtu/hr</u>
Offgas with oil (150°F)	508,380	11.31
Retorted Shale (380°F)	442,740	29.84
Water Vaporization	---	11.94
Carbonate Decomposition (27%)	---	33.69
Pyrolysis	---	22.48
Distributor Cooling	---	17.58
Skin Heat Loss & Unaccounted	-4,860	13.98
	946,260	140.82

TABLE NO. 4-12

TABLE NO. 4-12

DIRECT HEATED PROCESS
RETORT HEAT AND MASS BALANCE

IN:			
MMBtu/hr	Lbs/hr		
-3.06	246,600	Raw shale (50°F)	
12.94	303,780	Recycle Gas (125°F)	
2.24	95,880	Air (125°F)	
128.7	---	Combustion	
140.82	246,260		
OUT:			
MMBtu/hr	Lbs/hr		
11.31	208,360	Oil gas with oil (150°F)	
29.84	442,740	Retorted shale (130°F)	
11.94	---	Water Vaporization	
32.69	---	Carbonate Decomposition (125°F)	
22.48	---	Pyrolysis	
17.58	---	Distributor Cooling	
13.98	-4,860	Shin heat loss & Unaccounted	
140.82	246,260		

TABLE NO. 4-13

INDIRECT HEATED PROCESS
RETORT HEAT AND MASS BALANCE

IN:		
	<u>Lbs/hr</u>	<u>MMBtu/hr</u>
Raw Shale (50°F)	546,600	-3.06
Hot Gas (1300°F)	166,020	116.14
Bottom Cooling Gas (150°F)	<u>189,480</u>	<u>5.97</u>
	902,100	119.05
OUT:		
	<u>Lbs/hr</u>	<u>MMBtu/hr</u>
Offgas with oil (300°F)	423,360	43.51
Retorted Shale (310°F)	472,260	24.46
Water Vaporization	---	11.94
Carbonate Decomposition (2.5%)	---	3.20
Pyrolysis	---	22.48
Skin Heat Loss & Unaccounted	<u>6,480</u>	<u>13.46</u>
	902,100	119.05

4.5.2 Retorted Shale Handling

The retorted shale and rejected raw shale fines will be conveyed from the retorts to separate surge bins.

TABLE NO. 4-13

INDIRECT HEATED PROCESS
RETORT HEAT AND MASS BALANCE

IN:			OUT:		
MMBtu/hr	Lbs/hr		MMBtu/hr	Lbs/hr	
-3.06	246,600	Raw Shale (50°F)	43.51	423,360	Offgas with oil (300°F)
116.14	166,020	Hot Gas (1300°F)	24.46	423,360	Retorted Shale (310°F)
5.97	189,480	Bottom Cooling Gas (150°F)	11.94	---	Water Vaporization
119.02	902,100		3.20	---	Carbonate Decomposition (5.26)
			22.48	---	Pyrolysis
			13.46	6,480	Skin Heat Loss & Unaccounted
			119.02	902,100	

4.5 RETORTED SHALE MANAGEMENT

4.5.1 General

Retorted shale and rejected fine raw shale must be disposed of in an efficient manner. Surface disposal of all retorted shale and rejected fine raw shale has been selected for this project study. The environmental advantages of underground disposal are uncertain and not effectively demonstrated. Underground disposal would prevent secondary recovery of the oil shale in the pillars, back and floor of the mine. It is anticipated that a suitable technique for in situ retorting of this remaining resource will be developed during the 20-year plant life. The retorted shale disposal pile outlined in Figure 4-3 represents a 20-year disposal pile.

Volumes for this study were based on direct heated processes retorted shale. The retorted shale produced amounts to 82% of the raw shale retort feed on a weight basis. Rejected raw shale fines equal 5 weight% of the total shale mined and will be used for top dressing on the slopes, as well as fill material. Weight would increase by approximately 6% for retorted shale from the indirect heated process. Moisture addition may be required in order to control the greater dust potential and tendencies to self-ignite due to the higher quantity of active carbon on the surface.

4.5.2 Retorted Shale Handling

The retorted shale and rejected raw shale fines will be conveyed from the retorts to separate surge bins.

4.2 RETORTED SHALE MANAGEMENT

4.2.1 General

Retorted shale and rejected fine raw shale must be disposed of in an efficient manner. Surface disposal of all retorted shale and rejected fine raw shale has been selected for this project study. The environmental advantages of underground disposal are uncertain and not effectively demonstrated. Underground disposal would prevent secondary recovery of the oil shale in the pillars, back and floor of the mine. It is anticipated that a suitable technique for in situ retorting of this remaining resource will be developed during the 20-year plant life. The retorted shale disposal pile outlined in Figure 4-3 represents a 20-year disposal pile.

Volumes for this study were based on direct heated processes retorted shale. The retorted shale produced amounts to 82% of the raw shale retort feed on a weight basis. Rejected raw shale fines equal 2 weight% of the total shale mined and will be used for top dressing on the slopes, as well as fill material. Weight would increase by approximately 6% for retorted shale from the indirect heated process. Moisture addition may be required in order to control the greater dust potential and tendencies to self-ignite due to the higher quantity of active carbon on the surface.

4.2.2 Retorted Shale Handling

The retorted shale and rejected raw shale fines will be conveyed from the retorts to separate surge bins.

At full production, approximately 150,000 tons per day will be handled. Some of the rejected fines will be used to top dress the areas to be seeded in an effort to reduce surface temperatures and the remainder will be commingled with the cooled retorted shale unless some other beneficial use is available. Rejected fines will be used because the disposal site does not have an adequate source of soil for top dressing the areas to be vegetated.

The material will be hauled from the surge bins in 100 ton, bottom dump haulers to the disposal area. The hauler traffic will provide the primary compaction of the deposited material. To ensure structural integrity, the face area will be further compacted with conventional compactors. The dumps will be developed so that an average 4:1 slope is maintained. Each 40 foot lift will have a 40 foot wide berm for access and maintenance.

4.5.3 Water Quality and Vegetation

Water from normal run-off and leaching activities will be impounded in catchment basins. This water will be kept out of the regional drainage system. Evaporation and use for dust control will control the supply in the basins.

The areas to be vegetated will be surface leached with sprinklers prior to seeding. A heavy application of fertilizer will precede planting. A mixture of native grasses and shrubs will be seeded. The seeded areas will be irrigated and given supplemental applications of fertilizer for two growing seasons, after which that area will rely on natural precipitation for its water needs.

At full production, approximately 150,000 tons per day will be handled. Some of the rejected fines will be used to top dress the areas to be seeded in an effort to reduce surface temperatures and the remainder will be commingled with the cooled rejected shale unless some other beneficial use is available. Rejected fines will be used because the disposal site does not have an adequate source of soil for top dressing the areas to be vegetated.

The material will be hauled from the surge bins in 100 ton bottom dump haulers to the disposal area. The hauler traffic will provide the primary compaction of the deposited material. To ensure structural integrity, the face area will be further compacted with conventional compactors. The dumps will be developed so that an average 4:1 slope is maintained. Each 40 foot lift will have a 40 foot wide berm for access and maintenance.

4.5.3 Water Quality and Vegetation

Water from normal run-off and leaching activities will be impounded in catchment basins. This water will be kept out of the regional drainage system. Evaporation and use for dust control will control the supply in the basins.

The areas to be vegetated will be surface leached with sprinklers prior to seeding. A heavy application of fertilizer will precede planting. A mixture of native grasses and shrubs will be seeded. The seeded areas will be irrigated and given supplemental applications of fertilizer for two growing seasons, after which the area will rely on natural precipitation for its water needs.

4.6 OFFSITE FACILITIES

The offsite facilities required are:

- o Utilities

- Raw water filtration

- Boiler feed water treatment

- Steam generation

- Potable water treatment

- Cooling tower

- Electrical distribution

- Plant air

- (Instrument Air is included with retorting and process units)

- These facilities would be sized to provide the requirements listed in the Utility Summary - Base Case - Table 4-14.

- o Interconnecting Piping

- o Relief and Blowdown System - Dual System

- o Fire Water System

- o Waste Water Treatment

- o Sewers: Storm, Process, and Sanitary

- o Solid Waste Treatment

- o Administrative and Personnel Facilities

- o Maintenance and Warehousing Facilities

- o Control Laboratory

- o Safety Facilities

- o Roads

- o Product Blending and Loading Facilities

The following are general statements concerning the most critical offsite facilities. Standard petroleum refinery practice will apply to the facilities not discussed.

4.6 OFFSITE FACILITIES

The offsite facilities required are:

Utilities

- Raw water filtration
- Boiler feed water treatment
- Steam generation
- Potable water treatment
- Cooling tower
- Electrical distribution
- Pneum air
- (Instrument Air is included with retorting and process units)
- These facilities would be sized to provide the requirements listed in the Utility Summary - Base Case - Table 4-14.

- Interconnecting Piping
- Relief and Blowdown System - Dual System
- Fire Water System
- Waste Water Treatment
- Sewers: Storm, Process, and Sanitary
- Solid Waste Treatment
- Administrative and Personnel Facilities
- Maintenance and Warehousing Facilities
- Control Laboratory
- Safety Facilities
- Roads
- Product blending and loading facilities

The following are general statements concerning the most critical offsite facilities. Standard petroleum refinery practice will apply to the facilities not discussed.

TABLE 4-14
BASE CASE
UTILITY SUMMARY

	<u>Power</u> <u>kw</u>	<u>Steam</u> <u>lbs/hr</u>	<u>Required</u> <u>Water, gpm</u>	<u>Available</u> <u>Water, gpm</u>	<u>Circulating</u> <u>Cooling Twr.</u> (2) <u>Water, gpm</u>	<u>Fuel</u> <u>BPSD, FOE</u>	<u>Diesel Fuel</u> <u>BPSD</u>
MINING, CRUSHING AND SHALE DISPOSAL	77,500	-	1,257	-	-	-	830
RETORTING AND PRODUCT GAS PROCESSING	185,000	666,000	100	-	32,100	6,708	-
PROCESSING, OFFSITES AND AUXILIARIES	80,500	-	4,250	950	63,200	14,897	-
SUBTOTAL	343,000	666,000	5,607	950	95,300	21,605	830
POWER PLANT	(343,000)	-	345	-	-	17,409	-
TOTAL	-	666,000	5,952	950 ⁽¹⁾	95,300	39,014	830

NOTES:

1) Cooling tower blowdown available for dust control.

2) 30 F ΔT

4.6.1 Water

All water systems and consumptions have been carefully reviewed to minimize the amount of raw make-up water that will be required from the Colorado River.

The estimated make-up water quantities for the studied cases are:

	GPM	<u>Acre-ft/yr</u>	<u>Cu. ft/sec</u>
Base Case	5002	8,070	11.1
Alternate 1	5152	8,310	11.5
Alternate 2A	3557	5,740	7.9
Alternate 2B	2147	3,460	4.8
Alternate 2C	3182	5,130	7.1

(No water sources have been considered as being available from the mining operation).

The raw water supply system shall consist of a water intake, primary setting, and pumping facilities located at the Colorado River immediately south of Anvil Points.

On site water facilities will include an intermediate storage pond, raw water filtration, demineralized boiler feed water treatment, and potable water treatment.

4.6.2 Product Pipelines

Product pipelines have not been included in the cases studies but are pertinent to a shale oil project. The following information would relate to product lines from this shale oil complex:

4.6.1 Water

All water systems and consumptions have been carefully reviewed to minimize the amount of raw make-up water that will be required from the Colorado River.

The estimated make-up water quantities for the studied cases are:

	<u>Acres-ft/Yr</u>	<u>CU. Ft/sec</u>
Base Case	8,070	11.1
Alternate 1	8,310	11.5
Alternate 2A	8,740	12.0
Alternate 2B	9,450	12.8
Alternate 2C	9,130	12.5

(No water sources have been considered as being available from the mining operation).

The raw water supply system shall consist of a water intake, primary settling, and pumping facilities located at the Colorado River immediately south of Anvil Point.

On site water facilities will include an intermediate storage pond, raw water filtration, demineralized boiler feed water treatment, and potable water treatment.

4.6.2 Product Pipelines

Product pipelines have not been included in the cases studies but are pertinent to a shale oil project. The following information would relate to product lines from this shale oil complex:

A shale oil product pipeline is feasible to existing crude pipeline terminal facilities located at Casper, Wyoming, a distance of 290 miles away. It is estimated that the installation cost would be about \$75,000,000 plus appropriate owner's preoperation project costs.

A possible gas pipeline connection (not studied) is in the Rangely, Colorado area. A 75 mile line would be required, and the estimated installation cost is about \$13,000,000 plus appropriate owner's preoperation project costs.

4.6.3 Electric Power Plant

It has been assumed that a contiguous electric power generation plant would be built and operated by others. It would be sized to provide the shale oil complex requirements only, except for the all Direct Heated Retorts case where surplus low Btu gas would be used to generate export power. Capital construction costs for the electric power plants in the various cases are budget estimated as follows:

Base Case:	\$151 MM
Alternate 1:	\$157 MM
Alternate 2A:	\$166 MM
Alternate 2B:	\$108 MM
Alternate 2C:	\$131 MM

4.6.4 Waste Treatment

All waste systems will be designed and operated to protect the existing ecology and meet all environmental regulations.

Feed Point, °F	80	85
Nitrogen, Wt. %	1.80	2.05
Sulfur, Wt. %	.83	.82
Oxygen, Wt. %	1.24	1.28
C:H Ratio	7.30	7.34

(For details see Appendix)

A shale oil product pipeline is feasible to existing crude pipeline terminal facilities located at Casper, Wyoming, a distance of 250 miles away. It is estimated that the installation cost would be about \$75,000,000 plus appropriate owner's preoperation project costs.

A possible gas pipeline connection (not studied) is in the Rangely, Colorado area. A 75 mile line would be required, and the estimated installation cost is about \$13,000,000 plus appropriate owner's preoperation project costs.

4.5.3 Electric Power Plant

It has been assumed that a continuous electric power generation plant would be built and operated by others. It would be aimed to provide the shale oil complex requirements only, except for the All Direct Heated Retorts case where surplus low Btu gas would be used to generate export power. Capital connection costs for the electric power plants in the various cases are budget estimated as follows:

Base Case:	\$151 MM
Alternate 1:	\$157 MM
Alternate 2A:	\$166 MM
Alternate 2B:	\$168 MM
Alternate 2C:	\$171 MM

4.5.4 Waste Treatment

All waste systems will be designed and operated to protect the existing ecology and meet all environmental regulations.

4.7 UPGRADING

Crude shale oil from the retorting operation contains sulfur, nitrogen, and oxygen in amounts that restrict its use as a refinery feedstock. The petroleum industry, however, has technology which is adaptable for upgrading the crude shale oil to refined products.

The processing of crude shale oil is directed towards reduction of sulfur, nitrogen, and oxygen to product specification levels with proper attention to carbon/hydrogen ratios and the myriad of additional physical and chemical properties which deal with product usage. The processing of crude shale oil can be done at or near the mining/retorting site or at a refining site. The processing at the mining/retorting site can be directed towards meeting final product specifications or a somewhat reduced scope and severity sufficient to enable the upgraded shale oil to be used as a crude oil supplement in "normal" refinery operations. Crude shale oil has a pour point in the 50°F - 85°F range depending on retort operating conditions. Movement in a pipeline requires the addition of pour point depressant. If upgrading processing is conducted at the retort site the pour point of the liquid product is reduced sufficiently to allow pipeline movement without pour depressant.

Typical crude shale oil property values which were determined from Paraho produced oil are:

	<u>D.H. Retort</u>	<u>I.H. Retort</u>
Gravity, °API	21.2	19.1
Pour Point, °F	80	85
Nitrogen, Wt. %	1.90	2.05
Sulfur, Wt. %	.63	.62
Oxygen, Wt. %	1.24	1.28
C:H Ratio	7.20	7.34

(For details see Appendix)

4.7 UPGRADING

Crude shale oil from the retorting operation contains sulfur, nitrogen, and oxygen in amounts that restrict its use as a refinery feedstock. The petroleum industry, however, has technology which is adaptable for upgrading the crude shale oil to refined products.

The processing of crude shale oil is directed towards reduction of sulfur, nitrogen, and oxygen to product specifications levels with proper attention to carbon/hydrogen ratios and the myriad of additional physical and chemical properties which deal with product usage. The processing of crude shale oil can be done at or near the mining/retorting site or at a refining site. The processing at the mining/retorting site can be directed towards meeting final product specifications or a somewhat reduced scope and severity sufficient to enable the upgraded shale oil to be used as a crude oil supplement in "normal" refinery operations. Crude shale oil has a pour point in the 50°F - 85°F range depending on retort operating conditions. Movement in a pipeline requires the addition of pour point depressant. If upgrading processing is conducted at the retort site the pour point of the liquid product is reduced sufficiently to allow pipeline movement without pour depressant.

Typical crude shale oil property values which were determined from Paraho produced oil are:

Gravity, °API	D.N. Retort	I.H. Retort
Pour Point, °F	31.7	19.1
Nitrogen, Wt. %	80	85
Sulfur, Wt. %	1.90	2.05
Oxygen, Wt. %	.63	.63
C:H Ratio	1.34	1.38
	7.30	7.34

(For details see Appendix)

Two upgrading cases were evaluated for this study:

Base Case: Coking followed by liquid hydrotreating.

Alternate 1: Direct hydrotreating of crude shale oil.

space velocity considerations may make this case infeasible.

Three additional cases in which no upgrading was included were also studied:

greatly different. The direct hydrotreating case is similar

to the base case (coking followed by hydrotreating). The utilization

of coking in the base case and the coking operation

Alternate 2A: All DH Retorts
Alternate 2B: All IH Retorts
Alternate 2C: 18/6 DH/IH Retorts with IH Retort Gas to SNG

4.7.1 Base Case Upgrading

The base case upgrading scheme (coking followed by liquid hydrotreating) involves less technical risk. The coking operation encompasses (1) fractionation of the crude shale oil, (2) coking of recycle plus atmospheric tower bottoms, and (3) fractionation of coking liquid-gas products.

Crude Shale

The coker operation produces three liquid streams (naphtha, light gas oil, and heavy gas oil). These streams are processed individually in hydrotreaters. The gas streams, from the hydrotreaters contain both H_2S and ammonia in recoverable quantities.

facilities for sour water processing and sulfur

removal are similar to the base case.

Coker sour water and hydrotreater wash water are fed to a Chevron Waste Water Treating Unit for ammonia recovery and H_2S separation. The gas streams, after water washing for ammonia removal, are amine treated. The H_2S from the amine units and the WWT unit is fed to a sulfur plant. Tail gas is processed in the Stretford Unit.

The degree of sulfur and nitrogen removal in the hydrotreat-

ing operation is affected by coking the crude shale oil.

Two upgrading cases were evaluated for this study:

- Base Case: Coking followed by liquid hydrotreating.
- Alternative 1: Direct hydrotreating of crude shale oil.

Three additional cases in which no upgrading was included were also studied:

- Alternative 2A: All DR Refractor
- Alternative 2B: All IR Refractor
- Alternative 2C: 18% DR/IR Refractor with IR Refractor Gas to SNG

4.7.1 Base Case Upgrading

The base case upgrading scheme (coking followed by liquid hydrotreating) involves less technical risk. The coking operation encompasses (1) fractionation of the crude shale oil, (2) coking of recycle plus atmospheric tower bottoms, and (3) fractionation of coking liquid-gas products.

The coker operation produces three liquid streams (naphtha, light gas oil, and heavy gas oil). These streams are processed individually in hydrotreaters. The gas streams, from the hydrotreaters contain both H_2S and ammonia in recoverable quantities.

Coker sour water and hydrotreater wash water are fed to a Chevron Waste Water Treating Unit for ammonia recovery and H_2S separation. The gas streams, after water washing for ammonia removal, are amine treated. The H_2S from the amine units and the WWT unit is fed to a sulfur plant. Tail gas is processed in the Sulfur Unit.

4.7.2 Alternate 1 Upgrading

The assumption that crude shale oil can be fed to a hydro-treater (Alt. 1) has some technical risk. Catalyst life and space velocity considerations may make this case infeasible. Hydrogen consumption is not expected to be appreciably different from the coker case since the feed C/H ratios are not greatly different. The direct hydrotreating case is similar to the base case (coking - hydrotreating). The utilization of energy sources and elimination of the coking operation are the major differences.

4.7.3 Process Unit Requirements

Major process units for the two cases are:

	<u>Base Case</u>	<u>Alt. 1</u>
Cokers	2	-
Hydrogen Plants	2	2
Crude Shale Hydrotreaters	-	2
Coker Product Hydrotreaters	3	-
Naphtha Hydrotreater	-	1

The support facilities for sour water processing and sulfur removal are similar to the base case.

Block flow diagrams for the five cases are given in Figures 4-13, 4-14, 4-15, 4-16, and 4-17.

4.7.4 Product Specifications

The degree of sulfur and nitrogen removal in the hydrotreating operation is affected by coking the crude shale oil.

4.7.3 Alternate 1 Upgrading

The assumption that crude shale oil can be fed to a hydro-
 creaser (A/C. 1) has some technical risk. Catalyst life and
 space velocity considerations may make this case infeasible.
 Hydrogen consumption is not expected to be appreciably dif-
 ferent from the coker case since the feed C/H ratios are not
 greatly different. The direct hydrocracking case is similar
 to the base case (coking - hydrocracking). The utilization
 of energy sources and elimination of the coking operation
 are the major differences.

4.7.4 Process Unit Requirements

Major process units for the two cases are:


	Base Case	A/C. 1
Cokers	2	-
Hydrogen Plants	2	1
Crude Shale	-	2
Hydrocrackers	2	-
Coker Product	2	-
Hydrocrackers	-	1
Naphtha Hydrocracker	-	1

The support facilities for sour water processing and sulfur
 removal are similar to the base case.

Block flow diagrams for the five cases are given in Figures
 4-13, 4-14, 4-15, 4-16, and 4-17.

4.7.4 Product Specifications

The degree of sulfur and nitrogen removal in the hydrocra-
 king operation is affected by coking the crude shale oil.



The extent of sulfur and nitrogen remaining in the two cases is shown below in parts per million by weight.


	<u>Vol.%</u>	<u>PPMWN</u>	<u>PPMWS</u>	<u>Pour[°]F</u>	<u>°API</u>
Base Case					
Coking - H ₂ Treat					
Naphtha	24.0	1	1	-60	58
400-600 [°] F Diesel	45.0	200	20	20	40
600 [°] F + BTMS.	<u>31.0</u>	<u>1000</u>	<u>20</u>	<u>20</u>	<u>35</u>
TOTAL	100.0	405	16	15	42.3
Alternate 1					
H ₂ Treating					
Naphtha	25.0	1	-	-60	58
400-600 [°] F Diesel	30.0	200	50	0	39
600 [°] F + BTMS.	<u>45.0</u>	<u>600</u>	<u>400</u>	<u>100</u>	<u>32</u>
TOTAL	100.0	320	210	50	40.0


The upgraded shale oil is suitable as a refinery feedstock. The absence of 900[°]F plus material will be particularly advantageous to refiners that have problems with "bottom of the barrel" processing.

The extent of sulfur and nitrogen remaining in the two cases is shown below in parts per million by weight.

Base Case	Vol. %	BPMW	PPMWS	Pour P	°API
Coking - H ₂ Treat	24.0	1	1	-60	58
Naphtha	45.0	200	20	20	40
400-600° F Diesel	31.0	1000	20	20	32
600° F + RTMS	100.0	402	16	12	42.3
TOTAL					
Alcane 1					
H ₂ Treating	25.0	1	-	-60	58
Naphtha	30.0	200	20	0	39
400-600° F Diesel	45.0	600	400	100	32
600° F + RTMS	100.0	320	210	20	40.0
TOTAL					

The upgraded shale oil is suitable as a refinery feedstock. The absence of 900° F plus material will be particularly advantageous to refineries that have problems with "bottom of the barrel" processing.





NOTE-1: H₂S INCLUDED IN 105.4 TPSD

NOTE: This Print is the property of
PARAHO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
furnished by us.


PARAHO COMMERCIAL
EVALUATION STUDY

TITLE
BLOCK FLOW DIAGRAM
CASE: ALTERNATE-1

McKEE
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG. 4-14






NOTE: This Print is the property of
PARAHO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
furnished by us.

CLIENT
PARAHO COMMERCIAL
EVALUATION STUDY
TITLE
BLOCK FLOW DIAGRAM
CASE: ALTERNATE-2A
SCALE
S. M. NO.


McKEE
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG. 4-15





This diagram illustrates the waste management process for the mining of oil shale. The process begins with mining, which produces rock waste. This rock waste is then screened and washed, resulting in direct tailings and water. The direct tailings are processed into crude shale oil, while the water is recycled into shale. The recycled shale is then processed into recycled shale oil. The crude shale oil is then sent to waste management, which also receives recycled shale oil and water. The waste management process then produces recycled shale oil and water, which are then used to produce crude shale oil and waste management.



NOTE: This Print is the property of
PARAHO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
furnished by us.

PARAHO COMMERCIAL
EVALUATION STUDY


TITLE
BLOCK FLOW DIAGRAM
CASE: ALTERNATE-2B

SCALE: 3/16" = 1'-0"


McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG. 4-16





NOTE: This diagram is for general information only. It is not intended to be used as a basis for design or construction. The actual layout and dimensions of the system should be determined by a qualified engineer or architect.



NOTE: This Print is the property of PARAO DEVELOPMENT CORPORATION. It must not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.

CLIENT
PARAO COMMERCIAL
EVALUATION STUDY

TITLE
BLOCK FLOW DIAGRAM
CASE: ALTERNATE 2C

SCALE 1" = 100'

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

FIG 4-17





NOTE: This diagram is a simplified representation of the waste management system. It does not show the detailed engineering or the specific equipment used in the process. The diagram is intended to provide a general overview of the system's structure and flow.

SOHIO PETROLEUM COMPANY

DEVELOPMENT TECHNICAL RESPONSE NO. 171

Copies: S. K. Kunchal, E. K. Frazier, R. F. Faubus (2), J. C. Jansma,
J. L. Petersen (3), J. E. Metcalfe, Library

Title: Limited Assay of Crude Shale Oil Produced by Direct Heat Retorting

Project: 2330-02

Requested by S. K. Kunchal

Date: 5/19/76

Author: H. E. Alford

OBJECTIVE:

Conduct a limited assay of crude Shale Oil produced by Direct Heat Retorting. The oil received was labled drum 174 and was collected from tank number 520 on November 29, 1975. It was from Semi-Works Retort Run Number SW-20.

Crude Received:	2/8/76
Partial Assay:	4/1/76
Preliminary Assay:	4/15/76
(missing PNA & O ₂ data)	
Final Limited Assay:	5/19/76

CONCLUSIONS:

There was a considerable amount of water in the sample that caused some difficulty in sampling. The amount of water was not measured.

With some changes made on the mass spectrometer, we were able to obtain hydrocarbon type analyses on all fractions. The crude produced by direct heat retorting is more aromatic and the light fractions are more olefinic than that produced in the indirect heat mode. It is also more aromatic than the shale oil sampled last year (TR #4800, 5/28/75).

Metals were done by atomic adsorption spectroscopy. The results agree well with those obtained last year. The manner of retorting apparently has little effect.

5/19/76

Although crude shale oil produced by direct heat retorting did not form any gas on distillation, it did produce more liquid boiling below 380°F. than that produced by indirect heat retorting or that assayed in 1975.

As before, the nitrogen content was high, and in general, increases with boiling point. Sulfur content decreases with boiling point. The nitrogen content of this crude was slightly lower than that produced by indirect heat retorting.

The elemental analysis balances were good. Oxygen analyses were done by neutron activation.

All of the fractions were highly colored. The color appeared to deepen on standing.

DISCUSSION:

This assay was patterned after the one run a year ago (TR #4800, 5/28/75). It does not include all of the inspections normally obtained in a crude assay. This is by necessity in the case of the naphtha cuts, since only a small amount of light distillate was obtained. It does include an elemental analysis on each of the fractions.

This particular sample of crude shale oil gave us some problems in sampling because of water. We did not determine the water content; Paraho's analysis shows 11.91%. Because of the viscosity and gravity of the crude, this did not settle. Rather, it stayed in pockets and layers in the drum. By sampling carefully, we did obtain enough water-free material for distillation.

With our revamped mass spectrometer, combined with FIA or elution analysis, we were able to obtain hydrocarbon type analysis on all fractions. In addition to reporting the totals, we have also shown a breakdown of the hydrocarbons in each fraction. Naphthene content is reasonably constant over the entire boiling range; aromatics increase with boiling point. Olefins presented a unique problem in FIA separation; they did not fluoresce as they were supposed to. NMR analysis confirmed that the entire non-fluorescent band was olefinic. We believe the values to be correct. The cumulative totals have been plotted.

Originally, oxygen determinations were made using our Perkin-Elmer Model 240 Elemental Analyzer. These values were reported in the Partial Assay of the crude. We then discovered that we were getting interference, probably from sulfur compounds, using this technique. Consequently, oxygen determinations were repeated, using neutron activation. These values are reported in this assay.

NE Alford

HEA/vlm
2/11/76

SOHIO PETROLEUM COMPANY

DTR #171
5/19/76 HEA

CRUDE ASSAY

CRUDE Paraho Shale Oil - Direct Heat Retorting

C.O.P. No. --- TS No. 76-5200-5 Work Requested by S. K. Kunchal
Sample Received 2/8/76 Sample Collected
Source of Sample Paraho Oil Shale Demonstration, Inc.

Table 1 - Properties of Settled Crude

Gravity, °API	21.2	Total Sulfur, Wt. %	0.63
Specific Gravity @ 60°F	0.9267	Total Nitrogen, Wt. %	1.90
Pour Point, °F	80	RVP, lb.	---
Viscosity, SSU		Total Acid No., mg. KOH/gm	1.62
@ 60°F	Too Heavy	Asphaltenes, Wt. % (STM-31)	1.094
@ 100°F	162.9	Ramsbottom Carbon, Wt. %	1.585
VGC	0.8873		
BS & W, Vol. %	0.14	(0.27, vol. % as received unsettled)	
Salt, lb./M Bbls.	0.396	(0.428, lb./M Bbls. as received unsettled)	
Metals, ppm (AA)		Vis. @ 140°F. SSU 71.0	Carbon, Wt. % 84.20
As 20 Ni 2.3		Vis. @ 210°F. SSU 41.3	Hydrogen, Wt. % 11.69
Fe 35.8 V 0.25		Corrosive Sulfur	Oxygen, Wt. % 1.24

Temperature, °F.	Corrosive Sulfur, ppm		
	Hydrogen Sulfide-S	Mercaptan-S	Total
Ambient	---	---	---
Initial- 200	0.5	---	0.5
201 - 300	3.4	---	3.4
301 - 400	26.4	---	26.4
401 - 500	32.9	0.3	33.2
501 - 600	63.6	11.0	74.6
601 - 700	75.8	28.8	104.6
701 - 750	210.2	24.9	235.1
Purge	14.8	7.7	22.5
Total	427.6	72.7	500.3
Total, #/M bbls.	139	24	163

Table 2 - Hempel Distillation (D-235) of Crude

	IBP	186	Inspections on Residue (500+)	
Vol. % Rec. at 95°F			Specific Gravity @ 60°F	0.9478
125°F			Gravity, °API	17.8
165°F			Vix. SSU @ 140°F.	218
200°F	0.3		Vis. SSU @ 210°F	62.1
250°F	0.7		Car. Res., Ramsbottom, wt. %	2.822
300°F	1.3		Sulfur in Coke, Wt. %	
350°F	3.0			
400°F	7.0		Approximate Composition, Vol. %	
450°F	12.5		C ₅ & Ltr. (evap. @ 125)	0
500°F	18.7		125°-400° Naphtha	7.3
Weight of 500+ Residue	230.3		400°-500° Kerosine	11.7
Volume of Residue	243.0		Gas Oil (Res.-Asph.)	66.1
Vol. % Residue	81.0		Asphalt (Calc.)	14.9
Vol. % Loss	0.3		Asphalt Quality "A"	0.9152

DTR #171
5/19/76 HEA

SOHIO PETROLEUM COMPANY

Table 3

Crude Shale Oil - Direct Heat Retorting C.O.P. Number

TBP Distillation of Crude

Cut	°API	Sp. Gr.	Wt. %	Vol. %	Cum. Vol. %
Gas					
55-165					
165-220	52.9	0.7674	0.55	0.66	0.66
220-280	50.5	0.7775	0.10	0.12	0.78
280-340	45.7	0.7985	1.83	2.12	2.90
340-380	39.2	0.8289	1.96	2.19	5.09
380-480	36.1	0.8443	5.95	6.53	11.62
480-520	30.8	0.8718	4.34	4.61	16.23
520-600	28.3	0.8855	6.87	7.19	23.42
600-650	24.6	0.9065	5.53	5.65	29.07
650-700	21.9	0.9224	5.80	5.83	34.90
700-750	20.8	0.9291	5.70	5.69	40.59
750-800	20.6	0.9303	5.48	5.46	46.05
800-850	19.4	0.9377	6.03	5.96	52.01
850-900	16.3	0.9574	16.60	16.07	68.08
900 -Btms.	10.9	0.9937	32.45 33.26*	30.26 31.92*	100.00
Loss			0.81 0	1.66 0	
Total			100.00 100.00	100.00 100.00	

*Corrected for Loss

HEA/vlm
2/11/76

DTR #171
5/19/76 HEA

CRUDE ASSAY - TABLE 4

HYDROCARBON TYPE ANALYSIS BY MS

Crude: Shale Oil - Direct Heat Retorting

Cut Temperature, °F.	Vol. %						
	165-220	220-280	280-340	340-380	380-480	480-520	
Paraffins	26.8	20.3	41.0	40.7	37.3	39.4	
Cycloparaffins							
1 Ring	8.9	8.8	11.0	17.4	15.4	12.8	
2 Ring	0.4	2.0	6.4	7.9	17.5	14.9	
3 Ring							
4 Ring							
5 Ring							
6 Ring							
Total Cycloparaffins	9.3	10.8	17.4	25.3	32.9	27.7	
Aromatics							
Alkyl Benzenes	20.8	23.3	18.0	16.1	7.9	6.3	
Naphthene Benzenes	0.3	0.3	0.6	1.9	9.2	9.1	
Dinaphthene Benzenes							
Naphthalenes		0.1	0.5	0.1	2.1	7.7	
Acenaphthenes, Biphenyls					0.6	1.9	
Acanaphthalenes, Fluorenes					1.6	2.7	
Phenanthrenes, Anthracenes							
Naphthene Phenanthrenes							
Pyrenes							
Chrysenes							
Perylenes							
Dibenzo Anthracenes							
Benzothiophenes					1.6	3.0	
Dibenzothiophenes							
Naphthobenzothiophenes							
Total Aromatics	21.1	23.7	19.1	18.1	23.0	30.7	
Olefins	42.8	45.2	22.5	15.9	6.8	2.2	

HEA/vlm
2/11/76

DTR #171
5/19/76 HEA

CRUDE ASSAY - TABLE 4

HYDROCARBON TYPE ANALYSIS BY MS

Crude: Shale Oil - Direct Heat Retorting

Cut Temperature, °F.	Wt. %							
	520-600	600-650	650-700	700-750	750-800	800-850	850-900	900+
Paraffins	27.4	21.0	20.6	9.4	15.3	5.6	3.1	Ins. Sample
Cycloparaffins								
1 Ring	11.1	10.1	8.3	5.9	7.2	4.9	1.3	
2 Ring	3.1	2.9	2.1	3.2	2.4	8.2	1.6	
3 Ring	1.7	1.6	0.7	3.5	2.2	7.1	7.9	
4 Ring	0.8	0.6		3.4	1.1	4.3	7.8	
5 Ring			0.1	2.6	0.3	1.4	2.0	
6 Ring					0.2	0.9	1.8	
Total Cycloparaffins	16.7	15.2	11.2	18.6	13.4	26.8	22.4	
Aromatics								
Alkyl Benzenes	14.1	15.6	18.1	14.5	20.9	19.3	12.3	29.2
Naphthene Benzenes	11.9	12.0	11.1	8.7	8.8	9.3	8.9	12.8
Dinaphthene Benzenes	9.7	11.5	7.0	11.8	10.8	10.6	11.7	14.6
Naphthalenes	12.4	10.6	9.9	8.7	7.1	7.1	8.4	12.7
Acenaphthenes, Biphenyls	3.0	5.9	7.6	9.1	6.5	5.7	8.4	9.6
Acanaphthalenes, Fluorenes	2.1	4.8	9.7	8.8	6.6	5.4	8.5	8.6
Phenanthrenes, Anthracenes	1.4	2.9	4.0	5.8	5.4	4.6	7.3	5.4
Naphthene Phenanthrenes			0.8	1.2	1.6	1.7	2.9	0.6
Pyrenes		0.1		1.1	1.7	1.8	2.9	0.5
Chrysenes				0.3	0.2	0.5	1.3	0.1
Perylenes							0.1	
Dibenzo Anthracenes								
Benzothiophenes	1.3	0.4		1.7	1.4	1.3	1.0	1.1
Dibenzothiophenes				0.3	0.2	0.2	0.7	1.0
Naphthobenzothiophenes					0.1	0.1	0.1	
Total Aromatics	55.9	63.8	68.2	72.0	71.3	67.6	74.5	96.2

HEA/vlm
2/11/76

DTR #171
5/19/76 HEA

TABLE 5

PROPERTIES OF NAPHTHAS

	<u>165-220</u>	<u>220-280</u>	<u>280-340</u>	<u>340-380</u>
Cum. Mid Vol. %	0.33	0.72	1.84	4.00
Vol. % of Crude	0.66	0.12	2.12	2.19
Cum. Vol. % of Crude	0.66	0.78	2.90	5.09
Gravity, °API	52.9	50.5	45.7	39.2
Specific Gravity @ 60°F.	0.7674	0.7775	0.7985	0.8289
ASTM Dist., D-86, °F.				
IBP	Ins. Samp.	Ins. Samp.	260	300
@ 10% Evap.			297	330
@ 30% Evap.			311	345
@ 50% Evap.			314	356
@ 70% Evap.			318	361
@ 90% Evap.			330	370
EP			354	387
% Rec.			99	99
% Res.			1	1
Total Sulfur, ppm	1.02	1.13	0.96	0.83
Mercaptan Sulfur, Wt. %	xxxx	xxxx	xxxx	102
Total Nitrogen, Wt. %	0.05	0.14	0.74	1.23
UOP "K" Factor	xxxx	xxxx	11.50	11.27
Aniline Point, °F.	xxxx	xxxx	xxxx	85
Cetane Index	xxxx	xxxx	xxxx	287
Smoke Point, mm	xxxx	xxxx	xxxx	16
Pout Point, °F.	xxxx	xxxx	xxxx	f1. @ -50
Freezing Point, °F.	xxxx	xxxx	xxxx	too dark
Paraffins, Vol. %	26.8	20.3	41.0	40.7
Naphthenes, Vol. %	9.3	10.8	17.4	25.3
Aromatics, Vol. %	21.1	23.7	19.1	18.1
Olefins, Vol. %	42.8	45.2	22.5	15.9

TABLE 6
PROPERTIES OF MIDDLE DISTILLATES

	<u>380-480</u>	<u>480-520</u>	<u>520-600</u>	<u>600-650</u>
Cum. Mid Vol. %	8.36	13.93	19.83	26.25
Volume % of Crude	6.53	4.61	7.19	5.65
Cum. Vol. % of Crude	11.62	16.23	23.42	29.07
Gravity, °API	36.1	30.8	28.3	24.6
Specific Gravity @ 60°F.	0.8443	0.8718	0.8855	0.9065
ASTM Dist., D-86, °F.				
IBP	394	460	442	480
@ 10% Evap.	408	480	530	595
@ 30% Evap.	420	492	540	605
@ 50% Evap.	422	498	542	613
@ 70% Evap.	426	504	550	620
@ 90% Evap.	443	517	561	635
EP	462	557	580	660
% Rec.	99	99	99	99
% Res.	1	1	1	1
Vanadium, ppm	xxxx	xxxx	< 0.01	< 0.01
Nickel, ppm	xxxx	xxxx	0.18	0.24
Iron, ppm	xxxx	xxxx	5.4	3.2
Viscosity, CS/100°F.	xxxx	xxxx	5.66	10.17
Viscosity, SSU/100°F.	xxxx	xxxx	44.5	59.4
Viscosity, CS/210°F.	xxxx	xxxx	1.63	2.23
Viscosity, SSU/210°F.	xxxx	xxxx	31.5	33.6
Total Sulfur, Wt. %	0.74	0.82	0.69	0.74
Mercaptan Sulfur, ppm	56.4	60.7	37.9	28.8
Total Nitrogen, Wt. %	0.96	1.27	1.72	1.75
UOP "K" Factor	11.36	11.31	11.30	11.29
Paraffins, Volume %	37.3	39.4	27.4*	21.0*
Naphthenes, Volume %	32.9	27.7	16.7*	15.2*
Aromatics, Volume %	23.0	30.7	55.9*	63.8*
Olefins, Volume %	6.8	2.2	----	----
Aniline Point, °F.	98	99	112	97
Pour Point, °F.	-45	-20	15	35
Freezing Point, °F.	Too dark	too dark	xxxx	xxxx
Thermo Vis. @ 60°F.	too dark	too dark	xxxx	xxxx
Ring Number	too dark	too dark	xxxx	xxxx
Cetane Index	36.5	38.5	40.0	41.9
Smoke Point, mm	15	12	xxxx	xxxx
Diesel Index	35.3	30.4	31.7	23.9
T. Acid No., mg KOH/g.	xxxx	xxxx	1.341	0.790
R. I. @ 140°F.	xxxx	xxxx	too dark	too dark

*Wt. %

DTR #171
5/19/76 HEA

TABLE 7

PROPERTIES OF THE HEAVY DISTILLATES

	650-700	700-750	750-800	800-850	850-900
Cum. Mid Volume %	31.99	37.75	43.32	49.03	60.05
Volume % of Crude	5.83	5.69	5.46	5.96	16.07
Cum. Volume % of Crude	34.90	40.59	46.05	52.01	68.08
Gravity, °API	21.9	20.8	20.6	19.4	16.3
Specific Gravity @ 60°F.	0.9224	0.9291	0.9303	0.9377	0.9574
ASTM Dist., D-1160, °F.					
IBP	625	696	732	773	735
@ 10% Evap.	646	713	756	806	821
@ 30% Evap.	649	721	765	817	847
@ 50% Evap.	652	726	771	822	857
@ 70% Evap.	659	730	778	831	871
@ 90% Evap.	668	737	788	847	894
EP	684	755	812	888	915
% Rec.	98	98	98	98	97
% Res.	2	2	2	2	3
Vanadium, ppm	<0.01	0.01	0.01	0.01	0.05
Nickel, ppm	0.12	0.20	0.31	0.44	0.65
Iron, ppm	3.7	11.3	11.6	13.3	29.5
Viscosity, CS/100°F.	20.60	41.28	70.82	38.82*	87.06*
Viscosity, SSU/100°F.	100.4	192.6	328.5	xxxx	xxxx
Viscosity, CS/210°F.	3.29	4.76	6.50	9.31	15.87
Viscosity, SSU/210°F.	37.1	41.9	47.5	56.8	81.4
Total Sulfur, Wt. %	0.69	0.61	0.58	0.54	0.57
Mercaptan Sulfur, ppm	45.2	70.1	62.7	48.4	60.9
Total Nitrogen, Wt. %	2.02	2.08	2.01	1.74	1.84
UOP "K" Factor	11.23	11.39	11.52	11.59	11.45
Paraffins, Wt. %	20.6	9.4	15.3	5.6	3.1
Naphthenes, Wt. %	11.2	18.6	13.4	26.8	22.4
Aromatics, Wt. %	68.2	72.0	71.3	67.6	74.5
Aniline Point, °F.	106	107	114	128	129
Pour Point, °F.	60	75	90	105	105
Cetane Index	41.4	47.4	51.6	54.2	51.2
T. Acid No., mg KOH/g.	0.488	0.803	0.309	0.112	0.279
R. I. @ 140°F.	too dark	too dark	too dark	too dark	too dark

*Vis. @ 140°F.

TABLE 8

PROPERTIES OF THE RESIDUE

	<u>900+</u>
Volume % of Crude	31.92
Cum. Vol.% of Crude	100.00
Gravity, °API	10.9
Specific Gravity @ 60°F.	0.9937
Abs. Vis. @ 140°F., Poises	22.1
Kin. Vis. @ 140°F., CS	2292
Kin. Vis. @ 210°F., CS	154.4
Vis. @ 210°F., SSU	720
Kin. Vis. @ 275°F., CS	34.3
Furol Vis., @ 275°F., SSF	16.3
Total Sulfur, Wt. %	0.54
Total Nitrogen, Wt. %	2.42
Vanadium, ppm	1.0
Nickel, ppm	8.7
Iron, ppm	126
Insolubles in Pentane, Wt. %	7.44
Paraffins, Wt. %	}
Naphthenes, Wt. %	
Aromatics, Wt. %	
	96.2

TABLE 9

SULFUR BALANCE

<u>Cut</u>	<u>Cut, Wt. % of Crude</u>	<u>Total Sulfur, Wt. %</u>	
		<u>in Cut</u>	<u>in Crude</u>
165 - 220	0.55	1.02	0.0056
220 - 280	0.10	1.13	0.0011
280 - 340	1.83	0.96	0.0176
340 - 380	1.96	0.83	0.0163
380 - 480	5.95	0.74	0.0440
480 - 520	4.34	0.82	0.0356
520 - 600	6.87	0.69	0.0474
600 - 650	5.53	0.74	0.0409
650 - 700	5.80	0.69	0.0400
700 - 750	5.70	0.61	0.0348
750 - 800	5.48	0.58	0.0318
800 - 850	6.03	0.54	0.0326
850 - 900	16.60	0.57	0.0946
900+	33.26	0.54	0.1796
TOTAL	100.00		0.6219
In Whole Crude			0.63

TABLE 10

NITROGEN BALANCE

<u>Cut</u>	<u>Cut, Wt. % of Crude</u>	<u>Total Nitrogen, Wt%</u>	
		<u>in Cut</u>	<u>in Crude</u>
165 - 220	0.55	0.05	0.0003
220 - 280	0.10	0.14	0.0001
280 - 340	1.83	0.74	0.0135
340 - 380	1.96	1.23	0.0241
380 - 480	5.95	0.96	0.0571
480 - 520	4.34	1.27	0.0551
520 - 600	6.87	1.72	0.1182
600 - 650	5.53	1.75	0.0968
650 - 700	5.80	2.02	0.1172
700 - 750	5.70	2.08	0.1186
750 - 800	5.48	2.01	0.1101
800 - 850	6.03	1.74	0.1049
850 - 900	16.60	1.84	0.3054
900+	33.26	2.42	0.8049
TOTAL			1.9263
In Whole Crude			1.90

TABLE 11

OXYGEN BALANCE

<u>Cut</u>	<u>Cut, Wt. % of Crude</u>	<u>Total Oxygen, Wt. %</u>	
		<u>in Cut</u>	<u>in Crude</u>
165 - 220	0.55	0.27	0.0015
220 - 280	0.10	0.28	0.0003
280 - 340	1.83	0.66	0.0121
340 - 380	1.96	1.15	0.0225
380 - 480	5.95	1.28	0.0762
480 - 520	4.34	1.47	0.0638
520 - 600	6.87	1.18	0.0811
600 - 650	5.53	1.32	0.0730
650 - 700	5.80	1.13	0.0655
700 - 750	5.70	1.13	0.0644
750 - 800	5.48	1.07	0.0586
800 - 850	6.03	0.91	0.0549
850 - 900	16.60	0.98	0.1627
900+	33.26	0.95	0.3160
TOTAL			1.0526
In Whole Crude			1.24

DTR #171
5/19/76 HEA

TABLE 12

CARBON-HYDROGEN BALANCE

<u>Cut</u>	<u>Wt. % C</u>	<u>Wt. % H</u>	<u>C/H</u>	<u>H/C Atomic Ratio</u>
165 - 220	84.84	13.61	6.23	1.93
220 - 280	85.60	13.56	6.31	1.90
280 - 340	84.23	13.46	6.26	1.92
340 - 380	83.88	13.18	6.36	1.89
380 - 480	84.49	13.13	6.43	1.87
480 - 520	84.29	12.60	6.69	1.80
520 - 600	84.70	12.57	6.74	1.78
600 - 650	84.47	12.19	6.93	1.73
650 - 700	84.73	11.71	7.24	1.66
700 - 750	84.79	11.79	7.19	1.67
750 - 800	84.77	11.69	7.25	1.66
800 - 850	84.96	11.92	7.13	1.69
850 - 900	85.03	11.55	7.36	1.63
900+	85.29	10.94	7.80	1.54
Wtd. Av.	84.91	11.73	7.24	1.66
In Whole Crude	84.20	11.69	7.20	1.67

DTR #171
5/19/76 HEA

TABLE 13


ELEMENTAL BALANCE

<u>Cut</u>	<u>C</u>	<u>H</u>	<u>S</u>	<u>O</u>	<u>N</u>	<u>Total</u>
165 - 220	84.84	13.61	1.02	0.27	0.05	99.79
220 - 280	85.60	13.56	1.13	0.28	0.14	100.71
280 - 340	84.23	13.46	0.96	0.66	0.74	100.05
340 - 380	83.88	13.18	0.83	1.15	1.23	100.27
380 - 480	84.49	13.13	0.74	1.28	0.96	100.60
480 - 520	84.29	12.60	0.82	1.47	1.27	100.45
520 - 600	84.70	12.57	0.69	1.18	1.72	100.86
600 - 650	84.47	12.19	0.74	1.32	1.75	100.47
650 - 700	84.73	11.71	0.69	1.13	2.02	100.28
700 - 750	84.79	11.79	0.61	1.13	2.08	100.40
750 - 800	84.77	11.69	0.58	1.07	2.01	100.12
800 - 850	84.96	11.92	0.54	0.91	1.74	100.07
850 - 900	85.03	11.55	0.57	0.98	1.84	99.97
900+	85.29	10.94	0.54	0.95	2.42	100.14
Wtd. Av.	84.91	11.73	0.62	1.05	1.93	100.24
In Crude	84.20	11.69	0.63	1.24	1.90	99.66

DTR #171
5/19/76 HEA

Figure 1

TBP DISTILLATION
Crude Shale Oil
Direct Heat Retorting




NO. 319A. MILLIMETER. 200 BY 250 DIVISIONS
GRAPH PAPER
IN STOCK DIRECT FROM CODEX BOOK CO., NORWOOD, MASS. 02062

DTR #171
5/19/76 HBA

Figure 7

DISTILLATE GRAVITY VS. MID VOLUME PER CENT

Crude Shale Oil
Direct Heat Retorting




DTR #171
5/19/76 HEA

Figure 3

DISTILLATE TOTAL SULFUR AND TOTAL NITROGEN VS. MID VOLUME PER CENT

Crude Shale Oil
Direct Heat Retorting



DTR #171
5/19/76 HEA


Figure 4

DISTILLATE "K" FACTOR, ANILINE POINT AND POUR POINT VS.
MID VOLUME PER CENT
Crude Shale Oil
Direct Heat Retorting


IN STOCK DIRECT FROM CODEX BOOK CO., NORWICH, MASS 01901
PRINTED IN U.S.A.

GRAPH PAPER

NO. 319A. MILLIMETER. 200 BY 250 DIVISIONS.



11.5 X 7.0 INCHES
KIEFFEL & ISSER CO



NO. 319A. MILLIMETER, 200 BY 250 DIVISIONS
GRAPH PAPER

IN STOCK DIRECT FROM CODEX BOOK CO., NORWOOD, MASS 01922


CODER
GRAPH PAPER


DPR #171
5/19/76 HEA

Figure 6

COMPOSITION OF SHALE OIL

Direct Heat Retorting





SOHIO PETROLEUM COMPANY

DEVELOPMENT TECHNICAL RESPONSE NO. 172

Copies: S. K. Kunchal, E. K. Frazier, R. F. Paulus (2), J. C. Jansma,
J. L. Petersen (3), J. E. Metcalfe, Library

Title: Limited Assay of Crude Shale Oil Produced by Indirect Heat
Retorting

Project: 2330-03

Requested by: S. K. Kunchal

Date: 5/19/76

Author: H. E. Alford

OBJECTIVE

Conduct a limited assay of Crude Shale Oil produced by Indirect Heat Retorting.

Crude received:	2/17/76
Partial Assay:	4/1/76
Preliminary Assay:	4/15/76
(missing PNA & O ₂ data)	
Final Limited Assay:	5/19/76

CONCLUSIONS

With some changes made on the mass spectrometer, we were able to obtain hydrocarbon type analyses on all fractions. The crude produced by indirect heat retorting is less aromatic and the light fractions are less olefinic than that produced in the direct heat mode.

Metals were done by atomic adsorption spectroscopy. The results agree well with those obtained last year (TR #4800, 5/28/75). The manner of retorting apparently has little effect.

This crude has a slightly greater amount of material boiling below 380°F.; it is slightly less volatile than crude produced by direct heat retorting.

The nitrogen content was high and increased with boiling point. Sulfur content decreased with boiling point. The nitrogen content is slightly higher than that produced by direct heat retorting.

5/19/76

The elemental analysis balances were good. Oxygen analyses were done by neutron activation.

All of the fractions were highly colored. The color appeared to deepen on standing.

Corrosive sulfur content of this crude was higher than that for the crude produced in the direct heat mode.

DISCUSSION

This assay was patterned after the one run a year ago (TR #4800, 5/28/75). It does not include all of the inspections normally obtained in a crude assay. This is by necessity in the case of the naphtha cuts, since only a small amount of light distillate was obtained. It does include an elemental analysis on each of the fractions.

This crude does give some gaseous products on distillation. Overall, there is less light distillate than in the crude shale oil produced in the direct heat mode.

With our revamped mass spectrometer, combined with FIA or elution analysis, we were able to obtain hydrocarbon-type analysis on all fractions. In addition to reporting the totals, we have also shown a breakdown of the hydrocarbons in each fraction. Naphthene content is reasonably constant over the entire boiling range; aromatics increase with boiling point. Olefins presented a unique problem in FIA separation; they did not fluoresce as they were supposed to. NMR analysis confirmed that the entire non-fluorescent band was olefinic. We believe the values to be correct. The cumulative totals are plotted.

Originally, oxygen determinations were made using our Perkin-Elmer Model 240 Elemental Analyzer. These values were reported in the Partial Assay of the crude. We then discovered we were getting interference, probably from sulfur compounds, using this technique. Consequently, oxygen determinations were repeated, using neutron activation. These values are reported in this assay.

H. E. Alford /vr.

HEA/vlm
5/24/76

HEA/vlm
2/11/76

SOHIO PETROLEUM COMPANY

CRUDE ASSAY

CRUDE Paraho Shale Oil - Indirect Heat Retorting

C.O.P. No. --- TS No. 76-05390-5 Work Requested by S. K. Kunchal
Sample Received 2/17/76 Sample Collected ---
Source of Sample Paraho Oil Shale Demonstration, Inc.

Table 1 - Properties of Settled Crude

Gravity, °API	19.1	Total Sulfur, Wt. %	0.62
Specific Gravity @ 60°F	0.9396	Total Nitrogen, Wt. %	2.05
Pour Point, °F	+85	RVP, lb.	---
Viscosity, SSU		Total Acid No., mg. KOH/gm	2.411
@ 60°F	Too Heavy	Asphaltenes, Wt.% (STM-31)	1.051
@ 100°F	241	Ramsbottom Carbon, Wt. %	1.135
VGC	0.8989		
BS & W, Vol. %	0.05	(2.4 , vol.% as received unsettled)	
Salt, lb./M Bbls.	0.774	(1.048 , lb./M Bbls. as received unsettled)	
Metals, ppm (AA)		Vis. @ 140°F. SSU 88.0	Carbon, Wt. % 84.88
As 22	Ni 2.9	Vis. @ 210°F. SSU 45.0	Hydrogen, Wt.% 11.57
Fe 55.0	V 0.33	<u>Corrosive Sulfur</u>	Oxygen, Wt.% 1.28

Temperature, °F.	Corrosive Sulfur, ppm		
	Hydrogen Sulfide-S	Mercaptan-S	Total
Ambient	---	---	---
Initial- 200	0.5	---	0.5
201 - 300	12.0	---	12.0
301 - 400	22.8	---	22.8
401 - 500	44.5	---	44.5
501 - 600	20.5	4.3	24.8
601 - 700	208	25	233
701 - 750	247	31	278
Purge	12.4	6.6	19.0
Total	567.7	66.9	634.6
Total, #/M bbls.	186	22	208

Table 2 - Hempel Distillation (D-285) of Crude

	IBP	178	Inspections on Residue (500+)	
Vol. % Rec. at 95°F			Specific Gravity @ 60°F	0.944
125°F			Gravity, °API	18.4
165°F			Vis. SSU @ 140°F.	244
200°F	1.0		Vis. SSU @ 210°F	65.7
250°F	1.3		Car. Res., Ramsbottom, wt. %	2.921
300°F	1.6		Sulfur in Coke, Wt. %	
350°F	3.0			
400°F	5.0		Approximate Composition, Vol. %	
450°F	8.6		C ₅ & Ltr. (evap. @ 125°)	0
500°F	13.3		125°-400° Naphtha	6.4
Weight of 500+ Residue	243		400°-500° Kerosine	8.3
Volume of Residue	256		Gas Oil (Res.-Asph.)	69.1
Vol. % Residue	85.3		Asphalt (Calc.)	16.2
Vol. % Loss	1.4		Asphalt Quality "A"	0.90

SOHIO PETROLEUM COMPANY

Table 3

Crude Shale Oil-Indirect Heat
Retorting

C.O.P. Number ----

TBP Distillation of Crude

Cut	°API	Sp. Gr.	Wt. %	Vol. %	Cum. Vol. %
Gas		0.5577	0.33	0.56	0.56
55-165			0.00	0.00	0.56
165-220	41.1	0.8198	0.80	0.92	1.48
220-280			0	0	1.48
280-340	39.7	0.8265	0.47	0.54	2.02
340-380	37.9	0.8353	1.12	1.26	3.28
380-480	34.0	0.8550	4.91	5.40	8.68
480-520	30.3	0.8745	3.09	3.32	12.00
520-600	28.4	0.8849	7.65	8.12	20.12
600-650	24.6	0.9065	5.43	5.63	25.75
650-700	22.2	0.9206	6.56	6.70	32.45
700-750	20.5	0.9309	7.10	7.17	39.62
750-800	19.5	0.9371	7.62	7.64	47.26
800-850	17.9	0.9471	10.26	10.18	57.44
850-870	16.6	0.9554	4.26	4.19	61.63
870 + Btms	12.7	0.9813	39.53 40.40*	37.85 38.37*	100.00
Loss			0.87	0.52	
Total			100.00 100.00	100.00	

*corrected for loss

HEA/vlm

2/11/76

DTR #172
5/19/76

CRUDE ASSAY - TABLE 4

HYDROCARBON TYPE ANALYSIS BY MS

Crude: Shale Oil - Indirect Heat Retorting

Cut Temperature, °F.	Vol. %							
	55-165*	165-220	220-280	280-340	340-380	380-480	480-520	
Paraffins	xxxx	12.8	xxxx	28.3	30.3	32.6	43.9	
Cycloparaffins								
1 Ring		6.7		12.2	14.1	8.6	5.3	
2 Ring		0.8		5.1	6.1	10.9	11.1	
3 Ring								
4 Ring								
5 Ring								
6 Ring								
Total Cycloparaffins		7.5		17.3	20.2	19.5	16.4	
Aromatics								
Alkyl Benzenes		58.5		26.3	18.7	12.1	6.4	
Naphthene Benzenes		1.0		1.3	5.2	15.0	9.5	
Dinaphthene Benzenes								
Naphthalenes				0.1	0.6	4.9	9.6	
Acenaphthenes, Biphenyls						1.0	2.9	
Acanaphthalenes, Fluorenes						2.5	4.4	
Phenanthrenes, Anthracenes								
Naphthene Phenanthrenes								
Pyrenes								
Chrysenes								
Perylenes								
Dibenzo Anthracenes								
Benzothiophenes						1.6	2.5	
Dibenzothiophenes								
Naphthobenzothiophenes								
Total Aromatics		59.5		27.7	24.5	37.1	35.3	
Olefins		20.2		26.7	25.0	10.8	4.4	

HYDROCARBON TYPE ANALYSIS BY MS

Crude: Shale Oil - Indirect Heat Retorting

Cut Temperature, °F.	Wt. %							
	520-600	600-650	650-700	700-750	750-800	800-850	850-870	870+
Paraffins	31.4	22.3	22.1	15.5	11.7	23.2	2.0	Ins. Samp.
Cycloparaffins								
1 Ring	10.1	9.1	10.5	9.3	7.1	8.8		
2 Ring	2.9	4.5	2.2	3.7	4.7	2.1		
3 Ring	1.1	3.0	0.5	2.6	2.0	2.2	18.4	
4 Ring	0.9	1.3	0.2	1.0	1.4	1.7	5.4	
5 Ring			0.1	0.4	0.5	0.3	2.2	
6 Ring					0.3	0.2	1.8	
Total Cycloparaffins	15.0	17.9	13.5	17.0	16.0	15.3	27.8	
Aromatics								
Alkyl Benzenes	19.8	16.4	19.1	24.6	18.9	15.8	22.1	41.2
Naphthene Benzenes	8.8	8.7	9.8	10.1	10.2	6.9	9.1	10.3
Dlnaphthene Benzenes	10.0	9.9	8.8	9.2	12.2	8.6	9.8	10.2
Naphthalenes	7.9	6.6	8.3	6.5	8.0	8.4	10.0	13.4
Acenaphthenes, Biphenyls	2.6	6.4	6.5	5.1	6.4	5.8	6.6	5.0
Acanaphthalenes, Fluorenes	1.2	4.1	5.1	5.1	5.9	6.2	6.7	6.1
Phenanthrenes, Anthracenes	1.2	2.9	4.6	4.1	4.9	4.9	4.7	2.8
Naphthene Phenanthrenes		0.4	0.5	0.8	1.5	1.5	0.4	
Pyrenes	0.1	0.8	0.3	0.8	1.7	1.8	0.8	
Chrysenes		0.4	0.3	0.1	0.3	0.5		
Perylenes								
Dibenzo Anthracenes								
Benzothiophenes		2.0	0.5	0.8	1.9	0.9		
Dibenzothiophenes	1.8	1.1	0.6	0.1	0.4	0.2		
Naphthobenzothiophenes	0.2	0.1		0.2				
Total Aromatics	53.6	59.8	64.4	67.5	72.3	61.5	70.2	89.0

TABLE 5
PROPERTIES OF NAPHTHAS

	<u>165-220</u>	<u>280-340</u>	<u>340-380</u>
Cum. Mid Volume %	1.02	1.75	2.65
Vol. % of Crude	0.92	0.54	1.26
Cum. Vol. % of Crude	1.48	2.02	3.28
Gravity, °API	41.1	39.7	37.9
Specific Gravity @ 60°F.	0.8198	0.8265	0.8353
ASTM Dist., D-86, °F.			
IBP	150	Ins. Samp.	342
@ 10% Evap.	206		348
@ 30% Evap.	226		355
@ 50% Evap.	240		360
@ 70% Evap.	252		370
@ 90% Evap.	273		382
EP	293		396
% Rec.	98		99
% Res.	1		1
Total Sulfur, Wt.%	1.43	1.51	1.04
Mercaptan Sulfur, ppm	xxxx	xxxx	Nil
Total Nitrogen, Wt.%	0.18	1.10	1.45
UOP "K" Factor	10.83	xxxx	11.21
Aniline Point, °F.	xxxx	xxxx	78.5
Cetane Index	xxxx	xxxx	27.0
Smoke Point, mm	xxxx	xxxx	14.0
PNA by MS, Vol.%			
Paraffins	12.8	28.2	30.3
Naphthenes	7.5	17.3	20.2
Aromatics	59.5	27.7	24.5
Olefins	20.2	26.7	25.0

DTR #172

5/19/76 HEA

DTR #172
5/19/76 HEA

TABLE 6

PROPERTIES OF MIDDLE DISTILLATES

	<u>380-480</u>	<u>480-520</u>	<u>520-600</u>	<u>600-650</u>
Cum. Mid. Vol. %	5.98	10.34	16.06	22.94
Vol. % of Crude	5.40	3.32	8.12	5.63
Cum. Vol. % of Crude	8.68	12.00	20.12	25.75
Gravity, °API	34.0	30.3	28.4	24.6
Specific Gravity @ 60°F.	0.8550	0.8745	0.8849	0.9065
ASTM Dist., D-86, °F.				
IBP	395	180	502	555
@ 10% Evap.	410	465	530	587
@ 30% Evap.	424	488	538	594
@ 50% Evap.	434	495	543	600
@ 70% Evap.	445	500	550	606
@ 90% Evap.	460	505	562	616
EP	475	514	584	630
% Rec.	99	99	98.5	98
% Res.	1	1	1.5	2
Vanadium, ppm	xxxx	xxxx	0.01	0.01
Nickel, ppm	xxxx	xxxx	0.08	0.08
Iron, ppm	xxxx	xxxx	1.7	0.9
Vis., CS/100°F.	xxxx	xxxx	5.63	10.77
Vis. SSU/100°F.	xxxx	xxxx	44.4	61.5
Vis. CS/210°F.	xxxx	xxxx	1.62	2.31
Vis. SSU/210°F.	xxxx	xxxx	31.5	33.9
Total Sulfur, Wt. %	0.70	0.82	0.67	0.66
Mercap. Sulfur, ppm	102	67.8	88.8	59.5
Total Nitrogen, Wt. %	1.31	1.34	1.57	1.75
UOP "K" Factor	11.27	11.26	11.31	11.25
Paraffins, Vol. %	32.6	43.9	31.4*	22.3*
Naphthenes, Vol. %	19.5	16.4	15.0*	17.9*
Aromatics, Vol. %	37.1	35.3	53.6*	59.8*
Olefins, Vol. %	10.8	4.4	-----	-----
Aniline Point, °F.	86	95	111	103
Pour Point, °F.	fl. @-40	-15	10	40
Freezing Point, °F.	too dark	too dark	xxxx	xxxx
Thermo. Vis. @ 60°F.	too dark	too dark	xxxx	xxxx
Ring Number	too dark	too dark	xxxx	xxxx
Cetane Index	34.4	37.1	40.4	40.4
Smoke Point, mm	15	14	xxxx	xxxx
Diesel Index	29.2	28.8	31.5	25.3
T. Acid No., mg KOH/g.	xxxx	xxxx	3.147	1.388
R. I. @ 140°F.	xxxx	xxxx	too dark	too dark

*Wt. %

TABLE 7

PROPERTIES OF THE HEAVY DISTILLATES

	650-700	700-750	750-800	800-850	850-870
Cum. Mid. Vol. %	29.10	36.04	43.44	52.35	59.54
Vol. % of Crude	6.70	7.17	7.64	10.18	4.19
Cum. Vol. % of Crude	32.45	39.62	47.26	57.44	61.63
Gravity, °API	22.2	20.5	19.5	17.9	16.6
Specific Gravity @ 60°F.	0.9206	0.9309	0.9371	0.9471	0.9554
ASTM Dist., D-1160, °F.					
IBP	600**	691	673	696	650
@ 10% Evap.	633	715	760	800	845
@ 30% Evap.	640	721	771	806	853
@ 50% Evap.	647	723	774	810	859
@ 70% Evap.	653	733	779	814	860
@ 90% Evap.	667	743	790	823	865
EP	678	754	806	835	876
% Rec.	98.5	98	98	98	98
% Res.	1.5	2	2	2	2
Vanadium, ppm	<0.01	0.01	0.01	0.02	0.03
Nickel, ppm	0.08	0.09	0.30	0.44	0.36
Iron, ppm	0.90	2.7	3.1	6.7	19.4
Vis. CS/100°F.	19.75	40.80	25.88*	46.50*	80.98*
Vis. SSU/100°F.	96.8	190.4	xxxx	xxxx	xxxx
Vis. CS/210°F.	3.29	4.77	6.85	10.23	14.54
Vis. SSU/210°F.	37.1	41.9	48.6	60	76.1
Total Sulfur, Wt. %	0.66	0.63	0.59	0.53	0.53
Mercap. Sulfur, ppm	65.6	81.2	70.7	66.0	57.6
Total Nitrogen, Wt. %	1.98	2.08	2.04	1.81	1.90
UOP "K" FACTOR	11.24	11.36	11.45	11.43	11.48
Paraffins, Wt. %	22.1	15.5	11.7	23.2	2.0
Naphthenes, Wt. %	13.5	17.0	16.0	15.3	27.8
Aromatics, Wt. %	64.4	67.5	72.3	61.5	70.2
Aniline Point, °F.	101	100	110	125	116
Pour Point, °F.	55	75	90	95	105
Cetane Index,	41.4	46.5	49.7	50.0	52.0
T. Acid No, mg KOH/g.	0.858	0.457	0.374	0.196	0.059
R. I. @ 140°F.	too dark	too dark	too dark	too dark	too dark

*Vis. @ 140°F.

**D-86 Dist.

TABLE 8

PROPERTIES OF THE RESIDUE

	<u>870+</u>
Vol. % of Crude	38.37
Cum. Vol. % of Crude	100.00
Gravity, °API	12.7
Specific Gravity @ 60°F.	0.9813
Abs. Vis. @ 140°F., poises	14.7
Kin. Vis. @ 140°F., CS	1525
Kin. Vis. @ 210°F., CS	114.3
Vis. @ 210°F., SSU	532
Kin. Vis. @ 275°F., CS	26.9
Furol Vis. @ 275°F., SSF	12.8
Total Sulfur, Wt. %	0.52
Total Nitrogen, Wt. %	2.49
Vanadium, ppm	0.84
Nickel, ppm.	8.8
Iron, ppm	203
Insolubles in Pentane, Wt. %	7.85
Paraffins, Wt. %	} 11.0
Naphthenes, Wt. %	
Aromatics, Wt. %	

DTR #172
5/19/76 HEA

TABLE 9

SULFUR BALANCE

<u>Cut</u>	<u>Cut, Wt.% of Crude</u>	<u>Total Sulfur, Wt. %</u>	
		<u>in Cut</u>	<u>in Crude</u>
165 - 220	0.80	1.43	0.0114
280 - 340	0.47	1.51	0.0071
340 - 380	1.12	1.04	0.0116
380 - 480	4.91	0.70	0.0344
480 - 520	3.09	0.82	0.0253
520 - 600	7.65	0.67	0.0513
600 - 650	5.43	0.66	0.0358
650 - 700	6.56	0.66	0.0433
700 - 750	7.10	0.63	0.0447
750 - 800	7.62	0.59	0.0450
800 - 850	10.26	0.53	0.0544
850 - 870	4.26	0.53	0.0226
870+	40.40	0.52	0.2101
Total	99.67		0.5970
in Whole Crude			0.62

TABLE 10

NITROGEN BALANCE

<u>Cut</u>	<u>Cut, Wt.% of Crude</u>	<u>Total Nitrogen, Wt. %</u>	
		<u>in Cut</u>	<u>in Crude</u>
165 - 220	0.80	0.18	0.0014
280 - 340	0.47	1.10	0.0052
340 - 380	1.12	1.45	0.0162
380 - 480	4.91	1.31	0.0643
480 - 520	3.09	1.34	0.0414
520 - 600	7.65	1.57	0.1201
600 - 650	5.43	1.75	0.0950
650 - 700	6.56	1.98	0.1299
700 - 750	7.10	2.08	0.1477
750 - 800	7.62	2.04	0.1554
800 - 850	10.26	1.81	0.1857
850 - 870	4.26	1.90	0.0809
870+	40.40	2.49	1.0060
Total	99.67		2.0492
in Whole Crude			2.05

DTR #172
5/19/76 HUA

TABLE 11

OXYGEN BALANCE

<u>Cut</u>	<u>Cut, Wt.% of Crude</u>	<u>Oxygen, Wt.%</u>	
		<u>in Cut</u>	<u>in Crude</u>
165 - 220	0.80	0.36	0.0029
280 - 340	0.47	0.55	0.0026
340 - 380	1.12	0.86	0.0096
380 - 480	4.91	1.36	0.0668
480 - 520	3.09	1.17	0.0362
520 - 600	7.65	1.22	0.0933
600 - 650	5.43	1.14	0.0619
650 - 700	6.56	1.16	0.0761
700 - 750	7.10	1.13	0.0802
750 - 800	7.62	1.09	0.0831
800 - 850	10.26	0.92	0.0944
850 - 870	4.26	1.00	0.0426
870+	40.40	0.97	0.3919
	99.67		1.0416
Total			1.28
in Whole Crude			

TABLE 12

CARBON-HYDROGEN BALANCE

<u>Cut</u>	<u>Wt.% C</u>	<u>Wt.% H</u>	<u>C/H</u>	<u>H/C Atomic Ratio</u>
165 - 220	85.97	11.07	7.77	1.55
280 - 340	84.26	12.36	6.82	1.76
340 - 380	83.85	12.52	6.70	1.79
380 - 480	83.86	12.62	6.65	1.81
480 - 520	83.81	12.42	6.75	1.78
520 - 600	84.11	12.37	6.80	1.77
600 - 650	84.08	12.08	6.96	1.73
650 - 700	84.47	11.86	7.12	1.69
700 - 750	84.21	11.62	7.25	1.66
750 - 800	83.76	11.52	7.27	1.65
800 - 850	85.01	11.70	7.27	1.65
850 - 870	85.07	11.58	7.35	1.63
870+	85.39	10.95	7.80	1.54
Wtd. Av.	84.48	11.49	7.35	1.63
In Whole Crude	84.88	11.57	7.34	1.64

DTR #172
5/19/76 HEA

TABLE 13
ELEMENTAL BALANCE

<u>Cut</u>	<u>C</u>	<u>H</u>	<u>O</u>	<u>S</u>	<u>N</u>	<u>Total</u>
165 - 220	85.97	11.07	1.43	0.36	0.18	99.01
380 - 340	84.26	12.36	1.51	0.55	1.10	99.78
340 - 380	83.85	12.52	1.04	0.86	1.45	99.72
380 - 480	83.86	12.62	0.70	1.36	1.31	99.85
480 - 520	83.81	12.42	0.82	1.17	1.34	99.56
520 - 600	84.11	12.37	0.67	1.22	1.57	99.94
600 - 650	84.08	12.08	0.66	1.14	1.75	99.71
650 - 700	84.47	11.86	0.66	1.16	1.98	100.13
700 - 750	84.21	11.62	0.63	1.13	2.08	99.67
750 - 800	83.76	11.52	0.59	1.09	2.04	99.00
800 - 850	85.01	11.70	0.53	0.92	1.81	99.97
850 - 870	85.07	11.58	0.53	1.00	1.90	100.08
870+	85.39	10.95	0.52	0.97	2.49	100.32
Wtd. Av.	84.48	11.49	0.60	1.04	2.05	99.66
In Crude	84.88	11.57	0.62	1.28	2.05	100.40


DIR #172
5/19/76 HEA

Figure 1

TBP DISTILLATION
Crude Shale Oil
Indirect Heat Retorting

CODEX[®] IN STOCK DIRECT FROM CODEX BOOK CO., NORWOOD, MASS. 02062
PRINTED IN U.S.A.
GRAPH PAPER

NO. 319A. MILLIMETER 250 BY 250 DIVISIONS



DTR #172
5/19/76 HHA

Figure 2

DISTILLATE GRAVITY VS. MID VOLUME PER CENT

Crude Shale Oil
Indirect Heat Retorting

NO. 319A. MIL. IN. T.S. 100 BY 250 DIVISIONS
GRAPH PAPER


Specific Gravity @ 60°F.

Specific Gravity @ 60°F.

°AP

10 20 30 40 50 60 70 80 90

Cum. Mid Volume Per Cent




DTR #172
5/19/76 HEA

Figure 3

DISTILLATE TOTAL SULFUR AND TOTAL NITROGEN VS. MID VOLUME PER CENT

Crude Shale Oil
Indirect Heat Retorting




DFR #172
5/19/76 HEA

Figure 4

DESTILLATE "K" FACTOR, ANELINE POINT AND POUR POINT VS. MID VOLUME PER CENT

Crude Shale Oil
Indirect Heat Retorting

NO. 315A, MILLIMETER 2ND BY 2ND DIVISIONS
GRAPH PAPER
PRINTED IN U.S.A.




DTR #172
5/19/76 HEA

Figure 5

DISTILLATE VISCOSITY VS. MID VOLUME PER CENT

Crude Shale Oil
Indirect Heat Retorting



Date: January 20, 1976
 Title: Composition of Shale Oil


DTR #172
 5/19/76 HBA


Figure 6

Composition of Shale Oil

Indirect Heat Retorting

NO. 310A, MILLIFILME 203 BY 230 DIVISION 6
 CODING IN STOCK DIRECT FROM CODEX FOUR CO., NORWOOD, MASS 01962
 GRAPH 100





Date: January 20, 1976

To: Mr. R. E. Styring, Jr.


From: D. J. Curtin

Subject: Characterization of Product Gas from Paraho
Direct-Heated Semi-Works Retort

SAMPLING PROCEDURE

The following procedure was used to obtain wet and dry gas samples and liquid samples from the semi-works retort recycle gas line during Run SW-20, on November 23, 1975.

Gas from the retort was sampled in a 100 ml. gas sample bag. Near the end of the successful Paraho direct-heated semi-works Run SW-20, we obtained samples of the retort product gas, wet and dry ice condensates, and oil products. The sampling procedure and analyses of the gas and condensate samples are attached. Analyses of the condensate samples and oil products are not complete at this time, but the condensates are sufficiently characterized to allow calculation of the retort product gas composition. Tables 1 and 2 show this product gas composition.


D. J. Curtin

DJC:vs

LABORATORY Attachments

Wet Ice Tray Samples

The sample container was chilled to 127°K. The weights of water and hydrocarbon were measured by adding the sample container contents into chilled methanol, separating the phases, and weighing.

The GC-MS curves, an approximate elemental analysis, and the specific gravity of the sample obtained during Run 1 are attached. The sample from Run 2 was lost.

Dry Ice Tray Samples

The sample container from Run 1 was lost and this sample was discarded.


Date: January 30, 1936

To: Mr. E. L. Seyring, Jr.

From: H. J. Curtis

Subject: Characterization of Product Gas from Paraffin
Direct-Heated Semi-Water Heaters

At the end of the successful Paraffin direct-heated semi-water
gas run No. 20, an obtained sample of the retort product gas, was
and dry the condensate, and oil products. The sampling pro-
cedure and analysis of the gas and condensate samples are
attached. Analysis of the condensate samples and oil products
are not complete at this time, but the condensates are sufficiently
characterized to allow calculation of the retort product gas
composition. Tables 1 and 2 show this product gas composition.


H. J. Curtis

Attachment:

PARAHO RETORT GAS ANALYSIS

(Run SW-20 - 11/25/75)

SAMPLING PROCEDURE

The following procedure was used to obtain wet and dry ice trap gas and liquid samples from the semi-works retort recycle gas line during Run SW-20, on November 25, 1975.

Gas from the sample tap located on the blower discharge flowed through wet ice and dry ice traps connected in series. The traps consisted of coils of 5/8" O.D. aluminum tubing, 12 ft. and 10 ft. long, respectively, connected to 6000 c.c. stainless steel sampling containers. The two baths were filled with water-ice, and acetone-dry ice mixtures.

Gas from the dry ice trap was metered in a wet test meter and vented.

Two runs were attempted. Both runs were prematurely terminated because of plugging in the dry ice trap. The dry ice trap gas volume in each case was about 70 SCF. Samples of these streams were obtained:

- Gas from dry ice trap,
- Gas and liquid in dry ice trap,
- Liquid from wet ice trap, and
- Control room gas samples.

LABORATORY PROCEDURE

Wet Ice Trap Naphtha

The sample container was chilled to 32°F. The weights of water and hydrocarbons were measured by withdrawing the sample container contents into chilled receivers, separating the phases, and weighing.

The GC-TBP curve, an approximate component analysis, and the specific gravity of the sample obtained during Run 1 are attached. The sample from Run 2 was lost.

Dry Ice Trap Samples

The sample container from Run 1 had leaked and this sample was discarded.

Dry Ice Trap Samples (continued)

The sample from Run 2 was pressurized with helium to increase the pressure from ~2 psig to about 200 psig to facilitate sample handling. Liquid was withdrawn from the field sampling container (at 24°C) into small sample containers and weighed. The weight balance on the field sample container is attached.

The following analyses were performed:

GC Gas Analyses:

Vapor phase - container #2408

Dry Ice Trap Gas - container #2410

GC Liquid Analyses:

Liquid phase - container #2408

Simulated TBP

Component Analysis

Liquid Density (from container #2408) was measured.

CALCULATION PROCEDURE

Recombination of Dry Ice Trap Samples

The composition and quantity of liquid in the sample container at -108°F and 12 psia was determined by an equilibrium flash calculation at these conditions, using the vapor and liquid contents determined at 24°C. The -108°F liquid was recombined with the dry gas to obtain the vapor composition from the wet ice trap.

Two cases were calculated using:

- (1) The actual weight of liquid removed from the sample container (40.219 gm. liquid).
- (2) The liquid weight calculated from known vapor and liquid densities, container volume, and total sample weight. (50.401 gm. liquid)

All of the components in the naphtha samples were not identified. Molecular weights are needed for the conversion of weight to mole percent. The heavy fraction molecular weights were estimated from the API Data Book correlation (2B2.1). Molecular weights for the lower boiling point unidentified components were estimated from the component's boiling point (which, in turn, was estimated from the retention time in the gas chromatograph). Equilibrium constants for the flash calculation were obtained from the API Data Book.

two dry ice trap cases.

Results

Molal balances and gas compositions for the two cases calculate are shown in the attached tables.

AtlanticRichfieldCompany

TABLE 1

Well Calculation Sheet - Short



Title or object of calculations												
Problem												
Field												
Well												
Date												
References: (BASED ON LIQUID WITHDRAWN FROM FIELD CONTAINER)												
Equation:												
Remarks:												
Column no.	1	2	3	4	5	6	7	8	9	10	11	12
Name	Dry Gas		Dry Ice Trap		Composition		WET ICE TRAP		TOTAL GAS SAMPLE, grams		TOTAL GAS SAMPLE, moles	
Symbol	H ₂		H ₂		H ₂		H ₂		H ₂		H ₂	
Source	H ₂		H ₂		H ₂		H ₂		H ₂		H ₂	
Units	mol		mol		mol		mol		mol		mol	
H ₂	4.42	3.851				3.85101	4.39			3.85101		4.377
O ₂	0.93	.810				.81002	.92			.81002		.921
N ₂	65.07	56.704				56.7055	64.62			56.70550		64.456
C ₁	2.33	2.030				2.0302	2.31			2.03020		2.308
CO	2.01	1.752				1.75222	2.00			1.75222		1.992
CO ₂	22.05	19.215				19.2337	21.92			19.23370		21.752
C ₂	0.93	.810				.81163	.92			.81163		.923
C ₂	0.95	.828				.83164	.95			.83166		.945
C ₃	0.45	.392				.39962	.46			.39962		.454
C ₃	0.47	.410				.41772	.42			.41992		.477
iC ₄	0.06	.052				.05427	.06			.05428		.062
Butene-1	0.16	.139				.16039	.18			.16038		.182
HC ₄	0.27	.078				.10359	.12			.10397		.118
Butene-2	0.62	.017				.02121	.02			.02121		.024
Butene-2	0.01	.009				.01496	.02			.01505		.017
3-MeC ₄	Trace					.00331	.004			.00335		.004
iC ₅	0.01	.009				.01058	.02			.01067		.024
Pentene-1	0.02	.017				.02781	.03			.02781		.032
HC ₅	0.02	.017				.05732	.08			.07503		.085
TransPentene-2						.00479	.005			.00495		.006
CisPentene-2						.00123	.001			.00154		.002
2-MeC ₄						.00541	.006			.00592		.007
C ₆	Trace					.41976	.18			.63634		.723
	100.00	87.143				87.7587	99.996			87.17597		100.001
Calculated Properties												
Hexanes Plus:												
Specific Gravity: 1.00												
Molecular Weight: 96.23												

SIMULATED TBP DISTILLATION BY GC

SAMPLE: MARTHA - WEST FIELD N.B.P.
 TAP: 1
 COLUMN: 2-2-03 OPERATOR:
 DATE: 1-15-76

Table 2

Atlantic Richfield Company

Well Calculation Sheet - Short



Title or object of calculations										N° 86549		
Problem										From	Calculated	
References:										by:		
Equation:										started	finished	
Remarks:										Concurrent sheets		
Column no.	1	2	3	4	5	6	7	8	9	10	11	12
Name	Dry Gas			Dry Ice Trap			Gas Composition			Wet Ice		TOTAL
Symbol	#2410			Calc. Liquid			from Wet Ice			TRAP		GAS SAMPLE
Source	APIB g/mols			Composition			Trap			g/mols		COMPOSITION
Units				g-mols			g-mols					M.L.%
H ₂	4.42	3.851		.00001			.85101	4.39				4.375
O ₂ Ar	0.93	.810		.0002			.8102	.92				.920
N ₂	55.04	56.704		.00044			56.7044	64.57				64.414
C ₁	2.33	2.030		.00017			2.03017	2.31				2.306
CO	2.01	1.752		.00002			1.75202	2.00				1.990
CO ₂	22.05	19.25		.02253			19.2375	21.91				21.853
C ₂	0.93	.810		.00122			.81122	.92				.922
C ₃	0.25	.128		.00246			.23046	.195	.00002			.193
C ₄	0.45	.332		.00417			.39679	.45				.451
C ₅	0.47	.410		.00727			.41027	.48	.00017			.474
i.C ₆	0.06	.052		.01172			.05372	.06	.00001			.061
Butene-1	0.16	.139		.01328			.15228	.17				.173
NC ₄	0.09	.078		.02371			.10171	.12	.00035			.116
Butene-2	0.02	.017		.00261			.01761	.02				.022
C ₁₅	0.01	.009		.00598			.01478	.02	.00009			.017
3MeC ₄ Trap				.00347			.00347	.004	.00004			.004
i.C ₅	0.01	.009		.01184			.02024	.02	.00011			.024
Pentene-1	0.02	.017		.00671			.02371	.03				.027
NC ₅	0.02	.017		.06238			.07438	.07	.00071			.071
Trans-Butene				.00278			.00298	.003	.00016			.004
Cis-Butene				.00077			.00077	.001	.00031			.001
2MeC ₄				.00386			.00336	.004	.00051			.004
C ₆ +	Trace			.19441			.19441	.56	.21658			.308
	100.00	87.143		.67217			87.8129		.21913			100.000
							100.002					
Calculated Properties												
Hexane P16s:												
Specific Gravity 60/60 0.7439												
Molecular Weight 96.23												
0.7991												
134												

AR 78-355-1

WET ICE TRAP NAPHTHA

Run No. 1

Water Recovered 190.53 gm.

Oil Recovered 29.73 gm.

S.G. 60°/60°F 0.7991 (45.6° API)

Dry Ice Trap Gas Volume 73.91 SCF (Dry)

SIMULATED TBP DISTILLATION BY GC

SAMPLE: NAPTHA-WET ICE


N B P:

TRAP- RUN 1

COLUMN: # 2403

OPERATOR:

DATE: 1-15-76



SIMULATED TBP DISTILLATION BY GC
WHOLE OIL

WET ICE TRAP NAPHTHA

SAMPLE: 0055-121390-2403

DATE: 1-15-70

COLUMN: 1/8 x 6 Ft.

STANDARD OF: 1-12-70

OPERATOR: H.E. BOLCOTT

STANDARD ELUTION TIME				PERCENT DIST.		BOILING POINT	
COMP.	TIME	COMP.	TIME	TEMP.	PC.	PC.	B.P.
C4	0.	C32	32.10	100.0	0.05	0.5	150.0
C5	0.55	C33	32.12	150.0	0.37	5.0	222.1
C6	1.18	C34	33.38	200.0	2.39	10.0	253.0
C7	2.55	C35	34.03	250.0	9.35	15.0	263.3
C8	4.30	C36	34.07	300.0	31.01	20.0	280.1
C9	6.24	C37	35.29	350.0	66.90	25.0	287.0
C10	8.14	C38	35.90	400.0	80.08	30.0	298.0
C11	10.01	C39	36.49	450.0	90.06	35.0	304.5
C12	11.80	C40	37.07	500.0	96.09	40.0	309.8
C13	13.20	C41	37.04	550.0	99.75	45.0	321.2
C14	14.58	C42	38.20	600.0	0.	50.0	329.4
C15	15.78	C43	38.15	650.0	0.	55.0	338.7
C16	17.01	C44	39.28	700.0	0.	60.0	343.7
C17	18.22	C45	0.	750.0	0.	65.0	347.5
C18	19.39	C46	0.	800.0	0.	70.0	350.5
C19	20.52	C47	0.	850.0	0.	75.0	371.4
C20	21.61	C48	0.	900.0	0.	80.0	379.3
C21	22.00	C49	0.	950.0	0.	85.0	391.9
C22	23.08	C50	0.	1000.0	0.	90.0	410.2
C23	24.05	C51	0.	1050.0	0.	95.0	441.0
C24	25.59	C52	0.	1100.0	0.	99.0	510.0
C25	26.50	C53	0.	1150.0	0.	99.5	534.8
C26	27.38	C54	0.	1200.0	0.	100.0	571.0
C27	28.22	C55	0.				
C28	29.03	C56	0.				
C29	29.82	C57	0.				
C30	30.58	C58	0.				
C31	31.31	C59	0.				

SIMULATED TBP DISTILLATION BY GC


SAMPLE: *CONDENSATE SAMPLE* N B P:

COLUMN: *WITHDRAWN FROM*
#2408 (DRY ICE TRAP) OPERATOR:

DATE:

(B-48)

Temperature: 24°C



Sample No. 605 B-727390-2408

Weight Balance

Total contents (liquid, vapor, helium)
@ 212 psia, 23.5°C 79.015 gm

Helium added 11.775 gm
@ 212 psia, 23.5°C

Hydrocarbon content 67.240 gm

Liquid, vapor, and helium transferred
to container 2M68
@ 200 psia (calculated value), 24°C 41.349 gm

Vapor and helium transferred to
container B-48
@ 192 psia, 24°C 1.546 gm

Vapor and helium remaining in container No. 2408
@ 192 psia, 24°C 35.992 gm

Total 78.887 gm

Loss 0.128 gm

Calculated Vapor Density @ 0°C, 760 mm Hg
Vapor + Helium: 0.357 g/liter
Vapor (ex. Helium): 1.761 g/liter

Measured Liquid Density:
0.7206 g/cc @ 215 psia, 21.4°C
0.7259 g/cc 60°/60°F @ 215 psia

Sample Container Volumes:
No. 2408 6,071.96 cc
No. 2M68 319.812 cc
No. B-48 305.762 cc

(75.91 SCF - dry basis @ 60 F, 14.7 psia)

(75.91 SCF - dry basis @ 60 F, 14.7 psia)

Run 2

Run 2

GAS CHROMATOGRAPHIC ANALYSIS

SAMPLE NUMBER 605B-127390-2408

DATE 12-24-75

	MOL. WT. PC. FOUND	NORMALIZED		WEIGHT PC	DENSITY LB/CU. FT.
		HE FREE	HE, O2, N2, FREE		
HE	89.31	186.71	88.12	44.38	0.009892
H2	0.50	4.93	0.50	0.14	0.000031
O2	0.07	0.02	0.07	0.28	0.000002
N2	5.03	44.28	4.99	17.48	0.003897
Cl	0.10	1.41	0.10	0.32	0.000071
CO	0.17	1.50	0.17	0.59	0.000132
CO2	2.51	22.10	2.49	13.70	0.003054
C2-	0.12	1.00	0.12	0.42	0.000093
C2	0.15	1.32	0.15	0.50	0.000125
H2S	0.	0.	0.	0.	0.
C3-	0.15	1.32	0.15	0.78	0.000175
C3	0.15	1.32	0.15	0.82	0.000183
I-C4	0.03	0.20	0.03	0.22	0.000048
C4-	0.30	3.17	0.30	2.51	0.000558
N-C4	0.22	1.94	0.22	1.59	0.000354
C4-T	0.07	0.02	0.07	0.49	0.000109
C4-C	0.04	0.35	0.04	0.28	0.000062
C5-	0.02	0.18	0.02	0.17	0.000039
I-C5	0.07	0.02	0.07	0.63	0.000140
C5-	0.18	1.58	0.18	1.57	0.000349
N-C5	0.25	2.20	0.25	2.24	0.000499
C5-T	0.08	0.70	0.08	0.70	0.000155
C5-C	0.02	0.18	0.02	0.17	0.000039
C5-	0.09	0.79	0.09	0.78	0.000175
Co+	0.80	7.57	0.85	9.19	0.002049
TOTAL	100.13	886.71	100.00	100.00	0.022288

Mol. Wt. (ex He) =

1 g mole = 8.003 g

He = 88.72%

$(.8872)(4.003) + .1128x = 8.003$

$.1128x = 4.4515$

$x = \underline{39.464}$

SAMPLE NUMBER 605B-127390-2408

GAS CHROMATOGRAPHIC ANALYSIS

GAS DENSITY AT 32 F AND 14.696 PSIA, LB/CU.FT.	0.0223
GAS DENSITY AT 0 DEG. C AND 760 MM, G/L	0.3570
GAS SPECIFIC GRAVITY, AIR =1	0.2763
AVERAGE MOL WEIGHT OF GAS	8.003
AVERAGE MOL WEIGHT OF HYDROGEN IN GAS	0.313
AVERAGE MOL WEIGHT OF CARBON IN GAS	1.892
WEIGHT PERCENT TOTAL CARBON	23.05
WEIGHT PERCENT ORGANIC CARBON	19.05
WEIGHT PERCENT HYDROGEN	3.91
WEIGHT PERCENT C4+	20.31
SPECIFIC GRAVITY OF LIQUID C4+, 60/60 F	0.3862
DENSITY OF C4+ IN GAS, LBS/CU.FT. AT 32F, 14.696 PSIA	0.2017
DENSITY OF C3 MINUS, LBS/CU.FT. AT 32F, 14.696 PSIA	0.0181
DENSITY OF C3 MINUS, G/L, 0 DEG.C AND 760 MM	0.2904

ANALYST

CHECKED BY

GAS CHROMATOGRAPHIC ANALYSIS

SAMPLE NUMBER 005B-127390-2408

DATE 12-24-75

	MOL. WT. PC.FOUND	HE FREE	NORMALIZED HE, O2, N2, FREE	WEIGHT PC	DENSITY LB/CO. FT.
HE	89.37	0.	0.	0.	0.
H2	0.50	4.93	4.93	0.25	0.000277
O2	0.07	0.62	0.62	0.50	0.000549
N2	5.03	44.28	44.28	31.44	0.034555
Cl	0.10	1.41	1.41	0.57	0.000629
CO	0.17	1.50	1.50	1.00	0.001107
CO2	2.51	22.10	22.10	24.64	0.027083
C2-	0.12	1.00	1.00	0.75	0.000825
C2	0.15	1.32	1.32	1.01	0.001100
H2S	0.	0.	0.	0.	0.
C3-	0.15	1.32	1.32	1.41	0.001548
C3	0.15	1.32	1.32	1.48	0.001621
I-C4	0.03	0.20	0.20	0.39	0.000427
C4-	0.30	3.17	3.17	4.50	0.004952
N-C4	0.22	1.94	1.94	2.65	0.003135
C4-I	0.07	0.62	0.62	0.88	0.000903
C4-C	0.04	0.35	0.35	0.50	0.000550
C5-	0.02	0.18	0.18	0.31	0.000344
I-C5	0.07	0.62	0.62	1.13	0.001238
C5-	0.18	1.58	1.58	2.82	0.003095
N-C5	0.25	2.20	2.20	4.02	0.004422
C5-I	0.08	0.70	0.70	1.25	0.001376
C5-C	0.02	0.18	0.18	0.31	0.000344
C5-	0.09	0.79	0.79	1.41	0.001547
Co+	0.80	7.57	7.57	10.53	0.018109
TOTAL	100.73	100.00	100.00	100.00	0.109923

SAMPLE NUMBER 005B-121390-2400

GAS CHROMATOGRAPHIC ANALYSIS

GAS DENSITY AT 32 F AND 14.690 PSIA, LB/CU.FT.	0.1099
GAS DENSITY AT 0 DEG. C AND 760 MM, G/L	1.7608
GAS SPECIFIC GRAVITY, AIR =1	1.3025
AVERAGE MOL WEIGHT OF GAS	39.461
AVERAGE MOL WEIGHT OF HYDROGEN IN GAS	2.776
AVERAGE MOL WEIGHT OF CARBON IN GAS	16.779
WEIGHT PERCENT TOTAL CARBON	42.51
WEIGHT PERCENT ORGANIC CARBON	35.34
WEIGHT PERCENT HYDROGEN	1.03
WEIGHT PERCENT C4+	30.51
SPECIFIC GRAVITY OF LIQUID C4+, 60/60 F	0.3802
DENSITY OF C4+ IN GAS, LBS/CU.FT. AT 32F, 14.690 PSIA	0.2017
DENSITY OF C3 MINUS, LBS/CU.FT. AT 32F, 14.690 PSIA	0.0809
DENSITY OF C3 MINUS, G/L, 0 DEG.C AND 760 MM	1.3916

ANALYST

CHECKED BY

GAS CHROMATOGRAPHIC ANALYSIS

SAMPLE NUMBER 0055-127390-2410

DATE 12-19-75

	MOL. WT. PC. FOUND	NORMALIZED		WEIGHT PC	DENSITY LB/CO. FI.
		HE FREE	HE + C₂ + C₃ + C₄ + C₅ + C₆ + C₇ + C₈ + C₉ + C₁₀ + C₁₁ + C₁₂ + C₁₃ + C₁₄ + C₁₅ + C₁₆ + C₁₇ + C₁₈ + C₁₉ + C₂₀ + C₂₁ + C₂₂ + C₂₃ + C₂₄ + C₂₅ + C₂₆ + C₂₇ + C₂₈ + C₂₉ + C₃₀ + C₃₁ + C₃₂ + C₃₃ + C₃₄ + C₃₅ + C₃₆ + C₃₇ + C₃₈ + C₃₉ + C₄₀ + C₄₁ + C₄₂ + C₄₃ + C₄₄ + C₄₅ + C₄₆ + C₄₇ + C₄₈ + C₄₉ + C₅₀ + C₅₁ + C₅₂ + C₅₃ + C₅₄ + C₅₅ + C₅₆ + C₅₇ + C₅₈ + C₅₉ + C₆₀ + C₆₁ + C₆₂ + C₆₃ + C₆₄ + C₆₅ + C₆₆ + C₆₇ + C₆₈ + C₆₉ + C₇₀ + C₇₁ + C₇₂ + C₇₃ + C₇₄ + C₇₅ + C₇₆ + C₇₇ + C₇₈ + C₇₉ + C₈₀ + C₈₁ + C₈₂ + C₈₃ + C₈₄ + C₈₅ + C₈₆ + C₈₇ + C₈₈ + C₈₉ + C₉₀ + C₉₁ + C₉₂ + C₉₃ + C₉₄ + C₉₅ + C₉₆ + C₉₇ + C₉₈ + C₉₉ + C₁₀₀		
HE	2.09	0.	0.	0.	0.
H2	4.30	4.42	4.42	0.29	0.000246
O2	0.90	0.93	0.93	0.97	0.000825
N2	03.28	05.00	05.00	59.90	0.050775
C1	2.27	2.33	2.33	1.23	0.001043
C0	1.95	2.00	2.00	1.05	0.001504
CO2	21.45	22.05	22.05	31.89	0.027033
C2-	0.90	0.93	0.93	0.85	0.000723
C2	0.92	0.95	0.95	0.93	0.000792
H2S	0.	0.	0.	0.	0.
C3-	0.44	0.45	0.45	0.63	0.000530
C3	0.46	0.47	0.47	0.69	0.000581
I-C4	0.00	0.00	0.00	0.12	0.000100
C4-	0.10	0.10	0.10	0.30	0.000257
N-C4	0.09	0.09	0.09	0.16	0.000150
C4-I	0.02	0.02	0.02	0.04	0.000032
C4-C	0.01	0.01	0.01	0.02	0.000010
C5-	0.	0.	0.	0.	0.
I-C5	0.01	0.01	0.01	0.02	0.000021
C5-	0.02	0.02	0.02	0.05	0.000040
N-C5	0.02	0.02	0.02	0.05	0.000041
C5-I	0.	0.	0.	0.	0.
C5-C	0.	0.	0.	0.	0.
C5-	0.	0.	0.	0.	0.
C6+	0.	0.	0.	0.	0.
TOTAL	99.95	100.00	100.00	100.00	0.064772

SAMPLE NUMBER 005B-12/390-2410

GAS CHROMATOGRAPHIC ANALYSIS

GAS DENSITY AT 32 F AND 14.696 PSIA, LB/CU.FT.	0.0848
GAS DENSITY AT 0 DEG. C AND 760 MM, G/L	1.3579
GAS SPECIFIC GRAVITY, AIR =1	1.0508
AVERAGE MOL WEIGHT OF GAS	30.437
AVERAGE MOL WEIGHT OF HYDROGEN IN GAS	0.380
AVERAGE MOL WEIGHT OF CARBON IN GAS	4.152
WEIGHT PERCENT TOTAL CARBON	13.64
WEIGHT PERCENT ORGANIC CARBON	4.15
WEIGHT PERCENT HYDROGEN	1.25
WEIGHT PERCENT C4+	0.66
SPECIFIC GRAVITY OF LIQUID C4+, 60/60 F	0.5036
DENSITY OF C4+ IN GAS, LBS/CU.FT. AT 32F, 14.696 PSIA	0.1642
DENSITY OF C3 MINUS, LBS/CU.FT. AT 32F, 14.696 PSIA	0.0845
DENSITY OF C3 MINUS, G/L, 0 DEG.C AND 760 MM	1.3528

ANALYST

CHECKED BY

CHROMATOGRAPH ANALYSIS

Type of Sample: Paraho Project - 25A Run SW20

Method:

Date Run: December 5, 1975

Sample Cyl. No.:

Component	Run #1 (12/5/75)		Run #2 (12/8/75)	
	Mol %	Normalized Less	Mol %	Normalized Less
He	-	-	-	-
H ₂	3.62	3.60	3.64	3.63
O ₂ + AR	0.91	0.91	0.94	0.94
N ₂	64.56	64.27	64.47	64.36
C ₁	2.29	2.28	2.28	2.28
CO	2.41	2.40	2.45	2.45
CO ₂	23.06	22.96	23.07	23.03
C ₂ -	0.92	0.92	0.92	0.92
C ₂	0.87	0.87	0.85	0.85
H ₂ S	0.10	0.10	Trace	Trace
C ₃ -	0.44	0.44	0.43	0.43
C ₃	0.39	0.39	0.27	0.27
1C ₄	0.06	0.06	0.10	0.10
Iso Butylene Butene-1	0.19	0.19	0.18	0.18
NC ₄	0.10	0.10	0.09	0.09
Trans Butene-2	0.02	0.02	0.01	0.01
CIS Butene-2	0.01	0.01	0.01	0.01
³ Methylbutene	Trace	Trace	Trace	Trace
1C ₅	0.01	0.01	0.01	0.01
Pentene-1	0.03	0.03	0.04	0.04
NC ₅ 2-Methylbutene-1	0.04	0.04	0.05	0.05
Trans Pentene-2	Trace	Trace	Trace	Trace
CIS Pentene-2	Trace	Trace	Trace	Trace
² Methylbutene-2	Trace	Trace	0.01	0.01
C ₆ ⁺	0.40	0.40	0.34	0.34
	100.43	100.00 mol %	100.16	100.00

CHROMATOGRAPH ANALYSIS

Type of Sample: Paraho Project

Method: _____

Date Run: December 24, 1975

Sample Cyl. No.: —

Component	605B - 727390-2402		605B - 727290-2408 ✓	
	Mol %	Normalized Less	Mol %	Normalized Less
He	93.08	Helium	89.37	Helium
H ₂	0.19	2.44	0.56	4.93
O ₂ + AR	0.92	11.79	0.07	0.62
N ₂	4.83	61.94	5.03	44.27
C ₁	0.04	0.51	0.16	1.41
CO	0.03	0.38	0.17	1.50
CO ₂	0.53	6.79	2.51	22.09
C ₂ -	0.60	7.69	0.12	1.06
C ₂	0.04	0.51	0.15	1.32
H ₂ S	-	-	-	-
C ₃ -	0.02	0.26	0.15	1.32
C ₃	0.02	0.26	0.15	1.32
1C ₄	Trace	Trace	0.03	0.26
Iso Butylene Butene-1	0.06	0.77	0.36	3.17
NC ₄	0.04	0.51	0.22	1.94
Trans Butene-2	0.01	0.13	0.07	0.62
CIS Butene-2	0.01	0.13	0.04	0.35
³ Methylbutene	Trace	Trace	0.02	0.18
1C ₅	0.01	0.13	0.07	0.62
Pentene-1	0.03	0.38	0.18	1.58
NC ₅ 2-Methylbutene-1	0.04	0.51	0.25	2.20
Trans Pentene-2	Trace	Trace	0.08	0.70
CIS Pentene-2	Trace	Trace	0.02	0.18
² Methylbutene-2	0.01	0.13	0.09	0.79
C ₆ +	0.37	4.74	0.86	7.57
	100.88	100.00	100.73	100.00

CHROMATOGRAPH ANALYSIS

Type of Sample: Paraho Gas

Method: —

Date Run: December 19, 1975

Sample Cyl. No.: —

Component	605B - 727390-2404		605B - 727390-2410 ✓	
	Mol %	Normalized Loss	Mol %	Normalized Loss
He	18.12	Helium	2.69	Helium
H ₂	3.29	4.00	4.30	4.42
O ₂ + AR	1.34	1.63	0.90	0.93
N ₂	53.84	65.41	63.28	65.07
C ₁	1.70	2.06	2.27	2.33
CO	1.62	1.97	1.95	2.01
CO ₂	18.22	22.13	21.45	22.05
C ₂ -	0.76	0.92	0.90	0.93
C ₂	0.68	0.83	0.92	0.95
H ₂ S	-	-	-	-
C ₃ -	0.34	0.41	0.44	0.45
C ₃	0.33	0.40	0.46	0.47
1C ₄	0.06	0.07	0.06	0.06
Iso Butylene Butene-1	0.08	0.10	0.16	0.16
NC ₄	0.04	0.05	0.09	0.09
Trans Butene-2	Trace	Trace	0.02	0.02
CIS Butene-2	Trace	Trace	0.01	0.01
3 Methylbutene	Trace	Trace	Trace	Trace
1C ₅	Trace	Trace	0.01	0.01
Pentene-1	0.01	0.01	0.02	0.02
NC ₅ 2-Methylbutene-1	0.01	0.01	0.02	0.02
Trans Pentene-2				
CIS Pentene-2				
2 Methylbutene-2				
C ₆ +	Trace	Trace	Trace	Trace
	100.44	100.00	99.95	100.00

RUN SW-20

SAMPLE IDENTIFICATION




TABLE OF CONTENTS

	PAGE NO.
PURPOSE AND SCOPE	1-4
SIZE DISTRIBUTION	5
SIZE ANALYSIS	6-10
CRUSHING & SIZING	11
VIEWS OF CRUSHER	12-14
VIEWS OF PRODUCTS	15-18
STANDARD FEEDER BELT CRUSHING TEST	19
INCIDENTS (PACKET ENVELOPE)	

PARAHO DEMONSTRATION PROJECT
EVALUATION STUDY TO DETERMINE PER CENT -1/2"
PRODUCT RESULTING FROM BLASTING &
CRUSHING OIL SHALE TO -3"
+1/2" SIZE

THE CLEVELAND-CLIFFS IRON COMPANY
WESTERN DIVISION
Rifle, Colorado

PAVING INVESTIGATION PROJECT
EVALUATION STUDY TO DETERMINE PER CENT - 1/2"
PROJECT RESULTING FROM PLACING A
CRACKING OIL SEAL TO 3"
+ 1/2" SIZE

THE CLEVELAND-CLIFFS IRON COMPANY
WESTERN DIVISION
BRIEF, Colorado

TABLE OF CONTENTS

PAGE NO.

PURPOSE AND SCOPE - - - - - 1 - 4

SIZE CONSIST CHART - - - - - 5

SIZE CONSIST GRAPH - - - - - 6 -10

CRUSHING & SCREENING FLOW SHEET - - - - - 11

VIEWS OF CRUSHER - - - - - 13-14

VIEWS OF PRODUCTS - - - - - 14-15

STAMLER FEEDER BREAKER CRUSHING TEST - - - - - 16

INSERTS (POCKET ENVELOPE) - - - - -

TABLE OF CONTENTS

PAGE NO.

1 - 8	PURPOSE AND SCOPE
2	SIZE CRIST CRIST
3 - 10	SIZE CRIST CRIST
11	CRISTING & CRISTING FLOW SHEET
12 - 14	VIEWS OF CRIST
14 - 15	VIEWS OF CRIST
16	STAPLER FILER BEATER CRISTING TEST
	INDEXES (Pocket Index)

PARAHO DEMONSTRATION PROJECT

EVALUATION STUDY TO DETERMINE PER CENT OF -1/2" PRODUCT RESULTING FROM BLASTING AND CRUSHING OIL SHALE TO -3" +1/2" SIZE

To prepare the product for this study, a 55' wide, 40' high, 21-1/2' deep round was blasted at the Anvil Points mine using a 23 hole double V cut drill pattern. The holes drilled were 4-1/4" in diameter and were loaded with 1,900 pounds of ammonium nitrate explosives as the primary blasting agent. The round produced approximately 3,100 tons of oil shale with a powder factor of .61 pounds of explosives per ton of product. From the blasted round approximately 500 tons of representative product were separated and stored at the mine, the balance was trucked to the crushing plant for retorting. The approximate 500 tons at the mine were further separated and 98.83 tons were loaded and trucked to the housing area for screening and sizing.

The sizing and weighing of the 98.83 tons of oil shale were done at the housing area with a fixed grizzly fabricated at the Paraho shops. A 12" opening between parallel grizzly rails was used to screen out the +12" product, a 6" opening between parallel grizzly rails was used to screen out the -12" +6" product and a 3" opening between parallel grizzly rails was used to screen out the -6" +3" product and the final -3" product. In conjunction with screening of the mine blast -3" product further hand sorting was required of product sizes larger than 3" in one dimension passing through the parallel grizzly rails with the oversize material going in with the -6" +3" product. Subsequent screening of all products was done over vibrating screens with 6", 3", 1-1/2" and 1/2" square openings.

The +12" product from the commercial blast was loaded and shipped to the Harry T. Campbell & Sons crushing and screening plant in Cockeysville, Maryland, where primary and secondary crushing tests and screening tests were conducted using commercial size equipment similar to that envisioned for future oil shale crushing and screening plants. The tertiary crushing test of the -6" +3" product and the screen sizing of the -3" product was done at the Paraho crushing and screening plant. Due to the difficulty in screening the -6" product to -3" over the fixed grizzly the product was halved and 8.6 tons were screened off for this test.

The primary and secondary crushing tests conducted at Harry T. Campbell's crushing and screening plant were made using a 36" x 60" McLanahan Rockmaster toothed single roll crusher. For the primary crushing tests the crusher opening was set at 6-1/2" and for the secondary crushing test the crusher opening was set at 3-1/2". This crusher was powered by a 440 volt, 200 H.P., 585 rpm Continental motor with a roll speed of 27 rpm and a tip speed of 310 fpm. A recording ammeter was used on both tests and power consumption for primary crushing calculated out to .21 KW per ton at a feed rate of 628 tons per hour. Power consumption for secondary crushing calculated out to .63 KW per ton at a feed rate of 314 tons per hour. From visual observation the 36" x 60" toothed single roll crusher handled the throughput of both the primary and secondary oil shale feed without any difficulty. The Paraho crushing and screening plant was used for both tertiary crushing and screening of the -3" product.

Ro-Tap tests, to determine per cent of -1/2" +3 mesh, -3 mesh +6 mesh, -6 mesh +10 mesh, -10 mesh +28 mesh, -28 mesh +60 mesh, -60 mesh +200 mesh and -200 mesh fines, were conducted at the Paraho laboratory.

These tests were made from samples weighing approximately 60 pounds each of the -1/2" mine blast, primary crushed, secondary crushed, tertiary crushed and -3" products. These results are reported in Table I.

To obtain these samples the grab sampling technique was used and representative samples were taken of the -1/2" mine blast, primary crushed, secondary crushed and -3" products at two foot intervals with a laboratory hand scoop. These samples were placed in five gallon sample pails with proper covers for transportation to the Paraho laboratory.

Included is a table, graphs, flow sheet, views and inserts showing product sizing, mine blast drill pattern and crushing equipment drawings.


Page 5, Table I shows the size consist of the mine blast product, primary crushed product, secondary crushed product, tertiary crushed product and the final -3" product.

Pages 6, 7, 8, 9 and 10 show Graphs I, II, III, IV and V of resultant size distribution of the mine blast product, primary crushed product, secondary crushed product, tertiary crushed product and the final -3" product. The dashed line in Graph I shows the size distribution of mine blast oil shale from a test conducted by the U. S. Bureau of Mines at Anvil Points as reported by Mr. Matzack on page 20 in the Synthetic Fuels Data Handbook prepared by Cameron Engineers. The dashed line in Graph V shows the screen analysis of Paraho retort product showing the cutoff for usable oil shale retort product at 8 mesh. By calculation from this Graph the per cent waste -1/2" product for retorting is reduced from 8.7% to 5%.


Page 11 shows the crushing and screening flow sheet and tonnages passing through the primary, secondary and tertiary crushing stages.

SIZE SEPARATION OF MINE RUN PRODUCT, PRIMARY,
SECONDARY, TERTIARY CRUSHED PRODUCT, AND FINAL
-3" PRODUCT

Size	Mine Run 98.83 Tons		Primary Product 39.53 Tons		Secondary Product 42.52 Tons		Tertiary Product 48.12 Tons		-3" Product 98.83 Tons	
	<u>Tons</u> <u>Passing</u>	<u>%</u> <u>Passing</u>	<u>Tons</u> <u>Passing</u>	<u>%</u> <u>Passing</u>	<u>Tons</u> <u>Passing</u>	<u>%</u> <u>Passing</u>	<u>Tons</u> <u>Passing</u>	<u>%</u> <u>Passing</u>	<u>Tons</u> <u>Passing</u>	<u>%</u> <u>Passing</u>
+48"	98.83	100.00								
+12"	59.30	60.00	39.53	100.00						
+6"	36.47	36.90	19.84	50.19	42.52	100.00				
+3"	19.67	19.90	10.67	26.99	20.37	47.91	48.12	100.00	98.83	100
+1-1/2"	10.78	10.91	4.98	12.60	9.18	21.59	22.86	47.51	47.80	48.8
+1/2"	4.05	4.10	0.95	2.40	1.11	2.61	2.50	5.20	8.61	8.7
+3m	2.57	2.60	0.71	1.80	0.89	2.09	1.35	2.81	5.52	5.6
+6m	2.09	2.11	0.47	1.19	0.60	1.41	0.87	1.81	4.02	4.1
+10m	1.19	1.20	0.28	0.71	0.43	1.01	0.63	1.31	2.53	2.6
+28m	0.40	0.40	0.20	0.51	0.26	0.61	0.48	1.00	1.34	1.4
+60m	0.20	0.20	0.12	0.30	0.13	0.31	0.29	0.60	0.74	0.8
+200m	0.10	0.10	0.04	0.10	0.04	0.09	0.10	0.21	0.28	0.3
PAN	0	0	0	0	0	0	0	0	0	0



SCREEN OPENING^(B)




(A) ANY SCALE, IF IN MILLIMETERS, COINCIDES WITH LOWER SCALE.

(B) SQUARE HOLE IF USED AS CONTINUATION OF FINE SERIES.

Size Distribution After Mine Blast
Cameron — — — CCIC — — —

GRAPH I




(A) ANY SCALE. IF IN MILLIMETERS, COINCIDES WITH LOWER SCALE.

(B) SQUARE HOLE IF USED AS CONTINUATION OF FINE SERIES.

Size Distribution After Primary Crushing

GRAPH II




(A) ANY SCALE. IF IN MILLIMETERS, COINCIDES WITH LOWER SCALE.

(B) SQUARE HOLE IF USED AS CONTINUATION OF FINE SERIES.

Size Distribution After Secondary Crushing

GRAPH III




(A) ANY SCALE, IF IN MILLIMETERS, COINCIDES WITH LOWER SCALE.

(B) SQUARE HOLE IF USED AS CONTINUATION OF FINE SERIES.

Size Distribution After Tertiary Crushing

GRAPH IV




(A) ANY SCALE, IF IN MILLIMETERS, COINCIDES WITH LOWER SCALE.

(B) SQUARE HOLE IF USED AS CONTINUATION OF FINE SERIES.

Comparison of Size Distribution of
Retort Feed to Crushing Test Results

GRAPH V

Crushing Test ———
Retort Feed - - -



The Cleveland Cliffs Iron Company

WESTERN DIVISION



RIFLE, COLORADO 81650

FLWSHEET — CRUSHING AND
SCREENING OF OIL SHALE TO -3"+.5"

SCALE

DRAWN BY H08

REVISED

DATE

APPROVED BY

DRAWING NUMBER

3-3-76

STAMLER FEEDER BREAKER CRUSHING TEST

A Stamler feeder breaker S/N 10932, Model BB-14B-8 mechanical type machine was used to conduct a primary crushing test of +12" mined product at Paraho to determine the per ton power consumption and the amount of -1/2" fines generated with this type of crusher. The conveyor and breaker were driven by two 100 H.P. motors with the relief in both using shear pins. The breaker roll was 34" diameter, comprised of six discs with four picks per disc. The picks were spiraled to even the load on the shaft and the shaft was located so the picks were approximately 4" above the flights. The test with this unit, which was originally designed for crushing trona ore, was not satisfactory as the feeder breaker was a mechanical drive rather than a hydraulic drive resulting in shear pin breakage. Also, three bit holders broke off during this test as the holders were underdesigned for the special breaker used in the test. The fines generated from the Stamler feeder breaker were 7.2% of the total primary product crushed compared to the McLanahan toothed roll crusher of 2.4% of primary product crushed.

SIZE ANALYSIS OF PRODUCT

<u>Screen Size</u>	<u>% Passing</u>	<u>21.1 Tons</u>
+12"	100%	
6"	48.8%	
3"	24.3%	
1/2"	7.2%	

It was not possible to determine the power factor on this test as the motor would stall as soon as any appreciable load was fed through the feeder breaker.

